Kulka.

The Kulka Group
175 F Commerce Dr.
Hauppauge, NY, 11788
(631) 231-0900

Date: 03/06/2025

AVGI

2700 Grand Avenue
Bellmore, NY

Re: 200 Petit Ave

Budget Proposal

The Kulka Group will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$7,007,251**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia

The Kulka Group

Accepted By: _____

Date of Acceptance: _____

Kulka.

Status: Active Estimates
Contact:
Date: 03/06/2025

Estimate: 250032 200 Petit Ave

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
00 No division			
00.0000 No division	$33,698	0.48%	1.75
01 General Requirements			
01.3113 Project Coordination & Permits	$20,000	0.29%	1.04
01.4523 Testing and Monitoring Services	$10,000	0.14%	0.52
01.5000 Temporary Facilities And Controls	$15,000	0.21%	0.78
01.5526 Traffic Control & Signage	$15,000	0.21%	0.78
02 Existing Conditions			
02.1000 Demolition	$116,598	1.66%	6.04
03 Concrete			
03.1000 Concrete	$141,839	2.02%	7.35
03.3370 Concrete Topping	$63,435	0.91%	3.29
04 Masonry			
04.1000 Masonry	$157,572	2.25%	8.16
05 Metal			
05.0050 Structural Steel	$12,725	0.18%	0.66
05.0100 Misc. Steel	$69,038	0.99%	3.58
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$28,960	0.41%	1.50
06.2200 Millwork	$113,037	1.61%	5.85
06.4001 Wood Framing Materials	$381,390	5.44%	19.75
06.4002 Wood Framing Labor	$229,286	3.27%	11.87
06.4300 Wood Stairs And Railings	$2,460	0.04%	0.13
07 Thermal and Moisture Protection			
07.2000 Insulation	$76,225	1.09%	3.95
07.2400 Exterior Insulation & Finish Systems (EIFS)	$197,697	2.82%	10.24
07.3000 Roofing	$284,161	4.06%	14.72
07.7600 Roof Pavers	$72,744	1.04%	3.77
07.9510 Siding	$55,878	0.80%	2.89
08 Openings			
08.1100 HM Doors, Frames & HW	$83,530	1.19%	4.33
08.8200 Arch. Metal & Glass	$449,304	6.41%	23.27
08.8400 Glass Railings	$60,686	0.87%	3.14
09 Finishes			
09.2300 Drywall & Carpentry	$274,821	3.92%	14.23
09.3013 Tile & Stone	$84,193	1.20%	4.36
09.6000 Flooring	$110,017	1.57%	5.70
09.9100 Painting	$101,995	1.46%	5.28
10 Specialties			
10.2800 Bath Accessories/Trash Receptacles	$20,350	0.29%	1.05
10.5110 Package Delivery Lockers	$15,000	0.21%	0.78

Description	Total	Percent of Cost	Cost/SF
10.7313 Marquee/Awnings	$12,143	0.17%	0.63
11 Equipment			
11.3100 Appliances	$80,300	1.15%	4.16
12 Furnishing			
12.3600 Countertops	$35,166	0.50%	1.82
12.9313 Bike Racks	$7,800	0.11%	0.40
14 Conveying System			
14.2000 Elevators	$130,000	1.86%	6.73
21 Fire Suppression			
21.0000 Sprinkler	$139,835	2.00%	7.24
22 Plumbing			
22.0000 Plumbing	$453,390	6.47%	23.48
22.4000 Plumbing Fixtures	$124,630	1.78%	6.45
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$441,896	6.31%	22.88
26 Electrical			
26.0000 Electric	$424,010	6.05%	21.96
26.5000 Lighting Fixtures	$88,229	1.26%	4.57
27 Communications			
27.1000 Tel Data/Low Voltage	$86,895	1.24%	4.50
28 Safety And Security			
28.4600 Fire Alarm	$106,205	1.52%	5.50
31 Sitework			
31.0000 Sitework	$72,922	1.04%	3.78
31.1100 Drainage & Stormwater	$87,041	1.24%	4.51
31.1150 Sewer & Waste	$3,500	0.05%	0.18
31.1200 Water Service	$30,000	0.43%	1.55
32 Exterior Improvements			
32.1200 Repair Asphalt Roadway	$20,352	0.29%	1.05
32.1600 Site Concrete	$35,828	0.51%	1.86
32.1723 Pavement Markings	$2,196	0.03%	0.11
32.1900 Misc. Site Furnishings	$7,000	0.10%	0.36
Sub-Total (Direct Cost)	**$5,685,976**	**81.14%**	**294.46**
Contingency (5%)	$284,299	4.06%	14.72
General Requirements/Conditions	$477,622	6.82%	24.73
Fee	$322,395	4.60%	16.70
Insurance	$236,960	3.38%	12.27
Total Estimate	**$7,007,251**	**100%**	**362.88**

The Kulka Group
175 F Commerce Dr.
Hauppauge, NY, 11788
(631) 231-0900

Notes and Clarifications:

1. **Pricing Validity**: This budget is valid for **thirty (30) calendar days** from the date of issuance.
2. **Scope of Work**: The budget is based on a **white box** finish for both the residential and retail spaces, meaning walls will be primed, utilities will be stubbed, and floors will be left unfinished.
3. **Construction Type**: Pricing assumes **Type V wood-frame construction** with non-union/open shop labor.
4. **Work Hours**: All work is to be performed during **normal working hours**; overtime and after-hours work are excluded.
5. **Permits & Fees**: Permits, filing fees, expediting fees, and DOB filing costs **are not included** unless explicitly stated.
6. **Surveying & Layout**: Any **surveying, stakeouts, and as-built drawings** are excluded unless specifically noted.
7. **Temporary Utilities**: Temporary electric, water, gas, and internet for construction use are **not included**.
8. **Utility Connections**: Permanent connections, tap fees, and meter costs for **gas, water, sewer, and electric** are excluded.
9. **Sitework & Foundations**: Earthwork, dewatering, rock removal, and unforeseen subsurface conditions are excluded. Pricing assumes normal soil conditions.
10. **Retail Space White Box Scope**:
    - Drywall, primed walls, and ceiling
    - HVAC, electrical, and plumbing stubbed to the space
    - No flooring, finishes, or fixtures included
    - Entry storefront system included per base design
11. **Residential Unit White Box Scope**:
    - Framing, drywall, primed walls, and ceiling
    - Rough plumbing, electrical, and mechanical systems in place
    - No kitchens, no bathrooms, no finishes included
12. **MEP (Mechanical, Electrical, Plumbing)**: Rough-ins are included, but no final fixtures or trim-out work.
13. **Fire Protection**: Sprinkler system will be installed per code. **Shop drawings, permits, testing, and sign-off are included**.
14. **Elevator**: Pricing includes one (1) passenger elevator per architectural specifications.
15. **Façade & Envelope**: Assumes **brick veneer & panel system** with aluminum windows per base drawings.
16. **Roofing**: Assumes a **TPO roofing system**, warranty included per manufacturer specifications.
17. **Windows & Doors**: Pricing includes **aluminum windows and storefront system**. No window treatments or interior doors.
18. **Interior Partitions**: No demising walls inside residential units; all walls are assumed to be per fire separation and corridor design.
19. **Insulation & Soundproofing**: Includes **standard insulation per energy code**. Any enhanced soundproofing is excluded.
20. **Stairs & Railings**: Includes **two egress stairwells with code-compliant railings**.
21. **Common Areas**: Lobby and corridors **not included** in white box scope. Any finishes, millwork, or lighting beyond life safety requirements are excluded.
22. **HVAC**: Assumes **PTAC units** for residential spaces and a rooftop unit stubbed for the retail space.
23. **Parking & Sitework**: Any offsite work, sidewalk repairs, street trees, and DOT-related work are excluded.
24. **Exterior Lighting & Signage**: Excludes exterior signage and decorative lighting. Includes **code-required site lighting**.
25. **Sidewalk & ADA Compliance**: Sidewalk curb cuts, ramps, and ADA compliance-related work will be handled per municipal requirements but are excluded from this budget.
26. **Utility Relocation**: Any utility relocations, upgrades, or transformer installations required by the utility provider are excluded.
27. **Structural Requirements**: No major structural modifications or redesigns are included. Pricing assumes standard load-bearing conditions.
28. **Winter Conditions**: Any required **ground thawing, heating blankets, or winter additives for concrete** are excluded.
29. **Exclusions**:
    - No furniture, fixtures, or equipment (FF&E)
    - No appliances, cabinetry, or countertops
    - No security, AV, or access control systems
    - No specialty coatings or decorative treatments
30. **Change Orders & Contingency**: Any scope modifications or unforeseen conditions will be addressed via a formal change order process.