Centrifugal Concrete, LLC
A New Way To Build In New York
228 Frost Street, Brooklyn, NY, 11211
Finale Concrete DBA Centrifugal Concrete

8/4/2025

O+D Builders
26 West 17th ST., Suite 803
New York, NY, 10011
ATTN: Steve Meltzer

Project: 60 Bank St, NEW YORK, NY 10014

Thank you for the opportunity to provide this Proposal for the above-referenced Project. For and in consideration of $1,456,599.00 (One Million Four Hundred Fifty-Six Thousand Five Hundred Ninety-Nine Dollars) we hereby propose the following Scope of Work, for the price and terms listed above and below. Please note anything not specifically included in our scope is specifically excluded.

The proposal is based on the following drawings:
1) Architectural Set- 7.03.2025
2) Structural Set- 7.11.25
3) SOE 7.10.2025

SCOPE of Work:

- **SOE** **$460,393.00**
    - Form and pour Underpinning piers
    - F&I steel wedges and shims
    - Drypack top of piers
    - Pour 400psi concrete
    - F&I all soldier piles
    - Install lagging to subgrade
    - Parge rubble walls
    - Pour grout for soil stabilizing as necessary
    - Install timber posts
    - Forma nd pour Heel Blocks

- F&I Rakers and walers

- **EXCAVATION** **$260,774.00**
  - Excavate and haul material at front yard
  - Excavate and haul material from rear yard
  - Excavate and haul material at cellar to get to subgrade
- **CELLAR SLAB ON GRADE DEMO** **$61,985.00**
  - Demo existing SOG
  - Remove debris
  - Provide dumpsters
- **BASEMENT FLOOR** **$126,358.00**
  - Form and pour 10” elevated slab
  - F&I all reinforcement
  - Provide shop drawings via email
  - Provide engineered form drawings
  - Chop beam pockets for steel framing (multiple floors)
  - In-fill beam pockets post steel installation (multiple floors)
  - Form and pour front stairs
  - Form and pour footings for stairs
- **FOUNDATION** **$137,252.00**
  - Form and pour Wall footings
  - Form and pour foundation walls
  - Form and pour elevator pit slab and walls
  - F&I all reinforcement
  - Provide Shop drawings via email
  - Provide engineered form drawings
  - Form and pour 6” SOG

- F&I 6” gravel subbase and compact
- Form and pour Streab Beam (ST1)
- Install dowels into existing structure using HILTI HY 270

- **WATERPROOFING** **$99,130.00**
  - F&I WR Meadows Pre-Con WP for below slab
  - F&I WR Meadows Blindside WP for vertical walls
  - F&I 2” rigid insulation below slab and walls
  - Install according to manufacturers recommendations
- **STEEL FRAMING/SLAB ON METAL DECK** **$310,707.00**
  - F&I Steel framing cellar to bulkhead
  - Provide shop drawings via email
  - Pour slab on metal decks 1st floor thru bulkhead

Centrifugal Concrete, LLC
A New Way To Build In New York
228 Frost Street, Brooklyn, NY, 11211
Finale Concrete DBA Centrifugal Concrete

Clarification and Exclusions:

1. Anything not listed within our Scope of Work above is specifically excluded.
2. Layout and Mark-outs by others
3. Temp electrical, heat & water by others
4. Sales tax is excluded. Can be waived if Capital Improvement/Tax exempt certificate is provided.
5. Contaminated Soil, Rock removal, mixed materials, buried obstructions, unbalanced site conditions & unforeseen conditions are not included.
6. Site protection and safety fencing is not included.
7. Monitoring, surveying and testing fees are not included.
8. All required DOB permits, including Saturday \work, as well as all safety plans/logistic plans and required sidewalk sheds and staging areas within the street are the responsibility of others and must be provided to us for our use. Permit fees are not included.
9. All personnel will be non-union, and no wage reports will be supplied. All Federal minimum wage requirements will be followed. Overtime work is included.
10. All submittals/shop drawings will be submitted via electronic mail only.
11. Winter protection and any winter conditions are excluded from our price.
12. Insurance to our current limits using our current carriers is included only. No bond is included or available.
13. Payments shall be made as per the 30-day requisition cycle.
14. Retainage of 5% will be reduced to 2.5% at 75% complete. Last 2.5% retainage will be paid upon sign-off.
15. Centrifugal Concrete must be notified of all back charges within 48 hours. Written explanation/clarification must be submitted within 72 hours or Centrifugal Concrete will not be liable.
16. The price is based on normal working hours Monday through Friday.
17. In the event of any strikes, accidents, delays, stop work orders, etc. beyond our control, this agreement is subject to escalation for actual and demonstrably increased cost as a direct result thereof.
18. This proposal shall become part of any contract offered to Centrifugal Concrete.
19. Site demolition and clearing is not included except as indicated above.
20. De-watering and D-mucking is not included.
21. Centrifugal Concrete will not be responsible for Liquidated Damages.

Respectfully Submitted,

Vincent Cannistraci