6460 Metro Plantation Rd.
Fort Myers, FL 33966
239-337-DEMO

Admin@RedlineDemolition.com
www.RedlineDemolition.com

To: Roc Construction Group

Re: 649-663 5th Ave S. Naples FL (5th Ave Demo)

Date: 03/31/2025

Thank you for the opportunity to quote the above referenced project. Redline Demolition Services, Inc. offers the following for your consideration:

Scope of Work: Selective Demolition

1. Remove and dispose of **+/- 1,802 LF** of interior walls as per drawing **D2.0 and D3.0.**
2. Remove and dispose of **+/- 293 LF** of exterior walls as per drawing **D2.0 and D3.0.**
3. Remove and dispose of **+/- 261 LF** of metal tube railing as per drawing **D2.0 and D3.0.**
4. Remove and dispose of **+/- 13 LF** of PVC fencing as per drawing **D2.0.**
5. Remove and dispose of **+/- 15,570 SF** of flooring as per drawing **D2.0 and 3.0.**
6. Remove and dispose of **+/- 17,952 SF** of ceilings and finishes as per drawing **D2.0 and 3.0.**
7. Remove and dispose of **+/- 646 SF** of wood plank drop ceiling and 2x framing as per drawing **D3.0.**
8. Remove and dispose of **+/- 315 SF** of fabric canopy as per drawing **D3.0.**
9. Remove and dispose of **14** windows and casing as per drawing **D2.0 and D3.0.**
10. Remove and dispose of **3** doors and casing as per drawing **D2.0.**
11. Remove and dispose of **13** electrical panels as per drawing **D2.0.**
12. Remove and dispose of **19** HVAC equipment as per drawings **D2.0 and D4.0.**
13. Remove and dispose of **14** plumbing fixtures and **2** cabinets as per drawing **D2.0.**
14. Remove and dispose of **2** exterior signage as per drawing **D5.0.**
15. Remove and dispose of **+/- 7 LF** of display case as per drawing **D2.0.**
16. Remove and dispose of **+/- 6 LF** of wall pad as per drawing **D3.0.**
17. Remove and dispose of **5** gutters and downspout as per drawing **D5.1.**
18. Remove and dispose of **1** staircase as per drawing **D2.0.**
19. **Exclusions**:
    a. Elevator removal as per drawing **D2.0 Note #11.**
    b. Removal of roof finish as per drawing **D6.0.**

Clarifications

- Disposal by Redline Demolition Services, Inc.
- All mechanical, electrical, or plumbing disconnects performed by others.
- Layout by others prior to work commencement

Base Bid: $126,916.38

Terms: Progressive Payments and 100% Due Upon Completion

6460 Metro Plantation Rd.
Fort Myers, FL 33966
239-337-DEMO

Admin@RedlineDemolition.com
www.RedlineDemolition.com

Qualifications / Clarifications / Assumptions:

A. Redline Demolition Services, Inc., is not responsible for unforeseen damaged utilities, landscape, irrigation, or driveways.
B. Redline Demolition Services, Inc., shall have the rights to any / all salvageable materials.
C. Fire alarm / fire sprinkler system test mode enabled by others prior to work commencement.
D. All mechanical, electrical, or plumbing disconnects performed by others.
E. Notes not indicated above will not be a part of Redline Demolition's scope.
F. Proposal valid for 90 days contingent on strikes, accidents, or delays beyond our control.
G. Work to be performed during standard business hours.
H. This price is based on NO RETAINAGE being withheld from contract price.

Standard Exclusions:

A. Payment and performance bond.
B. Asbestos detection / survey / removal.
C. 10 Day notice to FDEP.
D. Hazardous material detection / removal.
E. Underground / foundation removal.
F. Layouts required for penetrations or concrete cutting.
G. Scanning and/or x-ray of slabs or walls.
H. Core drilling for MEP unless identified in scope listed above.
I. Silt fence and/or temporary barricades unless identified in scope listed above.
J. Utility locates, disconnects, and/or utility usage charges.

Insurance and Safety Considerations:

A. Supervision will be provided by Redline Demolition Services, Inc. for maintaining safe working conditions on jobsite and in accordance with current OSHA standards.
B. Any additional protections or safety standards imposed by Project Owner associated with additional costs to be added to contract price above.
C. Redline Demolition Services, Inc. shall furnish appropriate Liability and Worker's Compensation insurance.

Acceptance of Proposal – The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

Signature: _____ **Date:** _____

Printed Name: _____