VALLEY MECHANICAL SERVICES INC.

HEATING AND COOLING

(845) 353-0972

WC-16041-H05 RC-1374

PROPOSAL

April 29, 2025

The Angel
18 South Broadway
Nyack, NY 10960

Thank you for considering Valley Mechanical Services Inc. for your Heating, Air Conditioning and Energy Solutions. We are pleased to provide you with the following proposal. Below you will find the scope of work required, equipment and design, warranty information and pricing, based on the characteristics of the project.

SCOPE OF WORK

As per plans received on 4-15-24 Revision # 2 Dated March 01 2024
M-000,M-101,M-102,M-103,M–201,M-202,M-203,M-204,-204,M-206. M-301,M401

We will supply and install the following:
Phase 1 Sanctuary

- Mitsubishi Diamond system builder piping diagram
- Supply and Install Mitsubishi systems (2) PUHY-HP192TSNS
- Supply and Install Mitsubishi indoor units (6) PVFY-P54NAMU-E1
- Supply and Install all thermostats and controllers
- Supply and Install all ERV's (3) LGH-F1200RVX1
- Supply and Install all ductwork
- Supply and Install all duct insulation
- Supply and Install all registers, grilles and diffusers
- Supply and Install all refrigeration piping
- Supply and Install all roof curbs and equipment rails
- Supply and Install and fire dampers
- Supply and Install all electric heaters
- All condensate drains
- Crane and rigging of new units
- Sealing of all ductwork and fittings
- Duct pressure check with report
- Air balancing with report
- Start up and commissioning of new equipment

PRICING ,TERMS AND CONDITIONS: All equipment, materials necessary to perform scope of work, labor, permits (when applicable) and sales tax are included in the pricing. Pricing is in effect for (30) days from date of proposal. All agreements contingent upon weather,strikes,accidents or delays beyond our control. Warranties on equipment will not be registered until final payment has been received in full.

Total Investment : $ 274,041.00

Project Specific notes and Clarifications:

1. Pricing is based on open shop labor
2. Temporary cooling not included
3. Power wiring not included
4. Structural Steel supports under roof not included if required
5. Roof sealing
6. Building permits fees to be billed separately
7. Fire Stopping and fire proofing by others
8. Tax Exempt

WARRANTY

- Valley Mechanical Services Inc. Warranty: Work to be completed to the industry's highest standards and will include a one-year workmanship warranty on the new system and components..

Thank you for putting your trust in Valley Mechanical Services Inc. . Our goal is to provide you with peace of mind, and an exceptional customer experience. Please do not hesitate to contact me with any questions or concerns you may have regarding your project.

Sincerely,
James N. Bencivengo
Managing Partner
Valley Mechanical Services Inc.
M# 845.548.7470
Jamesb@valleymechanicalservices.com

AGREEMENT TO COMPLETE PROPOSED WORK

Client Signature _____ *Date* _____

Please return the signed contract in its entirety via fax or email to (845)267-8562 or office@valleymechanicalservices.com

Valley Mechanical Services _____ *Date* ___*4/29/25*____