Clipper Construction
1644 Beason St, Suite 201
Baltimore, MD, 21230
(443) 323-1880

Date: 11/11/2025

Christophe Richard
Toki Underground

Re: 3224 Greenmount Ave

Budget Proposal

Clipper Construction hereby proposes all materials, labor and supervision in accordance with drawings dated 06/10/2025 for the sum of **$810,830**

Attachments:
Schedule of Values

Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia

Clipper Construction

Accepted By: _____

Date of Acceptance: _____

Status: Active Estimates
Contact:
Date: 11/11/2025

Estimate: 250156 3224 Greenmount Ave

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
02 Existing Conditions			
02.1000 Demolition	$35,192	4.34%	17.64
03 Concrete			
03.1000 Concrete	$19,216	2.37%	9.63
04 Masonry			
04.1000 Masonry	$16,045	1.98%	8.04
04.5710 Brick	$4,374	0.54%	2.19
05 Metal			
05.0050 Structural Steel	$2,510	0.31%	1.26
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$18,696	2.31%	9.37
06.2200 Millwork	$38,451	4.74%	19.27
06.4001 Wood Framing Materials	$16,737	2.06%	8.39
06.4002 Wood Framing Labor	$27,327	3.37%	13.70
07 Thermal and Moisture Protection			
07.2000 Insulation	$15,352	1.89%	7.70
07.3000 Roofing	$2,900	0.36%	1.45
08 Openings			
08.1100 Doors, Frames & HW	$10,090	1.24%	5.06
08.3000 Eliason Door	$1,700	0.21%	0.85
08.5000 Windows	$1,700	0.21%	0.85
08.8200 Arch. Metal & Glass	$3,300	0.41%	1.65
08.8300 Mirrors	$41,176	5.08%	20.64
09 Finishes			
09.2300 Drywall	$28,728	3.54%	14.40
09.2500 Acoustical Ceilings	$4,599	0.57%	2.31
09.3013 Tile & Stone	$10,147	1.25%	5.09
09.6000 Flooring	$170	0.02%	0.09
09.6400 Wood Flooring	$21,107	2.60%	10.58
09.9100 Painting	$34,386	4.24%	17.24
10 Specialties			
10.1400 Signage	$0	0.00%	0.00
10.2600 Wall And Door Protection	$4,472	0.55%	2.24
10.2800 Bath Accessories	$3,615	0.45%	1.81
10.5110 Lockers	$1,950	0.24%	0.98
10.7313 Awnings	$2,403	0.30%	1.20
12 Furnishing			
12.3600 Countertops	$17,502	2.16%	8.77
22 Plumbing			
22.0000 Plumbing	$90,939	11.22%	45.58
22.4000 Plumbing Fixtures	$3,850	0.47%	1.93

Description	Total	Percent of Cost	Cost/SF
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$61,475	7.58%	30.81
26 Electrical			
26.0000 Electric	$53,165	6.56%	26.65
26.5000 Lighting Fixtures	$17,829	2.20%	8.94
27 Communications			
27.1000 Tel/Data	$5,686	0.70%	2.85
27.1020 Audio Visual	$8,213	1.01%	4.12
28 Safety And Security			
28.4600 Fire Alarm	$7,250	0.89%	3.63
28.4610 Security	$5,985	0.74%	3.00
31 Sitework			
31.0000 Earthwork	$11,300	1.39%	5.66
31.1100 Footing Drains (Not Shown)	$0	0.00%	0.00
31.4100 Shoring	$12,317	1.52%	6.17
Sub-Total (Direct Cost)	**$661,851**	**81.63%**	**331.75**
General Conditions	$99,278	12.24%	49.76
Fee	$45,668	5.63%	22.89
Insurance	$4,034	0.50%	2.02
Total Estimate	**$810,830**	**100%**	**406.43**

Estimate: 250156 3224 Greenmount Ave

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**02 Existing Conditions**			
2	**02.1000 Demolition**			
3	Remove Existing Roll-Down Gates	14.82 LF	16.00	237.12
4	Remove Awning	29.56 SF	6.00	177.36
5	Remove Exterior Storefront	48.77 LF	55.00	2,682.35
6	Remove Concrete Ramp	192.07 SF	10.00	1,920.70
7	Remove Deteriorated Steel Pipe Columns	10.00 EA	120.00	1,200.00
8	Remove Existing Floor Framing	1,121.54 SF	3.50	3,925.39
9	Remove Termite Damaged 3-1/4x7-1/4 Wood Beams	195.82 LF	5.00	979.10
10	Remove Existing Concrete Slab & Footings	1,031.77 SF	16.00	16,508.32
11	Remove Interior Partitions	241.27 LF	18.00	4,342.86
12	Remove Floor Tile	29.38 SF	3.50	102.83
13	Remove GWB Ceilings	1,777.21 SF	1.50	2,665.82
14	Remove Plumbing Fixtures	2.00 EA	75.00	150.00
15	Remove Doors & Frames	4.00 EA	75.00	300.00
16			**Demolition Total**	**$35,191.85**
17			**Existing Conditions Total**	**$35,191.85**
18	**03 Concrete**			
19	**03.1000 Concrete**			
20	F/I 2in Topping Slab	410.55 SF	8.00	3,284.40
21	Make Repairs to Existing Sidewalk	1.00 LS	1,500.00	1,500.00
22	Form & Pour Concrete Footings	0.87 CY	1,600.00	1,392.00
23	Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.	13.69 CY	575.00	7,871.75
24	Concrete Pumps	2.00 EA	1,800.00	3,600.00
25	F/I Concrete Fill Over Steel Decking (Installed by Steel Sub)	2.09 CY	750.00	1,567.50
26			**Concrete Total**	**$19,215.65**
27			**Concrete Total**	**$19,215.65**
28	**04 Masonry**			
29	**04.1000 Masonry**			
30	F/I CMU Block [8"x8"x16"]	106.02 BLOCK	32.00	3,392.64
31	F/I Glass Block Walls w/Horizontal & Vertical Rods [8"x8"x4"]	187.54 BLOCK	60.00	11,252.40
32	Create Beam Pocket	4.00 EA	350.00	1,400.00
33			**Masonry Total**	**$16,045.04**
34	**04.5710 Brick**			
35	F/I Brick Veneer (Full-Height)	149.90 SF	24.00	3,597.60
36	F/I Brick Veneer Above & Below Glass Block	32.36 SF	24.00	776.64
37			**Brick Total**	**$4,374.24**
38			**Masonry Total**	**$20,419.28**
39	**05 Metal**			
40	**05.0050 Structural Steel**			

Line	Description	Quantity	Unit Cost	Total
41	F/I 3in 20 Ga, Steel Decking	104.57 SF	24.00	2,509.68
42			**Structural Steel Total**	**$2,509.68**
43			**Metal Total**	**$2,509.68**
44	**06 Wood , Plastic and Composites**			
45	**06.2000 Finish Carpentry**			
46	F/I Wainscotting	142.66 SF	28.00	3,994.48
47	F/I Trim @ Vertical Columns	68.61 SF	20.00	1,372.20
48	F/I Faux Beams @ Bar Area	67.80 LF	70.00	4,746.00
49	I/O Pocket Door	1.00 EA	360.00	360.00
50	I/O Window Hardware & Screen(s)	2.00 EA	35.00	70.00
51	I/O Interior Door Hardware	1.00 EA	50.00	50.00
52	F/I Base Molding [Solid White Oak]	594.33 LF	13.00	7,726.29
53	F/I Window Casing [Solid White Oak]	29.00 LF	13.00	377.00
54			**Finish Carpentry Total**	**$18,695.97**
55	**06.2200 Millwork**			
56	F/I Open Shelving (Solid Stain-Grade Wood + Nosing & Routed Channel for Lights)	25.66 LF	250.00	6,415.00
57	F/I Steel Integrated Foot Rail @ Bar	39.47 LF	130.00	5,131.10
58	F/I Bar Die Wall (Plywood w/Stain-Grade White Oak Trim & Upholstered Panel)	37.96 LF	195.00	7,402.20
59	F/I CNC Open Wood Screen @ Entry	39.50 SF	115.00	4,542.50
60	F/I Lower Cabinets @ Back Bar	29.92 LF	500.00	14,960.00
61			**Millwork Total**	**$38,450.80**
62	**06.4001 Wood Framing Materials**			
63	F/O 2x4 PT	394.41 LF	1.90	747.80
64	F/O 2x4 DF	788.82 LF	1.63	1,287.36
65	F/O 2x4 Studs	2,933.40 LF	1.61	4,716.90
66	F/O 2x6 PT	119.02 LF	2.29	272.79
67	F/O 2x6 DF	220.06 LF	1.85	406.67
68	F/O 2x6 Studs	847.84 LF	1.85	1,566.81
69	F/O 2x8 DF	8.36 LF	1.99	16.64
70	F/O 2x10 DF	526.50 LF	4.10	2,160.76
71	F/O 1-3/4" x 9-1/4" LVL	61.12 LF	8.63	527.34
72	F/O 1-3/4" x 11-7/8" LVL	64.54 LF	8.66	559.17
73	F/O 4x8x3/4" TG Advantech Plywood	306.11 SF	2.15	658.68
74	F/O 4'x8'x1/2" Zip Sheathing	217.51 SF	1.65	359.92
75	F/O 11-7/8" Pro 560 TJI	229.58 LF	14.93	3,427.17
76	F/O Termite shield (6" x 25' Aluminum Roll)	20.14 LF	0.85	17.15
77	F/O FormSealR 5-1/2" x 50' Sill Seal	20.14 LF	0.60	12.00
78			**Wood Framing Materials Total**	**$16,737.16**
79	**06.4002 Wood Framing Labor**			
80	I/O Headers	66.78 LF	15.00	1,001.70

Line	Description	Quantity	Unit Cost	Total
81	I/O Vertical Column Framing @ Bar Area	10.00 EA	250.00	2,500.00
82	I/O Wood Blocking for Accessories, Equipment & Millwork	1.00 LS	1,500.00	1,500.00
83	I/O Interior Framed Wall	4,770.36 SF	3.00	14,311.08
84	I/O 2x10 Sistering	1,052.99 SF	4.50	4,738.46
85	I/O Floor Framing (Joists & Subfloor)	306.11 SF	5.00	1,530.55
86	I/O Exterior Wall Framing & Sheathing @ 1st Floor	217.51 SF	4.50	978.80
87	I/O Window(s) (Standard Sizes)	2.00 EA	200.00	400.00
88	I/O LVL/PSL Beams	30.56 LF	12.00	366.72
89			**Wood Framing Labor Total**	**$27,327.31**
90			**Wood , Plastic and Composites Total**	**$101,211.24**
91	**07 Thermal and Moisture Protection**			
92	**07.2000 Insulation**			
93	F/I R-20 Spray Foam Insulation @ Entry Slab	109.45 SF	10.00	1,094.50
94	F/I Insulation & Air Seal @ Window(s)/Exterior Door(s)	2.00 EA	25.00	50.00
95	F/I Rockwool Sound Insulation @ PT-3 Walls	1,230.64 SF	1.75	2,153.62
96	F/I R-13 Batt Insulation @ PT-5 Walls	3,042.79 SF	1.50	4,564.19
97	F/I R-13 Batt Insulation @ PT-4 Walls	973.96 SF	1.51	1,470.68
98	F/I R-19 Fiberglass Batt	217.51 SF	1.51	328.44
99	F/I R-49 Spray-Foam Insulation @ Roof	650.35 SF	8.75	5,690.56
100			**Insulation Total**	**$15,351.99**
101	**07.3000 Roofing**			
102	F/I Flashing for Penetrations/Pipes/Exhaust Fans	2.00 EA	650.00	1,300.00
103	F/I Flashing for RTU	1.00 EA	1,600.00	1,600.00
104			**Roofing Total**	**$2,900.00**
105			**Thermal and Moisture Protection Total**	**$18,251.99**
106	**08 Openings**			
107	**08.1100 Doors, Frames & HW**			
108	F/O HM Frame (Single)	6.00 EA	365.00	2,190.00
109	F/O Pocket Door with Kit	1.00 EA	850.00	850.00
110	F/O Pocket Door Hardware	1.00 EA	500.00	500.00
111	F/O Solid-Core Wood Door	5.00 EA	550.00	2,750.00
112	F/O Solid-Core Wood Door + Vision Lite	1.00 EA	800.00	800.00
113	F/O Door Hardware (Commercial Interior)	6.00 EA	500.00	3,000.00
114			**Doors, Frames & HW Total**	**$10,090.00**
115	**08.3000 Eliason Door**			
116	F/I Eliason Swinging Door	1.00 EA	1,700.00	1,700.00
117			**Eliason Door Total**	**$1,700.00**
118	**08.5000 Windows**			
119	F/O W1 Window [Andersen 400 (Assumed)]	1.00 EA	700.00	700.00
120	F/O W2 Window [Andersen 400 (Assumed)]	1.00 EA	1,000.00	1,000.00
121			**Windows Total**	**$1,700.00**

Line	Description	Quantity	Unit Cost	Total
122	**08.8200 Arch. Metal & Glass**			
123	F/I Door Type A [Single Swing Full-Light Exterior]	1.00 EA	3,300.00	3,300.00
124			**Arch. Metal & Glass Total**	**$3,300.00**
125	**08.8300 Mirrors**			
126	F/I Mirrors @ Bar & Seating Area Ceilings	614.56 SF	67.00	41,175.52
127			**Mirrors Total**	**$41,175.52**
128			**Openings Total**	**$57,965.52**
129	**09 Finishes**			
130	**09.2300 Drywall**			
131	F/I 1/2" GWB Walls (Level 4 Finish)	7,149.00 SF	3.00	21,447.00
132	F/I 1/2" GWB Ceilings (Level 4 Finish)	680.00 SF	2.45	1,666.00
133	F/I 1/2" GWB Ceilings (Level 4 Finish)	1,321.66 SF	3.00	3,964.98
134	I/O Interior HM Door, Frame & HW (Single)	6.00 EA	275.00	1,650.00
135			**Drywall Total**	**$28,727.98**
136	**09.2500 Acoustical Ceilings**			
137	F/I TECTUM Direct-Attach Ceiling	309.83 SF	14.84	4,598.65
138			**Acoustical Ceilings Total**	**$4,598.65**
139	**09.3013 Tile & Stone**			
140	F/I Quarry Floor Tile @ Kitchen Prep	90.17 SF	9.59	864.46
141	F/I Quarry Floor Tile @ Bar	203.36 SF	9.59	1,949.61
142	F/I Quarry Floor Tile @ Storage	305.71 SF	9.38	2,867.56
143	F/I Quarry Tile Base	114.61 LF	10.38	1,189.08
144	F/I Porecelain Floor Tile at Bathrooms ($7/SF Material Allowance)	120.63 SF	24.05	2,901.15
145	F/I Saddle/Threshold(s)	3.00 EA	125.00	375.00
146			**Tile & Stone Total**	**$10,146.86**
147	**09.6000 Flooring**			
148	F/I Tile->Wood Transition Strip	5.68 LF	30.00	170.40
149			**Flooring Total**	**$170.40**
150	**09.6400 Wood Flooring**			
151	F/I Engineered Wood Flooring ($13/SF Material Allowance)	981.71 SF	21.50	21,106.77
152			**Wood Flooring Total**	**$21,106.77**
153	**09.9100 Painting**			
154	Paint/Stain Wainscotting & Vertical Columns	211.26 SF	5.00	1,056.30
155	Paint Existing Siding @ Rear Facade	154.41 SF	5.00	772.05
156	Paint GWB Walls (Limewash Finish)	6,971.91 SF	3.25	22,658.71
157	Paint Existing GWB Walls	521.76 SF	1.30	678.29
158	Paint Base Molding	594.33 LF	3.50	2,080.16
159	Paint GWB Ceilings	3,360.76 SF	1.30	4,368.99
160	Paint/Stain Wood Doors & Casing	1.00 EA	225.00	225.00
161	Paint/Stain Wood Door + HM Frame (Single)	6.00 EA	225.00	1,350.00
162	Paint Window Casing	29.00 LF	5.00	145.00

Line	Description	Quantity	Unit Cost	Total
163	Paint New & Existing Brick @ Front & Rear Facades	420.52 SF	2.50	1,051.30
164			**Painting Total**	**$34,385.80**
165			**Finishes Total**	**$99,136.46**
166	**10 Specialties**			
167	**10.1400 Signage**			
168	F/I "Tomboy" Signage	1.00 EA	0.00	0.00
169			**Signage Total**	**$0.00**
170	**10.2600 Wall And Door Protection**			
171	Marlite FRP 4'x8' Panels (Light Gray P151)	605.66 SF	2.01	1,227.38
172	Marlite 8' FRP Divider	110.21 LF	0.49	52.80
173	Marlite 8' FRP Inside Corner	4.00 EA	3.30	13.20
174	Marlite 8' FRP Outside Corner	1.00 EA	3.30	3.30
175	Marlite 8' FRP End Cap	2.00 EA	3.30	6.60
176	FRP Adhesive	605.66 SF	0.24	140.00
177	Install FRP Panels	605.66 SF	5.00	3,028.30
178			**Wall And Door Protection Total**	**$4,471.58**
179	**10.2800 Bath Accessories**			
180	F/O Toilet Paper Holder [No Spec]	3.00 EA	175.00	525.00
181	F/I Electric Hand Dryers (Excel XL-BW-ECO White]	3.00 EA	675.00	2,025.00
182	F/I Soap Dispenser [Lavex 712LSD40V]	3.00 EA	85.00	255.00
183	F/I Mirror [Bobrick 179B292836 SS]	3.00 EA	270.00	810.00
184			**Bath Accessories Total**	**$3,615.00**
185	**10.5110 Lockers**			
186	F/I Employee Lockers w/Coat Rack Above	3.00 EA	650.00	1,950.00
187			**Lockers Total**	**$1,950.00**
188	**10.7313 Awnings**			
189	F/I New Awning	16.02 LF	150.00	2,403.00
190			**Awnings Total**	**$2,403.00**
191			**Specialties Total**	**$12,439.58**
192	**12 Furnishing**			
193	**12.3600 Countertops**			
194	Template, Fabricate & Install 3cm Quartz Countertop @ Back Bar ($75/SF Material Allowance)	45.78 SF	145.00	6,638.10
195	Template, Fabricate & Install Zinc Countertop @ Bar	77.60 SF	140.00	10,864.00
196			**Countertops Total**	**$17,502.10**
197			**Furnishing Total**	**$17,502.10**
198	**22 Plumbing**			
199	**22.0000 Plumbing**			
200	Make Gas Connection to RTU-1	1.00 EA	650.00	650.00
201	F/I 1-1/4" Gas Piping (Vertical)	11.00 LF	40.00	440.00
202	F/I CP-2025-1 Domestic Hot Water Circulator Pump	1.00 EA	1,350.00	1,350.00

Line	Description	Quantity	Unit Cost	Total
203	F/I FWH-1 Exterior Wall Hydrant	1.00 EA	600.00	600.00
204	F/I TWH-1 Electric Water Heater	1.00 EA	1,250.00	1,250.00
205	Make Connections to K-1 Dishwasher	1.00 EA	750.00	750.00
206	I/O 3-Compartment Sink	1.00 EA	1,200.00	1,200.00
207	Make Connections to K-11 Ice Machine	1.00 EA	900.00	900.00
208	Make Connections to K-14 3-Compartment Sink & Faucet	1.00 EA	1,850.00	1,850.00
209	Make Connections to K-4 Cocktail Station	1.00 EA	1,150.00	1,150.00
210	Make Connections to K-4 3-Bowl Underbar Sink & Faucet	1.00 EA	1,250.00	1,250.00
211	Make Connections to K-12/K13 Hand Sink & Faucet	1.00 EA	950.00	950.00
212	F/I TMV-1 Thermostatic Mixing Valve [Leonard ECO-MIX XL-32A-LF-BDT-LF ASSE 1017]	1.00 EA	1,650.00	1,650.00
213	Disconnect Existing Plumbing Fixtures	2.00 EA	150.00	300.00
214	I/O Commercial Toilet	3.00 EA	1,250.00	3,750.00
215	I/O Bath Lav (Sink) & Faucet	3.00 EA	1,050.00	3,150.00
216	F/I FD-1 Floor Drain	4.00 EA	950.00	3,800.00
217	Make Connnections to K-15 Mop Sink	1.00 EA	1,200.00	1,200.00
218	F/I FS-1 Floor Sink	3.00 EA	1,250.00	3,750.00
219	F/I WH-1 Domestic Hot Water Heater [AO Smith PMI-5 48 Gallon]	1.00 EA	3,000.00	3,000.00
220	F/I 2" Vent Piping	17.41 LF	26.00	452.66
221	F/I 3" Vent Piping	99.98 LF	35.00	3,499.30
222	F/I 1-1/4" Gas Line	76.08 LF	35.00	2,662.80
223	F/I 1" Gas Line	3.25 LF	32.00	104.00
224	F/I 4" Sanitary Line	182.96 LF	40.00	7,318.40
225	F/I Automatic Grease Interceptor	1.00 EA	8,791.52	8,791.52
226	F/I 1/2" HWR Piping	108.70 LF	22.00	2,391.40
227	F/I 2" Vent Piping (Vertical)	165.00 LF	34.00	5,610.00
228	F/I CW/HW Piping (Vertical)	250.00 LF	23.00	5,750.00
229	F/I 2" HW Piping	137.19 LF	50.00	6,859.50
230	F/I 2" CW Piping	180.30 LF	50.00	9,015.00
231	F/I Sanitary Piping (Vertical)	132.00 LF	42.00	5,544.00
232			**Plumbing Total**	**$90,938.58**
233	**22.4000 Plumbing Fixtures**			
234	F/O Faucet [T&S 510B2701VR SS]	3.00 EA	225.00	675.00
235	Sink [American Standard Decorum 20" 9024001EC.020 White]	3.00 EA	225.00	675.00
236	Toilet [Kohler Highline Classic K-3493-SS-0 White]	3.00 EA	550.00	1,650.00
237	F/O Mop Sink	1.00 EA	850.00	850.00
238			**Plumbing Fixtures Total**	**$3,850.00**
239			**Plumbing Total**	**$94,788.58**
240	**23 Heating, Ventilating and Air-Conditioning**			
241	**23.0000 HVAC**			
242	F/I EF-1 Exhaust Fan @ ADA Restroom (50 CFM)	1.00 EA	1,200.00	1,200.00

Line	Description	Quantity	Unit Cost	Total
243	F/I EF-2 Exhaust Fan @ Restroom(s) (75 CFM)	1.00 EA	1,300.00	1,300.00
244	F/I EF-3 Exhaust Fan @ Kitchen Prep (150 CRM)	1.00 EA	1,600.00	1,600.00
245	F/I EF-4 Exhaust Fan @ Hallway L2 (70 CFM)	1.00 EA	1,200.00	1,200.00
246	F/I EF-5 Exhaust Fan @ Bathroom L2 (75 CFM)	1.00 EA	1,300.00	1,300.00
247	F/I EWH-1 Electric Unit Heater @ Hallway (5kW) [Berko FRC-1512F]	1.00 EA	1,400.00	1,400.00
248	F/I EWH-2 Electric Unit Heater @ Entry (5kW) [Berko FRC-1512F]	1.00 EA	1,400.00	1,400.00
249	F/I EUH-1 Electric Unit Heater @ Basement/Crawlspace (10kW) [Berko HUHAA320]	1.00 EA	1,800.00	1,800.00
250	F/I DH-2025-1 Dehumidifier @ Crawlspace (Back) [Aprilaire Model #050]	1.00 EA	2,000.00	2,000.00
251	F/I DH-2025-2 Dehumidifier @ Crawlspace (Front) [Aprilaire Model #050]	1.00 EA	2,000.00	2,000.00
252	F/I Ductwork & Diffusers	1,378.00 SF	14.00	19,292.00
253	Provide Shop Drawings	1.00 EA	2,500.00	2,500.00
254	F/I Duct Smoke Detector	2.00 EA	500.00	1,000.00
255	F/I RTU-1 (8.5 Ton)	1.00 EA	22,100.00	22,100.00
256	F/I Condensate Piping	4.82 LF	38.00	183.16
257	Provide Air Balancing & Certified Report	1.00 EA	1,200.00	1,200.00
258			**HVAC Total**	**$61,475.16**
259			**Heating, Ventilating and Air-Conditioning Total**	**$61,475.16**
260	**26 Electrical**			
261	**26.0000 Electric**			
262	Wire EQP-11 Ice Machine	1.00 EA	575.00	575.00
263	Wire EQP-0 Induction Range	1.00 EA	550.00	550.00
264	Wire EQP-17 Walk-In Beer Cooler	1.00 EA	850.00	850.00
265	Wire P-2 Hot Water Heater	1.00 EA	850.00	850.00
266	F/I Panel "K" (225A, 120/208V, 3Ø, 4W) + Feeders	1.00 EA	8,500.00	8,500.00
267	F/I CT Cabinet/Meter Combo	1.00 EA	3,200.00	3,200.00
268	F/I Grounding	1.00 EA	2,250.00	2,250.00
269	Wire P-1 Automatic Grease Recovery Unit	1.00 EA	650.00	650.00
270	Wire EQP-1 UC Glass Washer	1.00 EA	525.00	525.00
271	Wire Electric Unit Heaters	3.00 EA	425.00	1,275.00
272	Wire EQP-18 AC Beverage Glycol System	1.00 EA	650.00	650.00
273	Wire CP-2025-1 Domestic Hot Water Circulator Pump	1.00 EA	325.00	325.00
274	Wire WH-1 Hot Water Heater	1.00 EA	550.00	550.00
275	F/I TV Outlet	1.00 EA	175.00	175.00
276	F/I Duplex Receptacle	15.00 EA	175.00	2,625.00
277	F/I Dedicated Duplex Receptacle	21.00 EA	175.00	3,675.00
278	F/I Quad Receptacle	1.00 EA	235.00	235.00
279	F/I Ceiling-Mount Duplex	1.00 EA	250.00	250.00
280	Wire Hand Dryers	3.00 EA	330.00	990.00
281	Wire RTU + WP Service Duplex	1.00 EA	2,400.00	2,400.00
282	Wire Exhaust Fans	5.00 EA	650.00	3,250.00

Line	Description	Quantity	Unit Cost	Total
283	I/O Lighting Fixture	69.00 EA	175.00	12,075.00
284	I/O Exit Sign	5.00 EA	175.00	875.00
285	F/I Single-Pole Switch	6.00 EA	140.00	840.00
286	F/I LED Dimmer Switch	16.00 EA	150.00	2,400.00
287	F/I Wall-Mounted Occupancy Sensor (OC)	3.00 EA	125.00	375.00
288	Electrical Disconnects Prior to Demo	1.00 EA	1,700.00	1,700.00
289	F/I Junction Box	2.00 EA	275.00	550.00
290			**Electric Total**	**$53,165.00**
291	**26.5000 Lighting Fixtures**			
292	F/O Track For C-Type Fixtures	12.21 LF	20.00	244.20
293	F/O E-Type Fixtures	8.00 EA	295.00	2,360.00
294	F/O C-Type Fixtures	10.00 EA	140.00	1,400.00
295	F/O D Type Fixtures	5.00 EA	260.00	1,300.00
296	F/O K-Type Fixtures (6'3")	4.00 EA	210.00	840.00
297	F/O A-Type Fixture (9')	1.00 EA	285.00	285.00
298	F/O G-Type Fixtures	31.00 EA	240.00	7,440.00
299	F/O Unspecified Fixture	2.00 EA	195.00	390.00
300	F/O B-Type Fixtures	2.00 EA	325.00	650.00
301	F/O H-Type Fixture (4')	1.00 EA	420.00	420.00
302	F/O F-Type Fixtures	5.00 EA	340.00	1,700.00
303	Exit Sign	5.00 EA	160.00	800.00
304			**Lighting Fixtures Total**	**$17,829.20**
305			**Electrical Total**	**$70,994.20**
306	**27 Communications**			
307	**27.1000 Tel/Data**			
308	Data Budget (Per SF)	1,995.00 SF	2.85	5,685.75
309			**Tel/Data Total**	**$5,685.75**
310	**27.1020 Audio Visual**			
311	Audio/Visual Budget (Per SF)	1,095.00 SF	7.50	8,212.50
312			**Audio Visual Total**	**$8,212.50**
313			**Communications Total**	**$13,898.25**
314	**28 Safety And Security**			
315	**28.4600 Fire Alarm**			
316	Duct Detector Tie-In	2.00 EA	325.00	650.00
317	Fire Alarm Control Tie-Ins	1.00 EA	1,850.00	1,850.00
318	F/I Smoke Detector	1.00 EA	150.00	150.00
319	Fire Alarm Control Panel	1.00 EA	2,500.00	2,500.00
320	F/I Horn/Strobe	6.00 EA	350.00	2,100.00
321			**Fire Alarm Total**	**$7,250.00**
322	**28.4610 Security**			
323	Security Budget (Per SF)	1,995.00 EA	3.00	5,985.00

Line	Description	Quantity	Unit Cost	Total
324			**Security Total**	**$5,985.00**
325			**Safety And Security Total**	**$13,235.00**
326	**31 Sitework**			
327	**31.0000 Earthwork**			
328	Moblization, Setup, Layout & Control	1.00 EA	850.00	850.00
329	Excavate to Subgrade	1,026.00 SF	3.00	3,078.00
330	Export Excess Fill	25.30 CY	50.00	1,265.00
331	Proofroll & Subgrade Compaction	1.00 LS	500.00	500.00
332	Backfill Foundation	1,062.00 SF	2.50	2,655.00
333	F/I Crushed Stone	25.67 CY	115.00	2,952.05
334			**Earthwork Total**	**$11,300.05**
335	**31.1100 Footing Drains (Not Shown)**			
336	F/I 4" Footing Drain (Not Shown)	0.00 LF	22.00	0.00
337			**Footing Drains (Not Shown) Total**	**$0.00**
338	**31.4100 Shoring**			
339	Provide Shoring as Needed at Cellar	1,449.00 SF	8.50	12,316.50
340			**Shoring Total**	**$12,316.50**
341			**Sitework Total**	**$23,616.55**
342	**Sub-Total (Base Cost)**			**$661,851.09**

Estimate Summary



Material [$62,429]
Labor [$292]
SubContractor [$590,653]
Equipment [$0]
Other [$8,478]

Description		Total
Sub-Total (Base Cost)		$661,851.09
Sub-Total (Direct Cost)		$661,851.09
General Conditions	15.0000%	99,277.66
Fee	6.0000%	45,667.73
Insurance	0.5000%	4,033.98
Total Estimate		$810,830.46

Clipper Construction
1644 Beason St, Suite 201
Baltimore, MD, 21230
(443) 323-1880

Notes and Clarifications:

1. Pricing is to be used for budgetary purposes only.
2. Hazardous material testing and abatement are not included.
3. Underpinning, shoring, or structural bracing are not included.
4. Dewatering or groundwater control is not included.
5. Remediation of unsuitable soils is not included.
6. Rock hammering is not included.
7. Protection, relocation, or repair of existing utilities is not included.
8. Permits, fees, inspections, and testing are not included.
9. Surveying, layout, and engineering are not included.
10. Restoration of finishes, flooring, or walls is not included.
11. Winter conditions, heating, and tenting are not included
12. After-hours or weekend work is not included.