Clipper Construction
1644 Beason St, Suite 201
Baltimore, MD, 21230
(443) 323-1880

Date: 08/19/2025

Al Tasker
Eagle Therapy
250 W Chase Street
Baltimore, MD 21201

Re: Eagle Therapy

Budget Proposal

Clipper Construction hereby proposes all materials, labor and supervision in accordance with drawings dated 07/28/2025 for the sum of **$1,607,485**

Attachments:
Schedule of Values

Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia

Clipper Construction

Accepted By: _____

Date of Acceptance: _____

Estimate: 250123 Eagle Therapy

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
02 Existing Conditions			
02.1000 Demolition	$40,703	2.53%	3.82
03 Concrete			
03.1000 Concrete	$6,535	0.41%	0.61
03.1500 Concrete Cutting	$21,694	1.35%	2.04
04 Masonry			
04.1000 Masonry	$25,000	1.56%	2.35
05 Metal			
05.0050 Structural Steel	$8,800	0.55%	0.83
05.7610 Lintels	$7,572	0.47%	0.71
06 Wood , Plastic and Composites			
06.2200 Millwork	$29,905	1.86%	2.81
07 Thermal and Moisture Protection			
07.3000 Roofing	$6,000	0.37%	0.56
08 Openings			
08.1100 HM Doors, Frames & HW	$42,840	2.67%	4.02
08.8200 Arch. Metal & Glass	$74,554	4.64%	6.99
09 Finishes			
09.2300 Drywall & Carpentry	$246,874	15.36%	23.16
09.2500 Acoustical Ceilings	$94,883	5.90%	8.90
09.3013 Tile & Stone	$47,180	2.94%	4.43
09.6000 Flooring	$82,392	5.13%	7.73
09.9100 Painting	$13,322	0.83%	1.25
10 Specialties			
10.1123 Whiteboards	$800	0.05%	0.08
10.1400 Signage	$7,500	0.47%	0.70
10.2800 Bath Accessories	$5,400	0.34%	0.51
10.2900 Toilet Partitions	$19,500	1.21%	1.83
10.4400 Fire Protection Specialties	$2,800	0.17%	0.26
10.5110 Storage Lockers	$2,550	0.16%	0.24
11 Equipment			
11.3100 Appliances	$6,450	0.40%	0.61
21 Fire Suppression			
21.0000 Sprinkler	$52,125	3.24%	4.89
22 Plumbing			
22.0000 Plumbing	$61,700	3.84%	5.79
22.4000 Plumbing Fixtures	$16,875	1.05%	1.58
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$232,100	14.44%	21.77
26 Electrical			
26.0000 Electric	$140,635	8.75%	13.19

Description	Total	Percent of Cost	Cost/SF
26.5000 Lighting Fixtures	$25,285	1.57%	2.37
27 Communications			
27.1000 Tel/Data	$13,050	0.81%	1.22
28 Safety And Security			
28.4600 Fire Alarm	$36,100	2.25%	3.39
28.4610 Low-Voltage/Cameras	$25,000	1.56%	2.35
Sub-Total (Direct Cost)	**$1,396,123**	**86.85%**	**130.97**
General Conditions	$111,690	6.95%	10.48
Overhead	$30,156	1.88%	2.83
Fee	$61,519	3.83%	5.77
Insurance	$7,997	0.50%	0.75
Total Estimate	**$1,607,485**	**100%**	**150.80**

Estimate: 250123 Eagle Therapy

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**02 Existing Conditions**			
2	**02.1000 Demolition**			
3	Remove Interior OH Door	1.00 EA	250.00	250.00
4	Remove Interior Partitions	209.24 LF	18.00	3,766.32
5	Remove Millwork	139.76 LF	25.00	3,494.00
6	Remove Floor Tile	70.42 SF	3.50	246.47
7	Remove Flooring, ACT Ceilings, Lights, Ductwork & Diffusers, etc.	10,195.04 SF	3.00	30,585.12
8	Remove Plumbing Fixtures	6.00 EA	75.00	450.00
9	Remove Doors & Frames	6.00 EA	75.00	450.00
10	Remove Interior Storefronts	48.69 LF	30.00	1,460.70
11			**Demolition Total**	**$40,702.61**
12			**Existing Conditions Total**	**$40,702.61**
13	**03 Concrete**			
14	**03.1000 Concrete**			
15	Patch Concrete Slab	256.26 SF	12.00	3,075.12
16	Hand-Dig Fill from Trench & Remove from Jobsite	128.13 LF	15.00	1,921.95
17	F/I Gravel Subbase in Trench	256.26 SF	6.00	1,537.56
18			**Concrete Total**	**$6,534.63**
19	**03.1500 Concrete Cutting**			
20	Sawcut & Remove Exterior Masonry Walls for New Storefronts (x8' Height)	84.97 LF	195.00	16,569.15
21	Sawcut Existing Slab (2' Wide) For Underground Utilities. Flip & Haul Concrete Off Site.	128.13 LF	40.00	5,125.20
22			**Concrete Cutting Total**	**$21,694.35**
23			**Concrete Total**	**$28,228.98**
24	**04 Masonry**			
25	**04.1000 Masonry**			
26	Exterior Envelope Upgrade Allowance	1.00 LS	25,000.00	25,000.00
27			**Masonry Total**	**$25,000.00**
28			**Masonry Total**	**$25,000.00**
29	**05 Metal**			
30	**05.0050 Structural Steel**			
31	F/I Dunnage for RTUs	2.00 EA	4,400.00	8,800.00
32			**Structural Steel Total**	**$8,800.00**
33	**05.7610 Lintels**			
34	F/I Lintels Above Storefronts	116.49 LF	65.00	7,571.85
35			**Lintels Total**	**$7,571.85**
36			**Metal Total**	**$16,371.85**
37	**06 Wood , Plastic and Composites**			
38	**06.2200 Millwork**			
39	F/I Millwork Lockers	3.00 EA	1,650.00	4,950.00
40	F/I Interior Shelving @ Storage	37.62 LF	150.00	5,643.00

Line	Description	Quantity	Unit Cost	Total
41	F/I Adjustable Shelves	7.05 LF	150.00	1,057.50
42	F/I Lower Cabinets w/Countertops @ Lounge/Break [Plastic Laminate]	11.67 LF	400.00	4,668.00
43	F/I Lower Cabinets w/Countertops @ Reception [Plastic Laminate]	6.88 LF	400.00	2,752.00
44	F/I Upper Cabinets @ Lounge/Break [Plastic Laminate]	11.28 LF	400.00	4,512.00
45	F/I Upper Cabinets @ Reception [Plastic Laminate]	6.92 LF	400.00	2,768.00
46	F/I Plastic Laminate Countertop @ Lounge/Break [Plastic Laminate]	15.67 SF	65.00	1,018.55
47	F/I Plastic Laminate Transaction Counter	30.99 SF	65.00	2,014.35
48	F/I Plastic Laminate Countertop @ Waiting	8.70 SF	60.00	522.00
49			**Millwork Total**	**$29,905.40**
50			**Wood , Plastic and Composites Total**	**$29,905.40**
51	**07 Thermal and Moisture Protection**			
52	**07.3000 Roofing**			
53	Roof Flashing & Penetration Allowance	1.00 LS	6,000.00	6,000.00
54			**Roofing Total**	**$6,000.00**
55			**Thermal and Moisture Protection Total**	**$6,000.00**
56	**08 Openings**			
57	**08.1100 HM Doors, Frames & HW**			
58	F/O HM Frame (Single)	42.00 EA	250.00	10,500.00
59	F/O HM Door	3.00 EA	400.00	1,200.00
60	F/O Solid-Core Birch Door	39.00 EA	250.00	9,750.00
61	F/O Door Hardware	39.00 EA	450.00	17,550.00
62	F/O Door Hardware	3.00 EA	500.00	1,500.00
63	F/O Vision Lite Kits w/Glass @ Private Offices/Conference Room	9.00 EA	260.00	2,340.00
64			**HM Doors, Frames & HW Total**	**$42,840.00**
65	**08.8200 Arch. Metal & Glass**			
66	F/I Exterior Glass Storefront System (Clear Anodized)	931.92 SF	80.00	74,553.60
67			**Arch. Metal & Glass Total**	**$74,553.60**
68			**Openings Total**	**$117,393.60**
69	**09 Finishes**			
70	**09.2300 Drywall & Carpentry**			
71	F/I 5/8" GWB Walls (Level 4 Finish)	27,165.30 SF	3.25	88,287.23
72	F/I Wood Blocking for Millwork	99.16 LF	12.00	1,189.92
73	F/I Blanket Insulation	19,447.20 SF	1.50	29,170.80
74	I/O Bath Accessories	4.00 BATH	500.00	2,000.00
75	I/O Fire Extinguisher Cabinet	8.00 EA	200.00	1,600.00
76	I/O Interior HM Door, Frame & HW (Single)	42.00 EA	275.00	11,550.00
77	F/I 3-5/8" Metal Stud Framing	19,659.90 SF	5.50	108,129.45
78	F/I Acoustical Sealant	4,946.88 LF	1.00	4,946.88
79			**Drywall & Carpentry Total**	**$246,874.28**
80	**09.2500 Acoustical Ceilings**			
81	F/I ACT Ceilings ($2.50/SF Material Budget)	10,660.98 SF	5.25	55,970.15

Line	Description	Quantity	Unit Cost	Total
82	F/I ACT Standard Grid ($1.50/SF Material Allowance)	10,660.98 SF	3.65	38,912.58
83			**Acoustical Ceilings Total**	**$94,882.73**
84	**09.3013 Tile & Stone**			
85	F/I Floor Tile @ Bathrooms ($7/SF Material Allowance)	376.22 SF	22.70	8,540.19
86	F/I Stone Flooring @ Vestibule ($30/SF Material Allowance)	90.42 SF	63.00	5,696.46
87	F/I Floor Tile @ Laundry ($7/SF Material Allowance)	82.24 SF	22.70	1,866.85
88	F/I Wall Tile (8' High) @ Unisex Bathrooms ($7/SF Material Allowance)	496.32 SF	22.70	11,266.46
89	F/I Wall Tile @ Men's & Women's Wet Walls (8' High) ($7/SF Material Allowance)	632.40 SF	22.70	14,355.48
90	F/I Waterproofing for Wall Tile	632.40 SF	5.00	3,162.00
91	F/I Waterproofing for Floor Tile @ Bathrooms	376.22 SF	5.00	1,881.10
92	F/I Waterproofing for Floor Tile @ Laundry	82.24 SF	5.00	411.20
93			**Tile & Stone Total**	**$47,179.74**
94	**09.6000 Flooring**			
95	Standard Floor Prep	10,660.98 SF	0.50	5,330.49
96	F/I VCT	119.63 SF	4.00	478.52
97	F/I 4" Vinyl Base	2,743.00 LF	2.95	8,091.85
98	F/I Carpet Tile ($45/SY Material Allowance)	357.68 SY	54.00	19,314.72
99	F/I LVT (Luxury Vinyl Tile) Flooring ($4/SF Material Allowance)	4,999.30 SF	8.40	41,994.12
100	F/I Loose Laid Rubber Gym Flooring	1,197.10 SF	6.00	7,182.60
101			**Flooring Total**	**$82,392.30**
102	**09.9100 Painting**			
103	Paint GWB Walls	425.40 SF	1.20	510.48
104	Paint Existing GWB Walls	2,696.70 SF	1.20	3,236.04
105	Paint/Stain Wood Door + HM Frame (Single)	39.00 EA	225.00	8,775.00
106	Paint HM Door & Frame (Single)	3.00 EA	200.00	600.00
107	Paint Existing HM Door & Frame (Single)	1.00 EA	200.00	200.00
108			**Painting Total**	**$13,321.52**
109			**Finishes Total**	**$484,650.57**
110	**10 Specialties**			
111	**10.1123 Whiteboards**			
112	F/I Whiteboard @ Conference	1.00 EA	800.00	800.00
113			**Whiteboards Total**	**$800.00**
114	**10.1400 Signage**			
115	Signage	1.00 LS	7,500.00	7,500.00
116			**Signage Total**	**$7,500.00**
117	**10.2800 Bath Accessories**			
118	F/O Bath Accessories (Unisex Bathrooms)	2.00 EA	1,000.00	2,000.00
119	F/O Bath Accessories (Men's/Women's Bathrooms)	2.00 EA	1,700.00	3,400.00
120			**Bath Accessories Total**	**$5,400.00**
121	**10.2900 Toilet Partitions**			

Line	Description	Quantity	Unit Cost	Total
122	F/I Toilet Partitions	5.00 EA	3,900.00	19,500.00
123			**Toilet Partitions Total**	**$19,500.00**
124	**10.4400 Fire Protection Specialties**			
125	Fire Extinguisher Cabinet + FE	8.00 EA	350.00	2,800.00
126			**Fire Protection Specialties Total**	**$2,800.00**
127	**10.5110 Storage Lockers**			
128	F/I Secure Storage Lockers	3.00 EA	850.00	2,550.00
129			**Storage Lockers Total**	**$2,550.00**
130			**Specialties Total**	**$38,550.00**
131	**11 Equipment**			
132	**11.3100 Appliances**			
133	F/O Washer	1.00 EA	2,500.00	2,500.00
134	F/O Dryer	1.00 EA	2,400.00	2,400.00
135	F/O Refrigerator (NIC - By Tenant)	1.00 EA	0.00	0.00
136	F/O Dishwasher	1.00 EA	1,200.00	1,200.00
137	F/O Microwave	1.00 EA	350.00	350.00
138			**Appliances Total**	**$6,450.00**
139			**Equipment Total**	**$6,450.00**
140	**21 Fire Suppression**			
141	**21.0000 Sprinkler**			
142	Modify Existing Sprinkler Heads	145.00 EA	325.00	47,125.00
143	Provide Shop Drawings	1.00 EA	2,500.00	2,500.00
144	Sprinkler Permits, Filing, Inspections, Signoff & Hydrostatic Testing	1.00 LS	2,500.00	2,500.00
145			**Sprinkler Total**	**$52,125.00**
146			**Fire Suppression Total**	**$52,125.00**
147	**22 Plumbing**			
148	**22.0000 Plumbing**			
149	F/I 80 gal, 76–100 kBTU/h Gas Tank□Type Water Heater	1.00 LS	12,500.00	12,500.00
150	Piping Distribution	1.00 LS	18,000.00	18,000.00
151	Disconnect Existing Plumbing Fixtures	6.00 EA	200.00	1,200.00
152	I/O Commercial Toilet	7.00 EA	1,500.00	10,500.00
153	I/O Bath Lav (Sink) & Faucet	8.00 EA	1,100.00	8,800.00
154	I/O Sink & Faucet	1.00 EA	1,200.00	1,200.00
155	I/O Wall-Mounted Urinal (Including Rough-In)	1.00 EA	1,600.00	1,600.00
156	I/O Water Fountain/Cooler	1.00 EA	2,000.00	2,000.00
157	I/O Appliance	2.00 EA	700.00	1,400.00
158	I/O Dishwasher	1.00 EA	1,500.00	1,500.00
159	F/I Refrigerator Waterline	1.00 EA	600.00	600.00
160	I/O Mop Sink Connection	1.00 EA	1,200.00	1,200.00
161	F/I Floor Drain 3"	1.00 EA	1,200.00	1,200.00
162			**Plumbing Total**	**$61,700.00**

Line	Description	Quantity	Unit Cost	Total
163	**22.4000 Plumbing Fixtures**			
164	F/O Kitchen Sink	1.00 EA	1,200.00	1,200.00
165	F/O Kitchen Faucet	1.00 EA	500.00	500.00
166	F/O LAV Sink	8.00 EA	600.00	4,800.00
167	F/O Lav Faucet	8.00 EA	250.00	2,000.00
168	F/O Commercial Wall-Mounted Toilet + Flushometer	7.00 EA	625.00	4,375.00
169	F/O Wall-Mounted Urinal	1.00 EA	800.00	800.00
170	F/O Mop Sink	1.00 EA	850.00	850.00
171	F/O Water Fountain/Cooler (Elkay or Equal) [Double]	1.00 EA	2,350.00	2,350.00
172			**Plumbing Fixtures Total**	**$16,875.00**
173			**Plumbing Total**	**$78,575.00**
174	**23 Heating, Ventilating and Air-Conditioning**			
175	**23.0000 HVAC**			
176	F/I Ductwork/Diffusers (Per SF)	10,660.00 SF	8.50	90,610.00
177	F/O VAVs/Zone Dampers	18.00 EA	1,500.00	27,000.00
178	F/I Exhaust System	1.00 LS	12,000.00	12,000.00
179	F/I Controls (Per SF)	10,660.00 SF	1.50	15,990.00
180	HVAC Testing & Startup	1.00 LS	4,500.00	4,500.00
181	HVAC Drain Downs & Disconnects	1.00 LS	3,500.00	3,500.00
182	F/I 12.5-Ton RTU	2.00 EA	38,000.00	76,000.00
183	Provide Air Balancing & Certified Report	1.00 EA	2,500.00	2,500.00
184			**HVAC Total**	**$232,100.00**
185			**Heating, Ventilating and Air-Conditioning Total**	**$232,100.00**
186	**26 Electrical**			
187	**26.0000 Electric**			
188	F/I Furniture Hookups	3.00 EA	550.00	1,650.00
189	F/I New 208/120V Panel (Assuming Existing Service is Adequate)	1.00 LS	39,500.00	39,500.00
190	F/I Duplex Receptacle	120.00 EA	175.00	21,000.00
191	F/I GFI Receptacle	2.00 EA	250.00	500.00
192	F/I Floor-Mounted Quad + Tel/Data + AV	1.00 EA	2,250.00	2,250.00
193	Mechanical Wiring	1.00 LS	43,000.00	43,000.00
194	I/O Lighting Fixture	139.00 EA	175.00	24,325.00
195	I/O Exit Sign	6.00 EA	175.00	1,050.00
196	F/I Single-Pole Switch	12.00 EA	140.00	1,680.00
197	F/I 3-Way Switch	7.00 EA	140.00	980.00
198	F/I Occupancy Sensor (OC)	24.00 EA	125.00	3,000.00
199	Electrical Disconnects Prior to Demo (Medium)	1.00 EA	1,700.00	1,700.00
200			**Electric Total**	**$140,635.00**
201	**26.5000 Lighting Fixtures**			
202	Lighting Fixture Budget	139.00 EA	175.00	24,325.00
203	Exit Sign	6.00 EA	160.00	960.00

Line	Description	Quantity	Unit Cost	Total
204			**Lighting Fixtures Total**	**$25,285.00**
205			**Electrical Total**	**$165,920.00**
206	**27 Communications**			
207	**27.1000 Tel/Data**			
208	Tel/Data Outlet	58.00 EA	225.00	13,050.00
209			**Tel/Data Total**	**$13,050.00**
210			**Communications Total**	**$13,050.00**
211	**28 Safety And Security**			
212	**28.4600 Fire Alarm**			
213	F/I Manual Pull Stations	2.00 EA	750.00	1,500.00
214	F/I Horn/Strobes	12.00 EA	950.00	11,400.00
215	F/I Strobes	6.00 EA	750.00	4,500.00
216	F/I Smoke Detector	1.00 EA	900.00	900.00
217	F/I Duct Smoke Detectors w/Relays	2.00 EA	1,800.00	3,600.00
218	F/I Monitor/Control Modules	8.00 EA	650.00	5,200.00
219	F/I NAC Power Supply & Batteries	1.00 EA	1,500.00	1,500.00
220	Tie-In to Existing System	1.00 LS	5,000.00	5,000.00
221	Fire Alarm Programming	1.00 LS	2,500.00	2,500.00
222			**Fire Alarm Total**	**$36,100.00**
223	**28.4610 Low-Voltage/Cameras**			
224	Security	1.00 LS	25,000.00	25,000.00
225			**Low-Voltage/Cameras Total**	**$25,000.00**
226			**Safety And Security Total**	**$61,100.00**
227	**Sub-Total (Base Cost)**			**$1,396,123.01**

Estimate Summary



Material [$126,891]
Labor [$0]
SubContractor [$1,269,232]
Equipment [$0]
Other [$0]

Description		Total
Sub-Total (Base Cost)		$1,396,123.01
Sub-Total (Direct Cost)		$1,396,123.01
General Conditions	8.0000%	111,689.84
Overhead	2.0000%	30,156.26
Fee	4.0000%	61,518.76
Insurance	0.5000%	7,997.44
Total Estimate		$1,607,485.31

Clipper Construction
1644 Beason St, Suite 201
Baltimore, MD, 21230
(443) 323-1880

Notes and Clarifications:

1. Pricing is to be used for budgetary purposes only.
2. Work performed during normal hours with open shop labor unless noted otherwise. After-hours premiums are excluded.
3. Asbestos testing/abatement is not included.
4. Permit fees are not included.
5. Utility fees are not included.
6. ACT ceilings include grid, tile, and basic perimeter trim in the office footprint only. Seismic bracing, ceiling clouds, specialty trims, and hard-lid details are not included.
7. Moisture mitigation, leveling, and slab repairs are excluded.
8. Occupancy/vacancy sensors provided in all enclosed rooms to meet IECC.
9. Low-voltage cabling, AV, security/access control are not included.
10. Height to deck is assumed to be 16' AFF.
11. Occupancy/vacancy sensors provided per IECC; daylighting controls included where required by code.
12. Access control is not included.