Cioffi Excavating Services Inc.
971 Rt 45, Suite 116
Pomona, NY, 10970
(845) 429-7711

03/27/2025

Estimate: 250061

TBD

Re: Gardner Ridge

Cioffi Excavating Services Inc.hereby proposes all materials, labor and supervision in accordance with drawings dated 01/28/2016 for the sum of **$4,922,995**

Description	Total Estimate
31.0000 Earthwork	446,903
31.1100 Drainage & Stormwater	1,170,519
31.1150 Sewer	239,908
31.1200 Water Service	343,566
31.2300 Rock Hammering	674,390
31.2500 Erosion And Sedimentation Controls	86,242
32.0001 Porous Unit Paving	89,575
32.1200 Paving	958,169
32.1500 Fencing & Gates	48,883
32.1600 Site Concrete	482,416
32.1723 Pavement Markings	17,850
32.9300 Landscaping	364,568
Totals	**$4,922,995**

CIOFFI EXCAVATING SERVICES INC.
845-429-7711

Status: Active Estimates
Contact:
Date: 03/27/2025

Estimate: 250061 Gardner Ridge

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**31 Sitework**			
2	**31.0000 Earthwork**			
3	Excavation for Entrance Road	4,673.52 CY	12.00	56,082.24
4	Excavate & Backfill for Light Pole Conduits	4,438.08 LF	13.50	59,914.08
5	Excavate Generator Pad	129.38 SF	5.00	646.90
6	Excavate Foundation (Frost Walls)	12.00 DAY	2,600.00	31,200.00
7	Backfill Frost Walls	9.00 DAY	2,600.00	23,400.00
8	Excavate Foundation (Slab on Grade)	10.00 DAY	2,600.00	26,000.00
9	Backfill Slab & Compact	9.00 DAY	2,600.00	23,400.00
10	Cut & Export of Fill for Slabs (1,190CY Used for Backfill)	4,022.39 CY	18.00	72,403.02
11	Fill Generated From Footings/Frost Wall Excavation to be Used for Backfill	1,190.37 CY	0.00	0.00
12	F/I 6" Gravel for Building Slabs	1,810.09 CY	85.00	153,857.65
13			**Earthwork Total**	**$446,903.89**
14	**31.1100 Drainage & Stormwater**			
15	F/I CB-GR6	1.00 EA	4,800.00	4,800.00
16	F/I CB-GR5	1.00 EA	4,800.00	4,800.00
17	F/I CB-D1	1.00 EA	4,800.00	4,800.00
18	F/I CB-C3-2	1.00 EA	4,800.00	4,800.00
19	F/I CB-C3-1	1.00 EA	6,240.00	6,240.00
20	F/I CB-C2	1.00 EA	3,840.00	3,840.00
21	F/I CB-D2	1.00 EA	3,840.00	3,840.00
22	F/I 24" HDPE @ 4.32%	138.20 LF	90.00	12,438.00
23	F/I 24" HDPE @ 2.85%	76.00 LF	90.00	6,840.00
24	F/I 15" HDPE @ 4.05%	109.75 LF	75.00	8,231.25
25	F/I 18" HDPE @ 5.54%	111.58 LF	53.00	5,913.74
26	F/I 24" HDPE @ 20.00%	111.00 LF	100.00	11,100.00
27	F/I 24" HDPE @ 7.24%	50.05 LF	90.00	4,504.50
28	F/I 24" HDPE @ 6.88%	88.98 LF	90.00	8,008.20
29	F/I 24" HDPE @ 1.00%	359.36 LF	90.00	32,342.40
30	F/I 15" HDPE @ 0.50%	296.95 LF	75.00	22,271.25
31	F/I 15" HDPE @ 0.25%	175.49 LF	75.00	13,161.75
32	F/I 24" HDPE @ 7.77%	133.75 LF	90.00	12,037.50
33	F/I 24" HDPE @ 7.39%	151.20 LF	90.00	13,608.00
34	F/I 30" HDPE @ 5.58%	69.14 LF	110.00	7,605.40
35	F/I 30" HDPE @ 6.53%	63.21 LF	110.00	6,953.10
36	F/I 24" HDPE @ 7.81%	128.99 LF	90.00	11,609.10
37	F/I 15" HDPE @ 1.00%	685.30 LF	75.00	51,397.50
38	F/I 18" HDPE @ 6.28%	70.13 LF	85.00	5,961.05
39	F/I 18" HDPE @ 1.00%	87.59 LF	85.00	7,445.15
40	F/I 18" HDPE @ 0.71%	341.45 LF	85.00	29,023.25
41	F/I 18" HDPE @ 0.50%	171.20 LF	85.00	14,552.00

Line	Description	Quantity	Unit Cost	Total
42	F/I CB-GR4	1.00 EA	3,840.00	3,840.00
43	F/I CB-16.1	1.00 EA	6,240.00	6,240.00
44	F/I CB-2	1.00 EA	3,840.00	3,840.00
45	F/I CB-1	1.00 EA	3,840.00	3,840.00
46	F/I CB-4	1.00 EA	3,840.00	3,840.00
47	F/I CB-3	1.00 EA	3,840.00	3,840.00
48	F/I CB-E2	1.00 EA	3,840.00	3,840.00
49	F/I CB-7	1.00 EA	4,800.00	4,800.00
50	F/I CB-6	1.00 EA	3,840.00	3,840.00
51	F/I CB-5	1.00 EA	3,840.00	3,840.00
52	F/I CB-5.1	1.00 EA	3,840.00	3,840.00
53	F/I CB-15.1	1.00 EA	6,240.00	6,240.00
54	F/I CB-19	2.00 EA	4,800.00	9,600.00
55	F/I CB-10	1.00 EA	4,800.00	4,800.00
56	F/I CB-11	1.00 EA	3,840.00	3,840.00
57	F/I CB-13	1.00 EA	4,800.00	4,800.00
58	F/I CB-16	1.00 EA	6,240.00	6,240.00
59	F/I CB-7.2	1.00 EA	4,800.00	4,800.00
60	F/I CB-7.1	1.00 EA	4,800.00	4,800.00
61	F/I CB-12	1.00 EA	3,840.00	3,840.00
62	F/I CB-14	1.00 EA	4,800.00	4,800.00
63	F/I CB-15	1.00 EA	4,800.00	4,800.00
64	F/I CB-16	1.00 EA	3,840.00	3,840.00
65	F/I CB-17	1.00 EA	4,800.00	4,800.00
66	F/I CB-17.1	1.00 EA	4,800.00	4,800.00
67	F/I CB-18.1	1.00 EA	3,840.00	3,840.00
68	F/I CB-18	1.00 EA	3,840.00	3,840.00
69	F/I CB-9	2.00 EA	3,840.00	7,680.00
70	F/I CB-8	1.00 EA	3,840.00	3,840.00
71	F/I CB-E1	1.00 EA	3,840.00	3,840.00
72	F/I Headwall(s)	2.00 EA	3,000.00	6,000.00
73	F/I FES-3	1.00 EA	1,140.00	1,140.00
74	F/I FES-2	1.00 EA	1,020.00	1,020.00
75	F/I FES	4.00 EA	960.00	3,840.00
76	F/I FES-1	1.00 EA	1,080.00	1,080.00
77	F/I CB-GR1	1.00 EA	3,840.00	3,840.00
78	F/I SMH-14	1.00 EA	5,040.00	5,040.00
79	F/I OS-1	1.00 EA	8,000.00	8,000.00
80	Strip and Scarify Subgrade for Bioretention Basins	10,704.37 SF	2.50	26,760.93
81	F/I Bioretention Soil (30") @ Bioretention Basins	10,704.37 SF	10.00	107,043.70
82	F/I 2"-3" of Mulch Layer @ Bioretention Basins	10,704.37 SF	1.25	13,380.46

Line	Description	Quantity	Unit Cost	Total
83	F/I Underdrain System @ Bioretention Basins	10,704.37 SF	3.00	32,113.11
84	F/I Filter Fabric @ Bioretention Basins	10,704.37 SF	0.75	8,028.28
85	Strip and Scarify Subgrade for Infiltration Bioretention Basins	9,334.55 SF	2.50	23,336.38
86	F/I Bioretention Soil (30") @ Infiltration Bioretention Basins	9,334.55 SF	10.00	93,345.50
87	F/I 2"-3" of Mulch Layer @ Infiltration Bioretention Basins	9,334.55 SF	1.25	11,668.19
88	F/I Filter Fabric @ BInfiltration ioretention Basins	9,334.55 SF	0.75	7,000.91
89	Earthwork & Grading @ Extended Detention Basins	11,692.30 SF	2.00	23,384.60
90	F/I Topsoil & Seeding @ Extended Detention Basins	11,692.30 SF	1.50	17,538.45
91	F/I Riprap @ Bioretention/Detention Basins	48.00 TN	250.00	12,000.00
92	Excavation & Grading @ Plunge Pools (3' Avg.)	11,085.71 SF	2.50	27,714.28
93	F/I 6" Aggregate Base @ Plunge Pools	11,085.71 SF	3.00	33,257.13
94	F/I Geotextile Fabric @ Plunge Pools	11,085.71 SF	1.25	13,857.14
95	F/I Riprap @ Plunge Pools (1'6" Depth)	925.47 TN	250.00	231,367.50
96			**Drainage & Stormwater Total**	**$1,170,519.70**
97	**31.1150 Sewer**			
98	F/I SMH-1	1.00 EA	5,040.00	5,040.00
99	F/I SMH-2	1.00 EA	5,040.00	5,040.00
100	F/I 8" PVC Pipe San Sewer @ 0.50%	947.65 LF	40.00	37,906.00
101	F/I 8" PVC Pipe San Sewer @ 1.21%	244.93 LF	40.00	9,797.20
102	F/I 8" PVC Pipe San Sewer @ 2.00%	211.10 LF	40.00	8,444.00
103	F/I 8" PVC Pipe San Sewer @ 2.77%	134.95 LF	40.00	5,398.00
104	F/I 8" PVC Pipe San Sewer @ 8.16%	109.33 LF	45.00	4,919.85
105	F/I 8" PVC Pipe San Sewer @ 12.41%	107.56 LF	50.00	5,378.00
106	F/I 8" PVC Pipe San Sewer @ 13.00%	87.12 LF	50.00	4,356.00
107	F/I 8" PVC Pipe San Sewer @ 14.44%	98.01 LF	50.00	4,900.50
108	F/I 8" PVC Pipe San Sewer @ 18.65%	126.89 LF	55.00	6,978.95
109	Tap Existing Sewer Lines	1.00 EA	1,500.00	1,500.00
110	F/I SMH-15	1.00 EA	5,040.00	5,040.00
111	F/I SMH-8	1.00 EA	5,040.00	5,040.00
112	F/I SMH-3	1.00 EA	6,040.00	6,040.00
113	F/I SMH-9	1.00 EA	5,040.00	5,040.00
114	F/I SMH-10	1.00 EA	5,040.00	5,040.00
115	F/I SDMH-1	1.00 EA	5,040.00	5,040.00
116	F/I SMH-11	1.00 EA	5,040.00	5,040.00
117	F/I SMH-12	1.00 EA	5,040.00	5,040.00
118	F/I SMH-13	1.00 EA	5,040.00	5,040.00
119	F/I SMH-7	1.00 EA	5,040.00	5,040.00
120	F/I SMH-6	1.00 EA	5,040.00	5,040.00
121	F/I SMH-5	1.00 EA	5,040.00	5,040.00
122	F/I SMH-4	1.00 EA	5,040.00	5,040.00
123	F/I Check Dam	10.00 EA	240.00	2,400.00

Line	Description	Quantity	Unit Cost	Total
124	Excavation for Sewer Piping	2,067.54 LF	13.50	27,911.79
125	Bedding Material for Sewer Piping	2,067.54 LF	8.00	16,540.32
126	Trench Backfill for Sewer Piping	2,067.54 LF	12.00	24,810.48
127	F/I Tracer Tape 12" Below Finish Grade	2,067.54 LF	1.00	2,067.54
128			**Sewer Total**	**$239,908.63**
129	**31.1200 Water Service**			
130	F/I 6" D.I.P. Water Service	406.70 LF	46.00	18,708.20
131	F/I 8" D.I.P. Water Service	3,038.16 LF	57.00	173,175.12
132	F/I Hydrant	5.00 EA	7,500.00	37,500.00
133	Excavate, Bedding (6" Under + 12" Over) & Backfill Trench for 6" Water Service	406.70 LF	27.00	10,980.90
134	Excavate, Bedding (NYSDOT Spec) & Backfill Trench for 6" Water Service	3,038.16 LF	30.00	91,144.80
135	Testing & Disinfection	3,444.86 LF	3.50	12,057.01
136			**Water Service Total**	**$343,566.03**
137	**31.2300 Rock Hammering**			
138	Rock Hammering Blast Area (Assuming 85% of 1.6 Acre Area @ 5' Depth)	10,971.00 CY	25.00	274,275.00
139	Haul Debris Off Site	12,907.00 CY	25.00	322,675.00
140	Rock Hammering (Assuming 15% of 1.6 Acre Area)	1,936.00 CY	40.00	77,440.00
141			**Rock Hammering Total**	**$674,390.00**
142	**31.2500 Erosion And Sedimentation Controls**			
143	F/I Catch Basin Stone Check Dam	37.00 EA	210.00	7,770.00
144	F/I Orange Construction Fencing.	6,362.49 LF	5.75	36,584.32
145	F/I Silt Fence	8,141.80 LF	4.85	39,487.73
146	F/I Construction Entrance	1.00 EA	2,400.00	2,400.00
147			**Erosion And Sedimentation Controls Total**	**$86,242.05**
148			**Sitework Total**	**$2,961,530.30**
149	**32 Exterior Improvements**			
150	**32.0001 Porous Unit Paving**			
151	F/I GrassPave2 Panels @ Emergency Access Driveway	8,237.83 SF	5.50	45,308.07
152	Strip Topsoil (6") @ Emergency Access Driveway	153.00 CY	8.00	1,224.00
153	Excavate to Subgrade @ Emergency Access Driveway	306.00 CY	12.00	3,672.00
154	Deliver & Place 8" Crushed Stone @ Emergency Access Driveway	204.00 CY	48.00	9,792.00
155	F/I Geotextile Fabric @ Emergency Access Driveway	8,237.83 SF	0.60	4,942.70
156	F/I Engineered Soil Mix (2" Depth) @ Emergency Access Driveway	51.00 CY	55.00	2,805.00
157	F/I Sod (Including Soil Prep & Watering) @ Emergency Access Driveway	8,237.83 SF	1.75	14,416.20
158	F/I Edging @ Emergency Access Driveway	824.00 LF	9.00	7,416.00
159			**Porous Unit Paving Total**	**$89,575.97**
160	**32.1200 Paving**			
161	Fine Grading & Compaction	126,185.14 SF	0.50	63,092.57
162	Sawcut Existing Asphalt	111.64 LF	9.00	1,004.76
163	F/I 2" Asphalt Top Course (Type 7F)	779.00 CY	205.00	159,695.00

Line	Description	Quantity	Unit Cost	Total
164	F/I 3" Asphalt Binder Course (3")	1,168.00 CY	175.00	204,400.00
165	F/I 6" Compacted NYSDOT Type 4 Subbase	5,888.64 CY	90.00	529,977.60
166			**Paving Total**	**$958,169.93**
167	**32.1500 Fencing & Gates**			
168	F/I Emergency Access Gates	2.00 EA	1,800.00	3,600.00
169	F/I Maintenance Access Gate(s)	2.00 EA	1,440.00	2,880.00
170	F/I Proposed Guide Rail [Cedar or PT Posts + 4"-6" Split Spruce Rail + Wire Mesh]	770.97 LF	55.00	42,403.35
171			**Fencing & Gates Total**	**$48,883.35**
172	**32.1600 Site Concrete**			
173	Concrete Curbs (No Detail Provided)	5,738.78 LF	23.00	131,991.94
174	Form & Pour Sidewalks	20,842.50 SF	10.00	208,425.00
175	F/I Precast Light Poll Bases	71.00 EA	2,000.00	142,000.00
176			**Site Concrete Total**	**$482,416.94**
177	**32.1723 Pavement Markings**			
178	Striping	21,000.00 LF	0.85	17,850.00
179			**Pavement Markings Total**	**$17,850.00**
180	**32.9300 Landscaping**			
181	F/I Plantings (Moderate Density) at Bioretention Basins	10,704.37 SF	5.00	53,521.85
182	F/I Plantings (Medium Density) @ Infiltration Bioretention Basins	9,334.55 SF	5.00	46,672.75
183	GT Sunburst Honey Locust	18.00 EA	300.00	5,400.00
184	Topsoil	1,023.00 CY	29.50	30,178.50
185	Mulch	93.00 CY	60.00	5,580.00
186	Tree Installation	300.00 HR	65.00	19,500.00
187	Shrub Installation	263.00 HR	65.00	17,095.00
188	Pre-Plant Soil Analysis Per Note 16	1.00 LS	1,500.00	1,500.00
189	1 Year of Manual Watering Per Note 14	208.00 HR	65.00	13,520.00
190	Provide 2 Year Warranty for Replacing Dead/Unhealthy Plants Per Note 15	1.00 LS	15,000.00	15,000.00
191	AR2 Red Maple	17.00 EA	100.00	1,700.00
192	AR Red Maple	13.00 EA	250.00	3,250.00
193	GM October Glory Maple	11.00 EA	300.00	3,300.00
194	AS Sugar Maple	20.00 EA	300.00	6,000.00
195	AA Serviceberry	2.00 EA	150.00	300.00
196	AC Canadian Serviceberry	9.00 EA	400.00	3,600.00
197	BN River Birch	16.00 EA	120.00	1,920.00
198	CFP Forest Pansy Redbud	7.00 EA	200.00	1,400.00
199	WFT White Fringetree	4.00 EA	180.00	720.00
200	K Kousa Dogwood	2.00 EA	150.00	300.00
201	CVH Winter King Hawthorn	18.00 EA	130.00	2,340.00
202	G Princeton Sentry Ginko	5.00 EA	350.00	1,750.00
203	JB Blue Point Juniper	15.00 EA	80.00	1,200.00

Line	Description	Quantity	Unit Cost	Total
204	JBA Blue Arrow Junipuer	4.00 EA	80.00	320.00
205	LS Sweet Gum	7.00 EA	300.00	2,100.00
206	LT Tulip Poplar	27.00 EA	120.00	3,240.00
207	CCA Centurion Crab Apple	5.00 EA	200.00	1,000.00
208	PA Norway Spruce	3.00 EA	400.00	1,200.00
209	PG White Spruce	23.00 EA	150.00	3,450.00
210	SSP Serbian Spruce	3.00 EA	500.00	1,500.00
211	PO2 American Sycamore	17.00 EA	120.00	2,040.00
212	PR Canadian Red Chokecherry	3.00 EA	180.00	540.00
213	QA White Oak	3.00 EA	350.00	1,050.00
214	QP Pin Oak	5.00 EA	120.00	600.00
215	QR Red Oak	9.00 EA	300.00	2,700.00
216	SR Japanese Tree Lilac	2.00 EA	180.00	360.00
217	TC Greenspire Littleleaf Linden	300.00 EA	300.00	90,000.00
218	BM Winter Gem Boxwood	93.00 EA	35.00	3,255.00
219	CP Golden Mopps False Cypress	30.00 EA	40.00	1,200.00
220	HQ Oakleaf Hydrangea	17.00 EA	45.00	765.00
221	HM2 Munchkin Oakleaf Hydrangea	11.00 EA	45.00	495.00
222	IG Inkberry Holly	21.00 EA	30.00	630.00
223	IGC Compact Inkberry	93.00 EA	30.00	2,790.00
224	IX3 Blue Princess Holly	9.00 EA	80.00	720.00
225	IVH Virginia Sweetspire	14.00 EA	25.00	350.00
226	JH Blue Rug Junipier	16.00 EA	20.00	320.00
227	JS Broadmoor Junipier	26.00 EA	20.00	520.00
228	KJP Double Flowered Kerria	8.00 EA	25.00	200.00
229	LAR Coastal Leucothoe	46.00 EA	35.00	1,610.00
230	PE Little Joker Ninebark	19.00 EA	40.00	760.00
231	RX3 Double Knockout Rose	12.00 EA	25.00	300.00
232	RXC Flower Carpet Rose	9.00 EA	35.00	315.00
233	SXG Goldflame Spirea	15.00 EA	30.00	450.00
234	SX2 Magic Carpet Spirea	14.00 EA	25.00	350.00
235	SYR Little Kim Lilac	11.00 EA	30.00	330.00
236	VB Prague Viburnum	48.00 EA	50.00	2,400.00
237	VB2 Burkwood Viburnum	15.00 EA	50.00	750.00
238	WF Weigela	6.00 EA	35.00	210.00
239			**Landscaping Total**	**$364,568.10**
240			**Exterior Improvements Total**	**$1,961,464.29**
241	**Sub-Total (Base Cost)**			**$4,922,994.59**

Cioffi Excavating Services Inc.
971 Rt 45, Suite 116
Pomona, NY, 10970
(845) 429-7711

Exclusions

1. Pricing is valid for thirty (30) calendar days from the date of proposal.
2. All work is based on normal working hours, Monday through Friday. Overtime, weekend, or holiday work is excluded unless otherwise noted.
3. Proposal assumes open, unobstructed access to the site with adequate laydown and staging areas.
4. No allowance has been made for dewatering, or obstructions below grade unless explicitly included.
5. If unsuitable soils are encountered during excavation, a change order will be issued for removal and replacement.
6. Frost wall and trench excavation assumes straight, clean cuts without shoring. If sloping or benching is required due to OSHA standards or soil conditions, this will be addressed as a change in scope.
7. Reuse of on-site material is assumed only for trench and wall backfill, and only if deemed suitable by geotechnical testing.
8. All under-slab, paving, and bioretention areas require imported structural fill or specified engineered soils.
9. All pipe bedding will be imported crushed stone per spec.
10. Stormwater features (bioretention basins, infiltration basins, extended detention, plunge pools) are priced based on the details provided.
11. Riprap quantities are based on plan details; no additional energy dissipation structures are included unless shown.
12. Bioretention soil and mulch are included per SF and depth specified.
13. No allowance has been made for tack coat, saw cutting, striping, or signage unless specifically noted.
14. Sanitary sewer installation includes pipe, bedding, excavation, backfill, and haul-off.
15. No allowance has been made for water mains, storm sewer, or electrical utilities unless listed separately.
16. Surveying or stakeouts are not included.
17. Permit fees or inspections are not included.
18. Final landscaping or topsoil placement
19. Excavation for pool or surrounding concrete slab is not included.
20. Hydroseeding is not included.
21. Irrigation system is not included.
22. Stone veneer is not included.

All materials guaranteed to be as specified, and above work to be performed in accordance with the drawings and specifications submitted for the above work, and completed in a substantial workmanlike manner.

Any alteration or deviation from above specifications involving extra costs will be executed only upon written order, and will become an extra charge over and above the proposal. All agreements contingent upon strikes, or delays beyond our control.

Total **$4,922,995**

By signing this document, the customer agrees to the services and conditions outlined by this document.

_____

Cioffi Excavating Services Inc.