Estimate: 250076 1216 5th Ave

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**02 Existing Conditions**			
2	**02.1000 Demolition**			
3	Remove Masonry Posts @ Front Porch (By Machine)	2.00 EA	500.00	1,000.00
4	Remove Concrete Steps @ Front Porch (By Machine)	4.00 EA	100.00	400.00
5	Remove Concrete Slab @ Front Porch Stairs (By Machine)	21.52 SF	20.00	430.40
6	Remove Concrete Porch (By Machine)	170.87 SF	12.00	2,050.44
7	Remove Existing Porch Railings (By Machine)	26.97 LF	7.00	188.79
8	Remove Porch Roof (By Hand)	197.59 SF	12.00	2,371.08
9	Remove Roof In Its Entirety (By Hand)	1,632.40 SF	5.00	8,162.00
10	Remove Exterior Walls @ 2nd Floor (By Hand)	32.34 LF	65.00	2,102.10
11	Remove Existing Tile Ceiling On 3/4" Furring (By Hand)	460.33 SF	3.75	1,726.24
12	Remove Wood Stairs (By Hand)	4.00 EA	350.00	1,400.00
13	Remove Existing Porch Foundation (By Machine)	37.76 LF	55.00	2,076.80
14	Remove Existing Siding (By Hand)	1,471.37 SF	2.00	2,942.74
15	Remove Stone Adjacent to Front Porch Windows (By Hand)	29.15 SF	20.00	583.00
16	Remove Interior Partitions (By Hand)	17.48 LF	25.00	437.00
17	Remove Doors & Frames (By Hand)	3.00 EA	75.00	225.00
18	Remove Windows (By Hand)	2.00 EA	125.00	250.00
19			**Demolition Total**	**$26,345.59**
20			**Existing Conditions Total**	**$26,345.59**
21	**03 Concrete**			
22	**03.1000 Concrete**			
23	Form & Pour Concrete Footings	3.56 CY	675.00	2,403.00
24	Form & Pour Concrete Foundation Wall(s)	7.64 CY	675.00	5,157.00
25	Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.	2.32 CY	625.00	1,450.00
26	Form & Pour Exterior Concrete Stairs (Per Risers). F/I All Applicable Rebar Per Plans & Specifications.	3.00 EA	1,250.00	3,750.00
27			**Concrete Total**	**$12,760.00**
28			**Concrete Total**	**$12,760.00**
29	**05 Metal**			
30	**05.0100 Misc. Steel**			
31	F/I 36" High Metal Rail with Spindles Painted Black @ Porch	28.64 LF	225.00	6,444.00
32	F/I 36" High Metal Rail with Spindles Painted Black @ Stairs	8.06 LF	225.00	1,813.50
33			**Misc. Steel Total**	**$8,257.50**
34			**Metal Total**	**$8,257.50**
35	**06 Wood , Plastic and Composites**			
36	**06.2000 Finish Carpentry**			
37	I/O Attic Access Doors	4.00 EA	250.00	1,000.00
38	I/O Interior Wood Door & F/I Trim	4.00 EA	250.00	1,000.00
39	I/O Pocket Door	5.00 EA	425.00	2,125.00
40	F/I Base Molding	317.59 LF	10.00	3,175.90

Line	Description	Quantity	Unit Cost	Total
41	F/I Door Casing	339.33 LF	9.50	3,223.64
42	F/I Window Casing	204.78 LF	11.00	2,252.58
43			**Finish Carpentry Total**	**$12,777.12**
44	**06.2200 Millwork**			
45	F/I Full-Height Cabinet @ Laundry Room ($1,500 Allowance to Supply)	1.01 LF	1,725.00	1,742.25
46	F/I Vanities ($400/LF Allowance to Supply)	5.02 LF	550.00	2,761.00
47			**Millwork Total**	**$4,503.25**
48	**06.2300 Closet Interiors**			
49	F/I Closet Interiors (Hat Shelf & Rod)	6.77 LF	95.00	643.15
50	F/I Closet Interiors (Master WIC)	11.17 LF	350.00	3,909.50
51			**Closet Interiors Total**	**$4,552.65**
52	**06.4001 Wood Framing Materials**			
53	F/O Pull Down Attic Access Hatch	1.00 EA	300.00	300.00
54	F/O 2x4 PT	13.71 LF	1.90	25.99
55	F/O 2x4 DF	27.42 LF	1.63	44.76
56	F/O 2x4 Studs	118.02 LF	1.61	189.77
57	F/O 2x6 PT	265.08 LF	2.29	607.57
58	F/O 2x6 DF	1,134.72 LF	1.85	2,096.96
59	F/O 2x6 Studs	1,365.32 LF	1.85	2,523.11
60	F/O 2x8 DF	169.21 LF	2.39	404.07
61	F/O 2x10 DF	1,979.70 LF	4.10	8,124.69
62	F/O 10"x10"x8' Cedar Post	2.00 EA	550.00	1,100.00
63	F/O 5-1/4" x 14" LVL @ Front Porch	37.42 LF	45.60	1,706.20
64	F/O 4x8x1/2" CDX Fir Plywood	1,161.85 SF	2.06	2,375.10
65	F/O 4x8x5/8" CDX Fir Plywood	2,433.32 SF	2.22	5,403.16
66	F/O 4x8x3/4" TG Advantech Plywood	685.97 SF	2.19	1,482.03
67	F/O Simpson ABU66Z Post Base	2.00 EA	50.00	100.00
68			**Wood Framing Materials Total**	**$26,483.41**
69	**06.4002 Wood Framing Labor**			
70	Remove Side Door	1.00 EA	100.00	100.00
71	Remove Front Door	1.00 EA	100.00	100.00
72	I/O Attic Access Hatch	1.00 EA	250.00	250.00
73	I/O LVL @ Front Porch	37.42 LF	15.00	561.30
74	Make Selective Cuts Existing House STructure Prior to Foundation	1.00 LS	1,200.00	1,200.00
75	I/O Interior Framed Wall	956.50 SF	3.00	2,869.50
76	I/O Floor Framing (Joists & Subfloor)	891.07 SF	4.50	4,009.82
77	I/O Ceiling Framing (Joists)	182.48 SF	3.00	547.44
78	I/O Exterior Wall Framing & Sheathing @ 2nd Floor	956.75 SF	5.50	5,262.13
79	I/O Roof Framing & Sheathing	2,433.32 SF	5.50	13,383.26
80	I/O Deck Post	2.00 EA	75.00	150.00
81	I/O Residential Exterior Door & Hardware	2.00 EA	400.00	800.00

Line	Description	Quantity	Unit Cost	Total
82			**Wood Framing Labor Total**	**$29,233.45**
83	**06.4300 Wood Stairs And Railings**			
84	F/I Wood Railings	12.79 LF	800.00	10,232.00
85	F/I White Oak Stairs w/Poplar Strings & Risers (Per Riser)	7.00 EA	475.00	3,325.00
86			**Wood Stairs And Railings Total**	**$13,557.00**
87			**Wood , Plastic and Composites Total**	**$91,106.88**
88	**07 Thermal and Moisture Protection**			
89	**07.2000 Insulation**			
90	F/I Sound Deadening Insulation	146.70 SF	1.50	220.05
91	F/I R-21 Fiberglass Batt	905.45 SF	1.51	1,367.23
92	F/I R-21 Fiberglass Batt (Plan View)	956.75 SF	1.51	1,444.69
93	F/I R-49 Spray-Foam	2,195.78 SF	9.10	19,981.60
94			**Insulation Total**	**$23,013.57**
95	**07.2400 Stucco**			
96	F/I Weather-Resistant Barrier (WRB), Flashing & Sealants	482.52 SF	4.00	1,930.08
97	F/I Metal Lath & Fasteners	482.52 SF	4.50	2,171.34
98	F/I Scratch & Brown Coats (Base Layers - Portland Cement Plaster)	482.52 SF	7.50	3,618.90
99	F/I Finish Coat (Acrylic or Cement-Based Stucco Finish)	482.52 SF	4.00	1,930.08
100	F/I Control Joints, Trim & Expansion Joints	482.52 SF	2.50	1,206.30
101	F/I Scaffolding & Access Equipment	482.52 SF	2.00	965.04
102			**Stucco Total**	**$11,821.74**
103	**07.3000 Roofing**			
104	F/I 3-Tab Asphalt Roof Shingles + Ice & Water Shield/Drip Edge & Ridge Cap	2,415.36 SF	5.50	13,284.48
105	F/I Standing Seam Sheet Metal Roofing	261.29 SF	20.00	5,225.80
106			**Roofing Total**	**$18,510.28**
107	**07.6200 Sheet Metal Flashing And Trim**			
108	F/I 10" Aluminum Fascia (Breakmetal)	344.66 LF	10.00	3,446.60
109			**Sheet Metal Flashing And Trim Total**	**$3,446.60**
110	**07.6600 Gutters & Leaders**			
111	5" Gutters	228.43 LF	9.00	2,055.87
112	5" Leaders	190.31 LF	9.00	1,712.79
113			**Gutters & Leaders Total**	**$3,768.66**
114	**07.9510 Siding**			
115	F/I Furring Strips @ Front Porch Area	93.23 SF	3.10	289.01
116	F/I James Hardie Fiber Cement Siding	2,041.54 SF	13.50	27,560.77
117	F/I James Hardie Board & Batten (16" O.C.)	223.06 SF	15.50	3,457.45
118	F/I 12" Vinyl Vented Soffits	229.35 LF	7.26	1,664.65
119	F/I Tyvek Housewrap	956.75 SF	1.33	1,402.05
120	F/I Wood Plank @ Porch Ceiling	182.48 SF	29.80	5,437.94
121	F/I Exterior Window Trim ($15/LF Budget)	709.78 LF	25.50	18,099.42

Line	Description	Quantity	Unit Cost	Total
122			**Siding Total**	**$57,911.29**
123			**Thermal and Moisture Protection Total**	**$118,472.14**
124	**08 Openings**			
125	**08.1400 Wood Doors & HW**			
126	F/O Attic Access Doors Pair 24"xTBD	4.00 EA	450.00	1,800.00
127	F/O Solid-Core Wood Door to Match Existing	4.00 EA	450.00	1,800.00
128	F/O Pocket Door with Kit (Builder Grade)	5.00 EA	550.00	2,750.00
129	F/O Door Hardware ($200 Allowance Each)	9.00 EA	200.00	1,800.00
130			**Wood Doors & HW Total**	**$8,150.00**
131	**08.1600 Residential Entry Doors & HW**			
132	F/O Residential Fiberglass Entry Door (36"x80"x6-9/16") ($1000/Each Allowance Placeholder]	1.00 EA	1,000.00	1,000.00
133	F/O Residential Wood Entry Door (36"x80"x9-1/6") ($1,500 Allowance Placeholder]	1.00 EA	1,500.00	1,500.00
134	F/O Residential Entry Door Deadlock/Door Knob Combo [$100/Each Allowance Placeholder]	2.00 EA	100.00	200.00
135			**Residential Entry Doors & HW Total**	**$2,700.00**
136	**08.5000 Windows**			
137	F/I Andersen 400 Series Windows	203.28 SF	50.00	10,164.00
138			**Windows Total**	**$10,164.00**
139	**08.8200 Arch. Metal & Glass**			
140	I/O Glass Doors And Panels @ Office	1.00 EA	3,600.00	3,600.00
141			**Arch. Metal & Glass Total**	**$3,600.00**
142	**08.8500 Shower Enclosures**			
143	F/I Shower Enclosure	1.00 EA	3,500.00	3,500.00
144			**Shower Enclosures Total**	**$3,500.00**
145			**Openings Total**	**$28,114.00**
146	**09 Finishes**			
147	**09.2300 Drywall & Carpentry**			
148	F/I 1/2" GWB Walls	2,853.76 SF	3.00	8,561.28
149	F/I 1/2" GWB Ceilings	3,837.43 SF	3.00	11,512.29
150	Patch Existing GWB Walls	2,182.64 SF	2.50	5,456.60
151			**Drywall & Carpentry Total**	**$25,530.17**
152	**09.3013 Tile & Stone**			
153	F/I Floor Tile ($10/SF Material Allowance)	134.97 SF	27.00	3,644.22
154	F/I Wall Tile ($10/SF Material Allowance)	323.04 SF	27.00	8,722.04
155	F/I Mud Job at Shower	1.00 EA	500.00	500.00
156	F/I Waterproofing for Wall Tile	40.38 SF	4.00	161.52
157	F/I Waterproofing for Floor Tile	117.66 SF	4.00	470.64
158	F/I Waterproofing for Floor Tile	17.31 SF	5.25	90.88
159			**Tile & Stone Total**	**$13,589.30**
160	**09.6400 Wood Flooring**			

Line	Description	Quantity	Unit Cost	Total
161	F/I Engineered Wood Flooring ($12/SF Material Allowance)	898.94 SF	19.00	17,079.86
162			**Wood Flooring Total**	**$17,079.86**
163	**09.9100 Painting**			
164	Paint GWB Walls	2,366.10 SF	1.30	3,075.93
165	Paint Base Molding	317.59 LF	3.50	1,111.57
166	Paint GWB Ceilings	3,549.25 SF	1.30	4,614.03
167	Paint Door Casing (Per LF)	33.33 LF	5.00	166.65
168	Paint/Stain Wood Doors & Casing	9.00 EA	225.00	2,025.00
169	Paint Window Casing	204.78 LF	5.00	1,023.90
170	Paint GWB Walls (Plan View)	2,182.64 SF	1.30	2,837.43
171	Prime & Paint Residential Fiberglass Entry Door	2.00 EA	350.00	700.00
172			**Painting Total**	**$15,554.51**
173			**Finishes Total**	**$71,753.84**
174	**11 Equipment**			
175	**11.3100 Appliances (Not Included)**			
176	Washer (By Owner)	1.00 EA	0.00	0.00
177	Dryer (By Owner)	1.00 EA	0.00	0.00
178			**Appliances (Not Included) Total**	**$0.00**
179			**Equipment Total**	**$0.00**
180	**12 Furnishing**			
181	**12.3600 Countertops**			
182	Template, Fabricate & Install Solid Surface Countertops ($60/SF Material Allowance)	9.20 SF	125.00	1,150.00
183	Template, Fabricate & Install Shower Curb ($60/SF Material Allowance)	7.68 SF	125.00	960.00
184			**Countertops Total**	**$2,110.00**
185			**Furnishing Total**	**$2,110.00**
186	**22 Plumbing**			
187	**22.0000 Plumbing**			
188	I/O Residential Toilet	1.00 EA	2,500.00	2,500.00
189	I/O Standard Shower	1.00 EA	2,500.00	2,500.00
190	I/O Freestanding Bathtub	1.00 EA	3,750.00	3,750.00
191	I/O Appliance	2.00 EA	750.00	1,500.00
192			**Plumbing Total**	**$10,250.00**
193	**22.4000 Plumbing Fixtures (Budget)**			
194	F/O Residential Toilet	1.00 EA	485.00	485.00
195	F/O Free-Standing Bathtub	1.00 EA	1,500.00	1,500.00
196	F/O Standard Shower Kit	2.00 EA	1,200.00	2,400.00
197	F/O Tub Filler/Faucet	1.00 EA	1,325.00	1,325.00
198			**Plumbing Fixtures (Budget) Total**	**$5,710.00**
199			**Plumbing Total**	**$15,960.00**
200	**23 Heating, Ventilating and Air-Conditioning**			

Line	Description	Quantity	Unit Cost	Total
201	**23.0000 HVAC**			
202	F/I Ductwork, Controls, etc.	800.00 SF	18.00	14,400.00
203	F/I AHU-5 Air Handler	1.00 EA	5,000.00	5,000.00
204	F/I AHU-4 Air Handler	1.00 EA	5,000.00	5,000.00
205	Duct Exhaust Fan	1.00 EA	300.00	300.00
206	F/I Condensers Feeding AHU-4 & 5	1.00 EA	12,500.00	12,500.00
207			**HVAC Total**	**$37,200.00**
208			**Heating, Ventilating and Air-Conditioning Total**	**$37,200.00**
209	**26 Electrical**			
210	**26.0000 Electric**			
211	Revise Existing Wiring & Switching	1.00 EA	1,500.00	1,500.00
212	Relocate Son's Bath Switches	1.00 EA	250.00	250.00
213	F/I Home Run + Arc-Fault Breaker	12.00 EA	275.00	3,300.00
214	F/I Duplex Receptacle	33.00 EA	105.00	3,465.00
215	F/I GFI Receptacle	3.00 EA	125.00	375.00
216	F/I Weatherproof GFI Receptacle	2.00 EA	220.00	440.00
217	F/I Dedicated Equipment Duplex 20amp	2.00 EA	300.00	600.00
218	Wire 60 Amp AC Condenser Unit	1.00 EA	1,300.00	1,300.00
219	Wire Air Handlers	2.00 EA	750.00	1,500.00
220	I/O Lighting Fixture	31.00 EA	200.00	6,200.00
221	I/O Ceiling Fan	6.00 EA	205.00	1,230.00
222	F/I Junction Box for Ceiling Fan	6.00 EA	185.00	1,110.00
223	F/I Residential Exhaust Fan	1.00 EA	250.00	250.00
224	F/I Single-Pole Switch	14.00 EA	105.00	1,470.00
225	3-Way Switch (Residential)	4.00 EA	90.00	360.00
226	LED Dimmer Switch	10.00 EA	160.00	1,600.00
227	Electrical Disconnects Prior to Demo	1.00 EA	1,200.00	1,200.00
228			**Electric Total**	**$26,150.00**
229	**26.5000 Lighting Fixtures (Budget)**			
230	F/O Exterior Wall Sconce Lighting Fixture	1.00 EA	550.00	550.00
231	F/O Recessed Lighting Fixture	9.00 EA	100.00	900.00
232	F/O Decorative Lighting Fixture Budget @ Freestanding Tub	1.00 EA	850.00	850.00
233	F/O Master Bath Vanity Lighting Fixture	2.00 EA	700.00	1,400.00
234	F/O Pendant Lighting Fixture Budget @ Desk In Master Bedroom	1.00 EA	1,100.00	1,100.00
235	F/O Closet Wall Mounted Lighting Fixture	8.00 EA	200.00	1,600.00
236	F/O Surface Mounted Hallway Lighting Fixture	3.00 EA	400.00	1,200.00
237	F/O Surface Mounted Fixture @ 3rd Floor	6.00 EA	450.00	2,700.00
238			**Lighting Fixtures (Budget) Total**	**$10,300.00**
239			**Electrical Total**	**$36,450.00**
240	**28 Safety And Security**			
241	**28.4600 Fire Alarm**			

Line	Description	Quantity	Unit Cost	Total
242	F/I Smoke/Carbon Monoxide Detector Combo	4.00 EA	300.00	1,200.00
243			**Fire Alarm Total**	**$1,200.00**
244			**Safety And Security Total**	**$1,200.00**
245	**31 Sitework**			
246	**31.0000 Earthwork**			
247	Excavate Foundation (Slab on Grade)	0.08 DAY	3,000.00	240.00
248	Excavate Foundation (Frost Walls)	0.24 DAY	3,000.00	720.00
249	Excavate Foundation (Frost Walls)	0.08 DAY	3,600.00	288.00
250	Backfill Frost Walls	0.24 DAY	3,000.00	720.00
251	Backfill Frost Walls	0.08 DAY	3,600.00	288.00
252	Backfill Slab & Compact	0.10 DAY	3,000.00	300.00
253	F/I Crushed Stone	23.20 CY	105.00	2,436.00
254	Mobilization	1.00 EA	2,500.00	2,500.00
255			**Earthwork Total**	**$7,492.00**
256			**Sitework Total**	**$7,492.00**
257	**32 Exterior Improvements**			
258	**32.1400 Hardscaping**			
259	F/I Bluestone Pavers (Including Excavation & Gravel)	194.88 SF	32.00	6,236.16
260	F/I 2" Bluestone Stair Treads	24.00 LF	65.00	1,560.00
261			**Hardscaping Total**	**$7,796.16**
262			**Exterior Improvements Total**	**$7,796.16**
263	**Sub-Total (Base Cost)**			**$465,018.11**

Estimate Summary



Material [$77,793]
Labor [$0]
SubContractor [$369,203]
Equipment [$0]
Other [$18,023]

Description		Total
Sub-Total (Base Cost)		$465,018.11
Material	10.0000%	7,779.25
Labor	30.0000%	0.00
SubContractor	25.0000%	92,300.63
Equipment	10.0000%	0.00
Other	10.0000%	1,802.31
Sub-Total (Direct Cost)		$566,900.30
Overhead & Profit	21.0000%	119,049.06
Total Estimate		$685,949.36