Kulka.

Status: Active Estimates
Contact:
Date: 03/07/2025

Estimate: 250032 200 Petit Ave **Estimate Unit Costs**

Line	Description	Quantity	Unit Cost	Total
1	**01 General Requirements**			
2	**01.3113 Project Coordination & Permits**			
3	LIRR Coordination & Permits	1.00 LS	20,000.00	20,000.00
4			**Project Coordination & Permits Total**	**$20,000.00**
5	**01.4523 Testing and Monitoring Services**			
6	Vibration Monitoring Equipment & Reporting	1.00 LS	10,000.00	10,000.00
7			**Testing and Monitoring Services Total**	**$10,000.00**
8	**01.5000 Temporary Facilities And Controls**			
9	Flaggers And Safety Personnel (LIRR Mandated)	10.00 DY	1,500.00	15,000.00
10			**Temporary Facilities And Controls Total**	**$15,000.00**
11	**01.5526 Traffic Control & Signage**			
12	Pedestrian & Traffic Control (Road Closures, Signage, Detours)	1.00 LS	15,000.00	15,000.00
13			**Traffic Control & Signage Total**	**$15,000.00**
14			**General Requirements Total**	**$60,000.00**
15	**02 Existing Conditions**			
16	**02.1000 Demolition**			
17	Demo Existing Sidewalks	1,718.87 SF	6.00	10,313.22
18	Demo Existing Single Story Building	1,140.00 SF	15.00	17,100.00
19	Demo 2 Story Building	1,725.00 SF	20.00	34,500.00
20	Remove And Cart Away Asphalt Driveway	2,300.00 SF	2.50	5,750.00
21	Demo Existing Single Story Building	3,650.00 SF	10.00	36,500.00
22	Demo Foundation	2,072.44 SF	6.00	12,434.64
23			**Demolition Total**	**$116,597.86**
24			**Existing Conditions Total**	**$116,597.86**
25	**03 Concrete**			
26	**03.1000 Concrete**			
27	Form & Pour 12" Slab @ 1st Floor (5,000-6,000 PSI)	308.00 CY	680.00	209,440.00
28	Form & Pour 36" Concrete Columns	104.40 CY	650.00	67,860.00
29	Form & Pour Concrete Footings	45.04 CY	675.00	30,402.00
30	Form & Pour Concrete Foundation Wall(s)	175.23 CY	675.00	118,280.25
31	Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.	116.99 CY	675.00	78,968.25
32	Form & Pour Spread Footings	10.15 CY	850.00	8,627.50
33	Pump Trucks	4.00 EA	2,200.00	8,800.00
34			**Concrete Total**	**$522,378.00**
35	**03.3370 Concrete Topping**			
36	F/I Gypcrete Topping 3000psi @ 2nd Floor	6,677.00 SF	5.00	33,385.00
37			**Concrete Topping Total**	**$33,385.00**
38			**Concrete Total**	**$555,763.00**
39	**05 Metal**			
40	**05.0050 Structural Steel**			

Line	Description	Quantity	Unit Cost	Total
41	F/I Elevator Hoist Beam	1.00 LS	1,500.00	1,500.00
42	F/I Galvanized Steel Dunnage	212.08 SF	60.00	12,724.80
43	F/I Steel Beams Vertical	14,014.00 LB	5.00	70,070.00
44			**Structural Steel Total**	**$84,294.80**
45	**05.0100 Misc. Steel**			
46	F/I Steel Pan Stairs & Railings (Per Riser)	72.00 EA	950.00	68,400.00
47	F/I 1-1/2" Pipe Rail Cellar To Ground Floor @ Retail Space	15.95 LF	40.00	638.00
48			**Misc. Steel Total**	**$69,038.00**
49			**Metal Total**	**$153,332.80**
50	**06 Wood , Plastic and Composites**			
51	**06.2000 Finish Carpentry**			
52	F/I Base Molding	3,141.77 LF	10.00	31,417.70
53			**Finish Carpentry Total**	**$31,417.70**
54	**06.2200 Millwork**			
55	F/I Kitchen Cabinets (Uppers & Lowers)	22.00 EA	3,850.00	84,700.00
56	F/I Vanities (Mid-Grade)	62.97 LF	450.00	28,336.50
57			**Millwork Total**	**$113,036.50**
58	**06.4001 Wood Framing Materials**			
59	F/O 2x4 PT	762.81 LF	1.90	1,446.28
60	F/O 2x4 DF	1,525.62 LF	1.63	2,489.82
61	F/O 2x4 Studs	5,263.19 LF	1.61	8,463.21
62	F/O 2x6 PT	1,170.48 LF	2.29	2,682.75
63	F/O 2x6 DF	5,945.06 LF	1.85	10,986.47
64	F/O 2x6 Studs	13,299.87 LF	1.85	24,578.15
65	F/O 2x10 DF	81.86 LF	4.10	335.95
66	F/O 4x8x1/2" CDX Fir Plywood x 2	2,203.46 SF	3.99	8,798.00
67	F/O 4x8x1/2" CDX Fir Plywood	5,605.38 SF	1.99	11,136.58
68	F/O 4x8x1/2" CDX Fir Plywood	2,959.47 SF	1.82	5,383.56
69	F/O 4x8x5/8" CDX Fir Plywood	7,983.72 SF	2.20	17,619.00
70	F/O 4x8x3/4" TG Advantech Plywood	6,742.16 SF	2.06	13,942.06
71	F/O 11-7/8" TJI 360 I-Joist (Per LF)	4,728.03 LF	9.12	43,119.66
72	F/O 11-7/8" Pro 560 TJI (Per LF)	6,234.52 LF	13.73	85,587.44
73	F/O Termite shield (6" x 25' Aluminum Roll)	328.83 LF	0.83	274.40
74	F/O FormSealR 5-1/2" x 50' Sill Seal	328.83 LF	0.29	96.00
75			**Wood Framing Materials Total**	**$236,939.33**
76	**06.4002 Wood Framing Labor**			
77	I/O Headers And Columns @ Parking Garage	1.00 LS	12,000.00	12,000.00
78	I/O Interior Framed Wall	13,854.41 SF	3.00	41,563.23
79	I/O Floor Framing (Joists & Subfloor)	6,742.16 SF	4.50	30,339.73
80	I/O Exterior Wall Framing & Sheathing @ 1st Floor	2,959.47 SF	4.50	13,317.62
81	I/O Exterior Wall Framing & Sheathing @ 2nd Floor	2,203.46 SF	11.00	24,238.06

Line	Description	Quantity	Unit Cost	Total
82	I/O Exterior Wall Framing & Sheathing @ 2nd Floor	5,605.38 SF	5.50	30,829.59
83	I/O Roof Framing & Sheathing	7,983.72 SF	5.50	43,910.46
84			**Wood Framing Labor Total**	**$196,198.69**
85	**06.4300 Wood Stairs And Railings**			
86	F/I Yellow Pine Box Stairs & Railings (Basement Stairs Per Riser)	12.00 EA	205.00	2,460.00
87			**Wood Stairs And Railings Total**	**$2,460.00**
88			**Wood , Plastic and Composites Total**	**$580,052.22**
89	**07 Thermal and Moisture Protection**			
90	**07.2000 Insulation**			
91	F/I R-11 FSK Insulation Above ACT Ceilings	7,459.71 SF	1.75	13,054.49
92	F/I Sound Deadening Insulation	5,976.93 SF	1.50	8,965.40
93	F/I R-21 Fiberglass Batt	7,574.79 SF	1.51	11,437.94
94	F/I R-21 Fiberglass Batt	10,768.31 SF	1.51	16,260.14
95	F/I R-30 Fiberglass Batt	7,296.31 SF	1.59	11,601.13
96	F/I R-38 Fiberglass Batt	7,983.72 SF	1.96	15,648.09
97			**Insulation Total**	**$76,967.19**
98	**07.2400 Exterior Insulation & Finish Systems (EIFS)**			
99	F/I Weather-Resistant Barrier (WRB), Flashing & Sealants	9,195.20 SF	4.00	36,780.80
100	F/I Control Joints, Trim & Expansion Joints	9,195.20 SF	2.50	22,988.00
101	F/I Scaffolding & Access Equipment	9,195.20 SF	2.00	18,390.40
102	F/I 2" Rigid Insulation [R-10 Continuous EPS]	9,195.20 SF	3.50	32,183.20
103	F/I Base Coat (Polymer-Modified Cement Adhesive, Fiberglass Reinforcement Mesh)	9,195.20 SF	5.00	45,976.00
104	F/I Finish Coat (Acrylic or Synthetic Textured Finish)	9,195.20 SF	4.50	41,378.40
105			**Exterior Insulation & Finish Systems (EIFS)\ Total**	**$197,696.80**
106	**07.3000 Roofing**			
107	F/I Roof Drains & Scuppers	8,782.00 SF	1.50	13,173.00
108	F/I DensDeck 1/2" Coverboard	8,782.00 SF	3.00	26,346.00
109	F/I R-30 Polyiso Insulation (4" Average)	8,782.00 SF	5.50	48,301.00
110	F/I TPO Mechanically Fastened Membrane	6,934.44 SF	20.00	138,688.80
111	F/I TPO Mechanically Fastened Membrane	1,847.65 SF	10.00	18,476.50
112	F/I TPO at Parapet Walls	808.95 SF	10.00	8,089.50
113	F/I .040 Aluminum Coping @ Parapet Walls	690.80 LF	45.00	31,086.00
114			**Roofing Total**	**$284,160.80**
115	**07.7600 Roof Pavers**			
116	F/I Roof Pavers on Pedestals @ Terrace	1,531.45 SF	47.50	72,743.88
117			**Roof Pavers Total**	**$72,743.88**
118	**07.9510 Siding**			
119	F/I Weather Barrier (Air & Moisture Barrier)	1,863.00 SF	4.50	8,383.50
120	F/I Rainscreen System	1,863.00 SF	4.50	8,383.50
121	F/I Fiber Cement Panel Siding	1,862.44 SF	21.00	39,111.24

Line	Description	Quantity	Unit Cost	Total
122			**Siding Total**	**$55,878.24**
123			**Thermal and Moisture Protection Total**	**$687,446.91**
124	**08 Openings**			
125	**08.1100 HM Doors, Frames & HW**			
126	F/O Bathroom HM Frame	22.00 EA	365.00	8,030.00
127	F/O Mechanical Room HM Frame	2.00 EA	365.00	730.00
128	F/O Unit Entry HM Frame	22.00 EA	365.00	8,030.00
129	F/O Garage To Residential Lobby HM Frame	1.00 EA	365.00	365.00
130	F/O HM Frame (Single)	6.00 EA	450.00	2,700.00
131	F/O Garage To Residential Lobby HM Door	1.00 EA	1,100.00	1,100.00
132	F/O Mechanical Room HM Door	2.00 EA	800.00	1,600.00
133	F/O Unit Entry HM Door	22.00 EA	1,100.00	24,200.00
134	F/O HM Door	6.00 EA	550.00	3,300.00
135	Bathroom Solid-Core Wood Door	22.00 EA	550.00	12,100.00
136	F/O Mechanical Room Door Hardware	2.00 EA	750.00	1,500.00
137	F/O Unit Entry Door Hardware	22.00 EA	500.00	11,000.00
138	F/O Door Hardware	6.00 EA	750.00	4,500.00
139	F/O Door Hardware	22.00 EA	150.00	3,300.00
140	F/O Garage To Residential Lobby Door Hardware	1.00 EA	1,075.00	1,075.00
141			**HM Doors, Frames & HW Total**	**$83,530.00**
142	**08.8200 Arch. Metal & Glass**			
143	F/I Exterior Sliding Storefront Door & HW	5.00 EA	7,000.00	35,000.00
144	F/I Terrace Door & HW	11.00 EA	4,500.00	49,500.00
145	F/I Exterior Storefront Door & HW	4.00 EA	4,500.00	18,000.00
146	F/I Exterior Glass Storefront System Black	3,152.76 SF	110.00	346,803.60
147			**Arch. Metal & Glass Total**	**$449,303.60**
148	**08.8400 Glass Railings**			
149	F/I Glass Railings [View Rail w/Black Metal Posts & Top Rail]	142.79 LF	425.00	60,685.75
150			**Glass Railings Total**	**$60,685.75**
151			**Openings Total**	**$593,519.35**
152	**09 Finishes**			
153	**09.2300 Drywall & Carpentry**			
154	F/I 1/2" GWB Walls	1,132.45 SF	2.75	3,114.24
155	F/I 2 Layers Of 5/8" GWB Ceilings	9,143.96 SF	5.50	50,291.79
156	F/I 5/8" GWB Walls	34,140.13 SF	3.50	119,490.46
157	F/I 5/8" GWB Walls	1,403.84 SF	3.25	4,562.48
158	F/I 5/8" GWB Ceilings	6,934.44 SF	3.50	24,270.54
159	F/I Blanket Insulation	1,403.84 SF	1.75	2,456.72
160	I/O Bath Accessories	22.00 BATH	500.00	11,000.00
161	I/O Interior HM Door, Frame & HW	46.00 EA	275.00	12,650.00
162	I/O Interior HM Door, Frame & HW (Single)	6.00 EA	275.00	1,650.00

Line	Description	Quantity	Unit Cost	Total
163	I/O Exterior HM Door, Frame & HW	1.00 EA	350.00	350.00
164	F/I 3-5/8" Metal Stud Framing	1,403.84 SF	5.85	8,212.46
165			**Drywall & Carpentry Total**	**$238,048.69**
166	**09.2500 Acoustical Ceilings**			
167	F/I ACT Ceilings [2x4 Armstrong's Cortega Fire Guard + Prelude XL 15/16" Grid]	7,459.71 SF	12.00	89,516.52
168			**Acoustical Ceilings Total**	**$89,516.52**
169	**09.3013 Tile & Stone**			
170	F/I Floor Tile	688.37 SF	24.70	17,002.76
171	F/I Wall Tile @ Bathtub Walls	1,624.80 SF	24.70	40,132.56
172	F/I Tile Backsplash	346.92 SF	38.20	13,252.32
173	F/I Waterproofing for Wall Tile	1,624.80 SF	5.00	8,124.00
174	F/I Waterproofing for Floor Tile	688.37 SF	5.00	3,441.85
175			**Tile & Stone Total**	**$81,953.49**
176	**09.6000 Flooring**			
177	F/I LVT (Luxury Vinyl Tile) Flooring @ Units	8,806.81 SF	9.50	83,664.69
178	F/I LVT (Luxury Vinyl Tile) Flooring @ Ground Floor Entryway	618.29 SF	9.50	5,873.75
179	F/I LVT (Luxury Vinyl Tile) Flooring @ Stairwells	625.30 SF	9.50	5,940.35
180	F/I LVT (Luxury Vinyl Tile) Flooring @ Corridors 1st And 2nd Floor	1,530.29 SF	9.50	14,537.76
181			**Flooring Total**	**$110,016.55**
182	**09.6700 Fluid-Applied Flooring**			
183	F/I Traffic Coating	6,321.83 SF	4.50	28,448.24
184			**Fluid-Applied Flooring Total**	**$28,448.24**
185	**09.9100 Painting**			
186	Paint GWB Walls	34,819.60 SF	1.30	45,265.48
187	Paint Base Molding	3,141.77 LF	3.50	10,996.21
188	Paint GWB Ceilings	14,616.73 SF	1.30	19,001.74
189	Paint/Stain Wood Door + HM Frame	22.00 EA	225.00	4,950.00
190	Paint CMU Walls @ Stairwells	3,520.00 SF	2.50	8,800.00
191	Paint HM Door & Frame	25.00 EA	200.00	5,000.00
192	Paint HM Door & Frame (Single)	6.00 EA	200.00	1,200.00
193			**Painting Total**	**$95,213.43**
194			**Finishes Total**	**$643,196.92**
195	**10 Specialties**			
196	**10.2800 Bath Accessories/Trash Receptacles**			
197	F/O Bath Accessories Budget (Mid-Grade Residential Guest Bath/Powder Room)	22.00 EA	700.00	15,400.00
198	Trash & Recycling Bins (Exterior & Common Area Waste Collection)	10.00 EA	450.00	4,500.00
199			**Bath Accessories/Trash Receptacles Total**	**$19,900.00**
200	**10.5110 Package Delivery Lockers**			
201	Package Delivery Lockers (Amazon Hub/Parcel Storage)	1.00 EA	15,000.00	15,000.00
202			**Package Delivery Lockers Total**	**$15,000.00**

Line	Description	Quantity	Unit Cost	Total
203	**10.7313 Marquee/Awnings**			
204	F/I Marquee	239.67 SF	40.00	9,586.80
205	F/I Awning @ Residential Lobby Entrance	63.91 SF	40.00	2,556.40
206			**Marquee/Awnings Total**	**$12,143.20**
207			**Specialties Total**	**$47,043.20**
208	**11 Equipment**			
209	**11.3100 Appliances**			
210	F/O Refrigerator	22.00 EA	1,300.00	28,600.00
211	F/O Dishwasher	22.00 EA	800.00	17,600.00
212	F/O Range	22.00 EA	1,200.00	26,400.00
213	F/O Over-The-Range Microwave	22.00 EA	350.00	7,700.00
214			**Appliances Total**	**$80,300.00**
215			**Equipment Total**	**$80,300.00**
216	**12 Furnishing**			
217	**12.3600 Countertops**			
218	Template, Fabricate & Install Solid Surface Countertops @ Vanities	351.66 SF	100.00	35,166.00
219			**Countertops Total**	**$35,166.00**
220	**12.9313 Bike Racks**			
221	Wall-Mounted Bike Racks	11.00 EA	300.00	3,300.00
222	Freestanding Bike Rack	6.00 EA	750.00	4,500.00
223			**Bike Racks Total**	**$7,800.00**
224			**Furnishing Total**	**$42,966.00**
225	**14 Conveying System**			
226	**14.2000 Elevators**			
227	Elevators 3 Stops (Per Stop)	1.00 EA	130,000.00	130,000.00
228			**Elevators Total**	**$130,000.00**
229			**Conveying System Total**	**$130,000.00**
230	**21 Fire Suppression**			
231	**21.0000 Sprinkler**			
232	Sprinkler Accessories And Mains	1.00 LS	15,000.00	15,000.00
233	Sprinkler Budget @ Units	9,588.58 SF	6.00	57,531.48
234	Sprinkler Budget Stairwells And Tenant Spaces	3,483.98 SF	6.00	20,903.88
235	Sprinkler Budget @ Cellar Retail Storage And Ground Floor Retail Space	2,710.77 SF	4.00	10,843.08
236	New Dry Sprinkler Heads @ Parking Garage	54.57 EA	450.00	24,556.50
237	Sprinkler Shop Drawings	1.00 LS	5,000.00	5,000.00
238	Sprinkler Permits, Filing, Inspections, Signoff & Hydrostatic Testing	1.00 LS	6,000.00	6,000.00
239			**Sprinkler Total**	**$139,834.94**
240			**Fire Suppression Total**	**$139,834.94**
241	**22 Plumbing**			
242	**22.0000 Plumbing**			
243	Plumbing Stub-Ups For Retail Space	1.00 LS	3,500.00	3,500.00

Line	Description	Quantity	Unit Cost	Total
244	F/I Domestic Water Supply	19,310.00 SF	4.00	77,240.00
245	F/I Sanitary Waste & Vent Piping	19,310.00 SF	5.00	96,550.00
246	F/I Tankless HWH	22.00 EA	2,600.00	57,200.00
247	F/I Water Meter & Backflow Preventer	1.00 LS	22,000.00	22,000.00
248	F/I Hose Bib	10.00 EA	550.00	5,500.00
249	I/O Residential Toilet	22.00 EA	1,200.00	26,400.00
250	I/O Bathroom Sink & Faucet	22.00 EA	1,200.00	26,400.00
251	I/O Standard Bathtub	22.00 EA	1,200.00	26,400.00
252	I/O Sink & Faucet	22.00 EA	1,200.00	26,400.00
253	I/O Washer(s)	22.00 EA	750.00	16,500.00
254	I/O Dryer(s)	22.00 EA	750.00	16,500.00
255	I/O Dishwasher	22.00 EA	1,200.00	26,400.00
256	F/I Gas Piping & Connection for Range	22.00 EA	1,200.00	26,400.00
257			**Plumbing Total**	**$453,390.00**
258	**22.4000 Plumbing Fixtures**			
259	F/O Kitchen Sink	22.00 EA	1,200.00	26,400.00
260	F/O Kitchen Faucet	22.00 EA	500.00	11,000.00
261	F/O Bathroom Sink	22.00 EA	600.00	13,200.00
262	F/O Bathroom Faucet	22.00 EA	250.00	5,500.00
263	F/O Residential Toilet	22.00 EA	400.00	8,800.00
264	F/O Standard Bathtub	22.00 EA	1,200.00	26,400.00
265	F/O Standard Shower Kit	22.00 EA	1,000.00	22,000.00
266			**Plumbing Fixtures Total**	**$113,300.00**
267			**Plumbing Total**	**$566,690.00**
268	**23 Heating, Ventilating and Air-Conditioning**			
269	**23.0000 HVAC**			
270	HVAC Budget @ Cellar Retail Storage And 1st Floor Retail Space	2,710.77 SF	28.00	75,901.56
271	HVAC Budget @ Tenant Spaces	3,482.64 SF	28.00	97,513.92
272	HVAC Budget @ Units	9,588.58 SF	28.00	268,480.24
273			**HVAC Total**	**$441,895.72**
274			**Heating, Ventilating and Air-Conditioning Total**	**$441,895.72**
275	**26 Electrical**			
276	**26.0000 Electric**			
277	F/I Temporary Power & Lighting (Construction Use, Jobsite Distribution, Temporary Panels & Outlets)	19,310.00 SF	1.50	28,965.00
278	F/I Main Electrical Service (Switchgear, Metering, Utility Connection, Transformer)	19,310.00 SF	5.00	96,550.00
279	F/I Distribution (Panels, Breakers, Feeders, Conduit, Bus Ducts, Wiring to Floors)$4 – $6$71,362 – $107,043 Branch Wiring (Ou	19,310.00 SF	7.00	135,170.00
280	F/I Branch Wiring (Outlets, Circuits, Wiring Devices, GFCI, EMT Conduit)	19,310.00 SF	7.50	144,825.00
281	F/I Transformer Vault	1.00 LS	18,500.00	18,500.00
282			**Electric Total**	**$424,010.00**

Line	Description	Quantity	Unit Cost	Total
283	**26.5000 Lighting Fixtures**			
284	F/O Lighting Fixture Budget @ Parking Garage	6,275.36 SF	4.00	25,101.44
285	F/O Lighting Fixture Budget @ Stairs And Tenant Spaces	1,215.81 SF	4.00	4,863.24
286	F/O Lighting Fixture Budget @ Cellar Retail Storage And 1st Floor Retail Space	2,710.77 SF	4.00	10,843.08
287	F/O Lighting Budget @ Units	9,588.58 SF	4.00	38,354.32
288	F/O Lighting Budget @ Stairwells And Tenant Spaces	2,266.73 SF	4.00	9,066.92
289			**Lighting Fixtures Total**	**$88,229.00**
290			**Electrical Total**	**$512,239.00**
291	**27 Communications**			
292	**27.1000 Tel Data/Low Voltage**			
293	F/I Telecom & Data (Cat6, Fiber, Wireless Access Points, Rack & Patch Panel, Terminations)	19,310.00 SF	1.50	28,965.00
294	F/I Low Voltage (Intercom, Security, Access Control, CCTV, Door Strikes, Cabling)	19,310.00 SF	3.00	57,930.00
295			**Tel Data/Low Voltage Total**	**$86,895.00**
296			**Communications Total**	**$86,895.00**
297	**28 Safety And Security**			
298	**28.4600 Fire Alarm**			
299	F/I Fire Alarm System (Pull Stations, Horn/Strobes, Smoke Detectors, Panels, Monitoring System)	19,310.00 SF	5.50	106,205.00
300			**Fire Alarm Total**	**$106,205.00**
301			**Safety And Security Total**	**$106,205.00**
302	**31 Sitework**			
303	**31.0000 Sitework**			
304	Excavate Foundation (Slab on Grade)	3.90 DAY	2,800.00	10,920.00
305	Excavate Foundation (Frost Walls)	3.76 DAY	2,800.00	10,528.00
306	Backfill Frost Walls	3.76 DAY	2,800.00	10,528.00
307	Backfill Slab & Compact	4.87 DAY	2,800.00	13,636.00
308	F/I Crushed Stone	219.37 CY	115.00	25,227.55
309	F/I Structural Fill (Recycled Item #4 + General Fill Combo)	498.92 CY	20.00	9,978.40
310			**Sitework Total**	**$80,817.95**
311	**31.1100 Drainage & Stormwater**			
312	F/I 4" Footing Drain	547.34 LF	22.00	12,041.48
313	F/I Drainage Allowance	1.00 EA	75,000.00	75,000.00
314			**Drainage & Stormwater Total**	**$87,041.48**
315	**31.1150 Sewer & Waste**			
316	Connect to Existing Sewer Main	1.00 EA	3,500.00	3,500.00
317			**Sewer & Waste Total**	**$3,500.00**
318	**31.1200 Water Service**			
319	F/I Sprinkler Main	1.00 EA	15,000.00	15,000.00
320	F/I Water Main	1.00 EA	15,000.00	15,000.00
321			**Water Service Total**	**$30,000.00**

Line	Description	Quantity	Unit Cost	Total
322			**Sitework Total**	**$201,359.43**
323	**32 Exterior Improvements**			
324	**32.1200 Repair Asphalt Roadway**			
325	Repair Asphalt Road	1,356.78 SF	15.00	20,351.70
326			**Repair Asphalt Roadway Total**	**$20,351.70**
327	**32.1600 Site Concrete**			
328	Form & Pour Concrete Curb (6” Wide @ Top & 8-1/4” @ Bottom) (Includes Excavation)	287.11 LF	29.00	8,326.19
329	Form & Pour Sidewalks	1,718.87 SF	16.00	27,501.92
330			**Site Concrete Total**	**$35,828.11**
331	**32.1723 Pavement Markings**			
332	F/I Basic Striping	6,275.00 SF	0.35	2,196.25
333			**Pavement Markings Total**	**$2,196.25**
334	**32.1900 Misc. Site Furnishings**			
335	Outdoor Metal/Wood Benches - 6-Foot Standard	4.00	1,750.00	7,000.00
336	F/I Wheel Stops	15.00 EA	350.00	5,250.00
337			**Misc. Site Furnishings Total**	**$12,250.00**
338			**Exterior Improvements Total**	**$70,626.06**
339	**Sub-Total (Base Cost)**			**$5,815,963.41**

Estimate Summary



Description		Total
Sub-Total (Base Cost)		$5,815,963.41
Material	10.0000%	37,713.01
Sub-Total (Direct Cost)		$5,853,676.42
Contingency (5%)	5.0000%	292,683.82
General Requirements/Conditions	8.0000%	491,708.82
Fee	5.0000%	331,903.45
Insurance	3.5000%	243,949.04
Total Estimate		$7,213,921.55