Estimate: 250043 318 Parkview Ave

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**02 Existing Conditions**			
2	**02.1000 Demolition**			
3	Remove Exterior Walls	15.90 LF	35.00	556.50
4	Remove Base Molding	383.16 LF	2.50	957.90
5	Remove Kitchen Cabinets, Appliances & Countertops	1.00 LS	1,500.00	1,500.00
6	Remove Existing Dormer Addition	300.00 SF	15.00	4,500.00
7	Remove Existing Stairs	10.00 EA	60.00	600.00
8	Remove Interior Walls	30.37 LF	23.00	698.51
9	Remove Floor Tile	131.26 SF	3.50	459.41
10	Remove Wall Tile & Backing	292.00 SF	3.50	1,022.00
11	Remove Flooring	1,417.32 SF	2.75	3,897.63
12	Remove Plumbing Fixtures	3.00 EA	75.00	225.00
13	Remove Doors & Frames	5.00 EA	75.00	375.00
14			**Demolition Total**	**$14,791.95**
15	**02.1500 Containers/Waste Removal**			
16	30-Yard Container	7.00 EA	925.00	6,475.00
17			**Containers/Waste Removal Total**	**$6,475.00**
18			**Existing Conditions Total**	**$21,266.95**
19	**03 Concrete**			
20	**03.1000 Concrete**			
21	Form & Pour 2'4"x4'8" Spread Footing	0.44 CY	1,050.00	462.00
22	Form & Pour 24"x32" Spread Footing	0.20 CY	1,050.00	210.00
23	Form & Pour 16"x16" Piers	0.57 CY	1,050.00	598.50
24	Form & Pour 8"x16" Piers	1.14 CY	1,050.00	1,197.00
25	Hand-Dig Fill from & Remove from Jobsite	2.00 DAY	400.00	800.00
26			**Concrete Total**	**$3,267.50**
27	**03.1500 Concrete Cutting**			
28	Sawcut Existing Slab for Spread Footings	16.97 SF	105.00	1,781.85
29	Cut Out Existing Masonry Wall for Sill Plate Installation	16.26 LF	45.00	731.70
30			**Concrete Cutting Total**	**$2,513.55**
31			**Concrete Total**	**$5,781.05**
32	**04 Masonry**			
33	**04.1000 Masonry**			
34	F/I CMU Block [8"x8"x16"]	27.54 BLOCK	34.97	963.06
35			**Masonry Total**	**$963.06**
36			**Masonry Total**	**$963.06**
37	**05 Metal**			
38	**05.0050 Structural Steel**			
39	F/O 3/4" Flitch Plate	607.29 LB	2.50	1,518.23
40	F/O 5/8" Flitch Plate	170.68 LB	2.50	426.70
41			**Structural Steel Total**	**$1,944.93**

Line	Description	Quantity	Unit Cost	Total
42			**Metal Total**	**$1,944.93**
43	**06 Wood , Plastic and Composites**			
44	**06.2000 Finish Carpentry**			
45	I/O Interior Wood Door & F/I Trim	11.50 EA	250.00	2,875.00
46	F/I Base Molding	613.01 LF	10.00	6,130.10
47	F/I Door Casing	396.33 LF	9.50	3,765.14
48	F/I Window Casing	139.28 LF	11.00	1,532.08
49			**Finish Carpentry Total**	**$14,302.32**
50	**06.2200 Millwork**			
51	F/I Decorative Slat Walls	6.21 LF	900.00	5,589.00
52	F/I Built-In Bar	6.38 LF	1,050.00	6,699.00
53	F/I Lower Cabinets @ Kitchen	26.47 LF	650.00	17,205.50
54	F/I Upper Cabinets @ Kitchen	15.85 LF	625.00	9,906.25
55	F/I Islands Cabinets @ Kitchen	6.11 LF	1,000.00	6,110.00
56	F/I Vanity @ Master Bath	9.66 LF	475.00	4,588.50
57	F/I Vanities	5.99 LF	475.00	2,845.25
58			**Millwork Total**	**$52,943.50**
59	**06.2300 Closet Interiors**			
60	F/I Closet Interiors (Hat Shelf & Rod)	3.17 LF	95.00	301.15
61	F/I Closet Interiors (Master WIC)	41.69 LF	350.00	14,591.50
62			**Closet Interiors Total**	**$14,892.65**
63	**06.4001 Wood Framing Materials**			
64	F/O 6"x6"x10' DF Posts	22.00 EA	57.60	1,267.20
65	F/O 4"x4"x10' DF Posts	8.00 EA	21.60	172.80
66	F/O 2x4 PT	36.59 LF	1.13	41.28
67	F/O 2x4 PT	81.02 LF	1.90	153.62
68	F/O 2x4 DF	73.18 LF	0.90	65.87
69	F/O 2x4 DF	162.04 LF	1.63	264.45
70	F/O 2x4 Studs	232.09 LF	0.90	208.88
71	F/O 2x4 Studs	110.01 LF	1.61	176.89
72	F/O 2x6 PT	16.18 LF	1.27	20.59
73	F/O 2x6 PT	1.11 LF	2.29	2.54
74	F/O 2x6 DF	32.36 LF	1.14	36.89
75	F/O 2x6 DF	322.87 LF	1.85	596.66
76	F/O 2x6 Studs	107.18 LF	1.07	114.47
77	F/O 2x6 Studs	974.55 LF	1.85	1,800.97
78	F/O 2x8 DF	577.95 LF	1.44	832.25
79	F/O 2x8 DF Blocking @ Fascias	121.44 LF	2.39	290.00
80	F/O 2x10 DF	126.84 LF	1.80	228.32
81	F/O 2x10 DF Blocking @ Fascias	121.44 LF	4.10	498.40
82	F/O 1-3/4" x 7-1/4" LVL 19.E	78.98 LF	6.96	549.73

Line	Description	Quantity	Unit Cost	Total
83	F/O 1-3/4" x 9-1/4" LVL	22.22 LF	8.64	191.95
84	F/O 1-3/4" x 11-7/8" LVL	105.60 LF	10.20	1,077.12
85	F/O 1-3/4" x 11-7/8" LVL Ridge Beam	107.89 LF	10.20	1,100.50
86	F/O 5-1/4" x 14" LVL Rafters	639.62 LF	45.63	29,184.00
87	F/O 4x8x1/2" CDX Fir Plywood	132.03 SF	2.00	263.90
88	F/O 4x8x1/2" CDX Fir Plywood	1,283.40 SF	1.85	2,375.10
89	F/O 4x8x5/8" CDX Fir Plywood	852.82 SF	2.20	1,879.36
90	F/O 4x8x3/4" T&G Plywood	797.70 SF	2.01	1,606.20
91	F/O Termite shield (6" x 25' Aluminum Roll)	16.18 LF	0.99	15.98
92	F/O FormSealR 5-1/2" x 50' Sill Seal	16.18 LF	0.74	12.00
93			**Wood Framing Materials Total**	**$45,027.92**
94	**06.4002 Wood Framing Labor**			
95	Sister Existing 2x8 Floor Joists	471.46 LF	14.00	6,600.44
96	I/O 2x8 Floor Joists	99.60 LF	4.50	448.20
97	I/O Sliding Door	1.00 EA	400.00	400.00
98	I/O Interior Framed Wall	429.25 SF	3.50	1,502.38
99	I/O Exterior Wall Framing & Sheathing @ 1st Floor	132.03 SF	5.00	660.15
100	I/O Exterior Wall Framing & Sheathing @ 2nd Floor	1,283.40 SF	6.00	7,700.40
101	I/O Roof Framing & Sheathing	852.82 SF	6.00	5,116.92
102	I/O Plywood Subfloor	797.70 SF	2.00	1,595.40
103	I/O Residential Exterior Door & Hardware	1.00 EA	400.00	400.00
104	I/O Window(s) (Standard Sizes)	12.00 EA	200.00	2,400.00
105			**Wood Framing Labor Total**	**$26,823.89**
106	**06.4300 Wood Stairs And Railings**			
107	F/I White Oak Stairs w/Poplar Strings & Risers (Per Riser)	12.00 EA	600.00	7,200.00
108			**Wood Stairs And Railings Total**	**$7,200.00**
109			**Wood , Plastic and Composites Total**	**$161,190.28**
110	**07 Thermal and Moisture Protection**			
111	**07.2000 Insulation**			
112	F/I Sound Deadening Insulation	328.43 SF	1.50	492.65
113	F/I R-26 Closed-Cell Insulation	1,283.40 SF	6.06	7,777.40
114	F/I R-26 Closed-Cell Insulation	132.03 SF	6.06	800.10
115	F/I F/I R-26 Closed-Cell Insulation @ Display Area (Existing Walls)	252.00 SF	6.06	1,527.12
116	F/I R-49 Spray-Foam	852.82 SF	9.10	7,760.66
117			**Insulation Total**	**$18,357.93**
118	**07.3000 Roofing**			
119	Tie-Into Existing Roofing	1.00 LS	2,500.00	2,500.00
120	F/I 3-Tab Asphalt Roof Shingles + Ice & Water Shield/Drip Edge & Ridge Cap	938.11 SF	5.50	5,159.61
121			**Roofing Total**	**$7,659.61**
122	**07.6600 Gutters & Leaders**			

Line	Description	Quantity	Unit Cost	Total
123	F/I 5" Gutters	36.19 LF	17.00	615.23
124	F/I 5" Leaders	22.64 LF	17.00	384.88
125			**Gutters & Leaders Total**	**$1,000.11**
126	**07.9510 Siding**			
127	F/I Hardie Wrap Weather Barrier	796.40 SF	2.10	1,672.44
128	F/I Modern Mill 1x6 Shiplap Siding	796.40 SF	22.03	17,540.71
129	F/I 1"x8"x12' Azek Trim	120.95 LF	16.53	1,999.11
130	1/2"x12"x18' Azek Soffits	85.15 SF	15.81	1,346.19
131			**Siding Total**	**$22,558.45**
132			**Thermal and Moisture Protection Total**	**$49,576.10**
133	**08 Openings**			
134	**08.1400 Wood Doors & HW**			
135	F/O 3'0"x6'8"Solid-Core Wood Door	3.00 EA	446.60	1,339.80
136	F/O 2'6"x6'8" Solid-Core Wood Door [REEB Saratoga Series]	1.00 EA	412.00	412.00
137	F/O 2'8"x6'8"Solid-Core Wood Door	6.00 EA	424.60	2,547.60
138	F/O 5'0"x6'8"Solid-Core Wood Doors (Pair)	1.00 EA	778.80	778.80
139	F/O Door Hardware	12.00 EA	250.00	3,000.00
140			**Wood Doors & HW Total**	**$8,078.20**
141	**08.1600 Residential Entry Doors & HW**			
142	F/O Residential Fiberglass Entry Door (36"x80"x6-9/16") ($2,500 Allowance Placeholder]	1.00 EA	2,500.00	2,500.00
143	F/O Residential Entry Door Deadlock/Door Knob Combo [$250/Each Allowance Placeholder]	1.00 EA	250.00	250.00
144			**Residential Entry Doors & HW Total**	**$2,750.00**
145	**08.5000 Windows**			
146	F/O Exterior Sliding French Door Pair	1.00 EA	3,200.00	3,200.00
147	F/O Marvin Elevate (Fixed) Windows	59.40 SF	65.00	3,861.00
148	F/O Marvin Elevate (Casement) Windows	49.53 SF	75.00	3,714.75
149			**Windows Total**	**$10,775.75**
150	**08.8300 Glass Shelving**			
151	F/I Glass Shelves	5.21 SF	100.00	521.00
152			**Glass Shelving Total**	**$521.00**
153	**08.8500 Shower Enclosures**			
154	F/I Shower Enclosure @ 1st Floor Shower	1.00 EA	1,800.00	1,800.00
155	F/I Shower Panel @ Master Bath	1.00 EA	1,600.00	1,600.00
156			**Shower Enclosures Total**	**$3,400.00**
157			**Openings Total**	**$25,524.95**
158	**09 Finishes**			
159	**09.2300 Drywall & Carpentry**			
160	F/I 1/2" GWB Walls	2,488.69 SF	3.25	8,088.24
161	F/I 1/2" GWB Ceilings	938.11 SF	3.25	3,048.86
162	I/O Bath Accessories	3.00 BATH	500.00	1,500.00

Line	Description	Quantity	Unit Cost	Total
163			**Drywall & Carpentry Total**	**$12,637.10**
164	**09.3013 Tile & Stone**			
165	F/I Linear Floor Drain	5.06 LF	50.00	253.00
166	F/I Floor Tile @ Shower	12.52 SF	27.00	338.02
167	F/I Floor Tile @ 1st Floor Bathrooms	86.01 SF	26.00	2,236.25
168	F/I Floor Tile @ Master Bath	119.15 SF	27.00	3,217.10
169	F/I Wall Tile @ Master Bath	416.32 SF	27.00	11,240.62
170	F/I Wall Tile @ Master Bath Walls (Full Height)	57.84 SF	27.00	1,561.64
171	F/I Wall Tile @ Master Bathroom (Full Height)	449.60 SF	27.00	12,139.20
172	F/I Mud Job @ 1st Floor Shower	1.00 EA	500.00	500.00
173	F/I Mud Job @ Master Shower	1.00 EA	1,200.00	1,200.00
174	F/I Waterproofing for Wall Tile	57.84 SF	5.25	303.66
175	F/I Waterproofing for Floor Tile	131.67 SF	5.25	691.27
176			**Tile & Stone Total**	**$33,680.76**
177	**09.6400 Wood Flooring**			
178	F/I Engineered Wood Flooring	1,923.76 SF	12.00	23,085.12
179			**Wood Flooring Total**	**$23,085.12**
180	**09.9100 Painting**			
181	Paint Existing Windows & Casing	4.00 EA	250.00	1,000.00
182	Stain Siding (Per GN-2)	796.40 SF	5.00	3,982.00
183	Paint GWB Walls	2,475.62 SF	1.30	3,218.32
184	Paint Existing GWB Walls	3,114.96 SF	1.50	4,672.44
185	Paint Base Molding	613.01 LF	3.50	2,145.55
186	Paint GWB Ceilings	852.82 SF	1.30	1,108.67
187	Paint Door Casing (Per LF)	16.33 LF	5.00	81.65
188	Paint/Stain Wood Doors & Casing	11.50 EA	225.00	2,587.50
189	Paint Window Casing	139.28 LF	5.00	696.40
190	Paint/Stain Existing Wood Door & Casing	5.00 EA	225.00	1,125.00
191	Prime & Paint Residential Fiberglass Entry Door	1.00 EA	350.00	350.00
192			**Painting Total**	**$20,967.53**
193			**Finishes Total**	**$90,370.51**
194	**10 Specialties**			
195	**10.2800 Bath Accessories (Supplied by Owner Per GN-2)**			
196	F/O Bath Accessories Budget (High-End Residential Master Bath)	2.00 EA	0.00	0.00
197	F/O Bath Accessories Budget (High-End Residential Guest Bath/Powder Room)	1.00 EA	0.00	0.00
198			**Bath Accessories (Supplied by Owner Per GN-2) Total**	**$0.00**
199			**Specialties Total**	**$0.00**
200	**11 Equipment**			
201	**11.3100 Appliances (Supplied by Owner Per GN-2)**			
202	Washer	1.00 EA	0.00	0.00

Line	Description	Quantity	Unit Cost	Total
203	Dryer	1.00 EA	0.00	0.00
204	Refrigerator	1.00 EA	0.00	0.00
205	Dishwasher	1.00 EA	0.00	0.00
206	Range	1.00 EA	0.00	0.00
207	Vent Hood Insert 30"	1.00 EA	0.00	0.00
208	**Appliances (Supplied by Owner Per GN-2) Total**			**$0.00**
209	**11.3200 Outdoor Kitchens/BBQs**			
210	F/I Outdoor Kitchen with Appliances & Fixtures	9.43 LF	3,200.00	30,176.00
211	**Outdoor Kitchens/BBQs Total**			**$30,176.00**
212	**Equipment Total**			**$30,176.00**
213	**12 Furnishing**			
214	**12.3600 Countertops**			
215	Template, Fabricate & Install Solid Surface Countertops @ Kitchen	72.63 SF	140.00	10,168.20
216	Template, Fabricate & Install Solid Surface Countertops @ Master Bath	9.98 SF	140.00	1,397.20
217	Template, Fabricate & Install Solid Surface Shelf @ Master Bath Half-Wall	2.10 SF	140.00	294.00
218	Template, Fabricate & Install Solid Surface Sill @ Master Shower	2.37 SF	140.00	331.80
219	Template, Fabricate & Install Solid Surface Backsplash	58.03 SF	140.00	8,124.20
220	**Countertops Total**			**$20,315.40**
221	**Furnishing Total**			**$20,315.40**
222	**22 Plumbing**			
223	**22.0000 Plumbing**			
224	F/I Gas Piping & Connection to Outdoor Grill	1.00 EA	2,500.00	2,500.00
225	Disconnect Existing Plumbing Fixtures	3.00 EA	150.00	450.00
226	I/O Residential Toilet	3.00 EA	2,500.00	7,500.00
227	I/O Bath Lav (Sink) & Faucet	4.00 EA	2,500.00	10,000.00
228	I/O Custom Shower@ 1st Floor	1.00 EA	3,250.00	3,250.00
229	I/O Custom Shower @ Master Bath	1.00 EA	3,600.00	3,600.00
230	I/O Freestanding Bathtub	1.00 EA	4,750.00	4,750.00
231	I/O Sink & Faucet	1.00 EA	2,500.00	2,500.00
232	I/O Appliance	2.00 EA	750.00	1,500.00
233	I/O Dishwasher	2.00 EA	2,250.00	4,500.00
234	F/I Refrigerator Waterline	1.00 EA	800.00	800.00
235	F/I Gas Piping & Connection for Range	1.00 EA	1,500.00	1,500.00
236	**Plumbing Total**			**$42,850.00**
237	**22.4000 Plumbing Fixtures (Supplied by Owner Per GN-2)**			
238	F/O Kitchen Sink	1.00 EA	0.00	0.00
239	F/O Kitchen Faucet	1.00 EA	0.00	0.00
240	F/O LAV Sink	4.00 EA	0.00	0.00
241	F/O Lav Faucet	4.00 EA	0.00	0.00
242	F/O Residential Toilet	3.00 EA	0.00	0.00
243	F/O Free-Standing Bathtub	1.00 EA	0.00	0.00

Line	Description	Quantity	Unit Cost	Total
244	F/O Standard Shower Kit	1.00 EA	0.00	0.00
245	F/O Custom Shower Kit @ 1st Floor	1.00 EA	0.00	0.00
246	F/O Custom Shower Kit @ Master Bath	1.00 EA	0.00	0.00
247	F/O Tub Filler/Faucet	1.00 EA	0.00	0.00
248	**Plumbing Fixtures (Supplied by Owner Per GN-2) Total**			**$0.00**
249	**Plumbing Total**			**$42,850.00**
250	**23 Heating, Ventilating and Air-Conditioning**			
251	**23.0000 HVAC**			
252	Provide Manual J Load Calcs w/Manual D Duct Design	1.00 LS	3,000.00	3,000.00
253	F/I 95% AFUE Gas Boiler	1.00 EA	10,500.00	10,500.00
254	Extend Existing Baseboard Heating to Addition	1.00 LS	7,000.00	7,000.00
255	F/I 16 SEER AC System w/Air Handler	3.50 TN	6,000.00	21,000.00
256	F/I Ductwork	6,600.00 SF	1.10	7,260.00
257	F/I Ductwork Insulation	6,600.00 SF	0.25	1,650.00
258	F/I Refrigerant Line Set	1.00 LS	1,500.00	1,500.00
259	F/I Condensate Drain Lines	1.00 LS	850.00	850.00
260	Testing & Programming	1.00 LS	2,500.00	2,500.00
261	F/I Thermostats	2.00 EA	500.00	1,000.00
262	Duct Exhaust Fan (Residential)	3.00 EA	300.00	900.00
263	**HVAC Total**			**$57,160.00**
264	**Heating, Ventilating and Air-Conditioning Total**			**$57,160.00**
265	**26 Electrical**			
266	**26.0000 Electric**			
267	Wire Mechanical Equipment (TBD)	1.00 LS	3,000.00	3,000.00
268	F/I Conduit Stubbed Out for Future Pool	1.00 LS	950.00	950.00
269	F/I Home Run + Standard Breaker	4.00 EA	235.00	940.00
270	F/I Home Run + Arc-Fault Breaker	19.00 EA	285.00	5,415.00
271	Home Run + Arc-Fault Breaker	1.00 EA	275.00	275.00
272	F/I Duplex Receptacle (Residential)	43.00 EA	115.00	4,945.00
273	F/I GFI Receptacle (Residential)	2.00 EA	115.00	230.00
274	F/I Weatherproof GFI Receptacle (Residential)	2.00 EA	230.00	460.00
275	I/O Lighting Fixture (Residential)	113.00 EA	195.00	22,035.00
276	I/O Lighting Fixture - CP-1	2.00 EA	195.00	390.00
277	I/O Lighting Fixture (Residential)	1.00 EA	185.00	185.00
278	I/O Lighting Fixture - CP-2	1.00 EA	185.00	185.00
279	I/O Ceiling Fan	1.00 EA	195.00	195.00
280	F/I Junction Box for Ceiling Fan	1.00 EA	170.00	170.00
281	F/I Junction Box for DW	1.00 EA	170.00	170.00
282	F/I Junction Box for Range	2.00 EA	170.00	340.00
283	F/I Junction Box for Grill Hood	1.00 EA	170.00	170.00
284	F/I Junction Box for Fireplace	1.00 EA	170.00	170.00

Line	Description	Quantity	Unit Cost	Total
285	Residential Exhaust Fan	3.00 EA	250.00	750.00
286	F/I 3-Way Switch (Residential)	3.00 EA	100.00	300.00
287	F/I LED Dimmer Switch (Residential)	15.00 EA	160.00	2,400.00
288	Electrical Disconnects Prior to Demo (Small)	1.00 EA	850.00	850.00
289			**Electric Total**	**$44,525.00**
290	**26.5000 Lighting Fixtures**			
291	F/O WS-3	9.00 EA	500.00	4,500.00
292	F/O WS-2	3.00 EA	500.00	1,500.00
293	F/O R-1 4"	68.00 EA	125.00	8,500.00
294	F/O R-1 MR 4"	25.00 EA	200.00	5,000.00
295	F/O R-2 4"	1.00 EA	200.00	200.00
296	F/O EWS-1	2.00 EA	500.00	1,000.00
297	F/O S-1	3.00 EA	500.00	1,500.00
298	F/O WS-1	2.00 EA	500.00	1,000.00
299	F/O EW-1	1.00 EA	500.00	500.00
300			**Lighting Fixtures Total**	**$23,700.00**
301			**Electrical Total**	**$68,225.00**
302	**28 Safety And Security**			
303	**28.4600 Fire Alarm**			
304	Smoke Detector	3.00 EA	250.00	750.00
305	Smoke/Carbon Monoxide Detector Combo	2.00 EA	300.00	600.00
306			**Fire Alarm Total**	**$1,350.00**
307			**Safety And Security Total**	**$1,350.00**
308	**32 Exterior Improvements**			
309	**32.1400 Hardscaping**			
310	F/I Bluestone Pavers (Including Hand Excavation & Gravel)	20.74 SF	60.00	1,244.40
311			**Hardscaping Total**	**$1,244.40**
312			**Exterior Improvements Total**	**$1,244.40**
313	**Sub-Total (Base Cost)**			**$577,938.63**

Estimate Summary



Material [$99,980]
Labor [$0]
SubContractor [$432,495]
Equipment [$0]
Other [$45,464]

Description		Total
Sub-Total (Base Cost)		$577,938.63
Material	10.0000%	9,997.97
Labor	30.0000%	0.00
SubContractor	25.0000%	108,123.68
Equipment	10.0000%	0.00
Other	10.0000%	4,546.43
Sub-Total (Direct Cost)		$700,606.70
OH&P	21.0000%	147,127.41
Total Estimate		$847,734.11