AREABUILDERS

Status: Active Estimates
Contact:
Date: 10/24/2025

Estimate: 250145 515 Madison Ave - 4th Floor

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**02 Existing Conditions**			
2	**02.1000 Demolition**			
3	Demolition	1.00 EA	0.00	0.00
4			**Demolition Total**	**$0.00**
5			**Existing Conditions Total**	**$0.00**
6	**03 Concrete**			
7	**03.1000 Concrete**			
8	Trenching & Patching for Electrical	60.83 LF	105.00	6,387.15
9	Core Drills for Concrete	25.00 EA	280.00	7,000.00
10	Trenching & Patching for Plumbing	27.00 LF	105.00	2,835.00
11			**Concrete Total**	**$16,222.15**
12			**Concrete Total**	**$16,222.15**
13	**06 Wood , Plastic and Composites**			
14	**06.2000 Convector Covers**			
15	F/I Convector Covers	175.75 LF	250.00	43,937.50
16			**Convector Covers Total**	**$43,937.50**
17	**06.2200 Millwork**			
18	F/I 1/2" Plywood w/Walnut Frame @ Petrified Moss Walls	118.22 SF	120.00	14,186.40
19	F/I Wood Slat Walls	763.14 SF	60.00	45,788.40
20	RFI#7 - F/I File Cabinet @ Reception Desk	1.00 EA	2,700.00	2,700.00
21	F/I Seating Nooks [Blocking + Plywood + PL-1 Laminate]	3.00 EA	5,400.00	16,200.00
22	F/I Millwork Panel @ Pantry Island Trash Pullout	3.78 SF	80.00	302.40
23	F/I 4-Tier Free Floating Shelves @ Pantry	5.52 LF	350.00	1,932.00
24	F/I HW-1 Lower Cabinets @ Pantry	13.52 LF	600.00	8,112.00
25	F/I Lower Cabinets @ Pantry Island	15.76 LF	800.00	12,608.00
26	F/I HW-1 Upper Cabinets @ Pantry	10.01 LF	550.00	5,505.50
27	F/I Wood Veneer Wall Panels	247.04 SF	100.00	24,704.00
28			**Millwork Total**	**$132,038.70**
29			**Wood , Plastic and Composites Total**	**$175,976.20**
30	**08 Openings**			
31	**08.1100 Doors, Frames & HW**			
32	F/O Hardware Set #3 (Electrified Storeroom)	1.00 EA	1,950.00	1,950.00
33	F/O Hardware Set #4 (Storeroom)	6.00 EA	1,465.00	8,790.00
34	F/O Hardware Set #5 (Sliding Door Hardware)	3.00 EA	755.00	2,265.00
35	F/O Hardware Set #6 (Passage)	2.00 EA	1,355.00	2,710.00
36	F/O Hardware Set #7 (Privacy)	6.00 EA	1,080.00	6,480.00
37	F/O Door Type C [Veneer Per RFI #24] + Aluminum Frame (Pair)	8.00 EA	2,800.00	22,400.00
38	F/O Door Type F [Veneer Per RFI #24] + HM KD Frame	2.00 EA	1,350.00	2,700.00
39	F/O Door Type D [Veneer Per RFI #24] + HM KD Frame	14.00 EA	1,350.00	18,900.00
40			**Doors, Frames & HW Total**	**$66,195.00**
41	**08.8200 Arch. Metal & Glass (By Owner)**			

Line	Description	Quantity	Unit Cost	Total
42	Arch. Metal & Glass	1.00 EA	0.00	0.00
43			**Arch. Metal & Glass (By Owner) Total**	**$0.00**
44			**Openings Total**	**$66,195.00**
45	**09 Finishes**			
46	**09.2300 Drywall & Carpentry**			
47	F/I Column Enclosure(s) (3/A-701)	2.00 EA	800.00	1,600.00
48	F/I Framing Supports / Niche Edges	3.00 EA	1,800.00	5,400.00
49	F/I Wood Blocking @ Vertical Slat Wall Locations	691.65 SF	7.00	4,841.55
50	F/I 5/8" GWB Walls (Level 4 Finish) @ Shaft Wall(s)	346.08 SF	4.25	1,470.84
51	F/I 5/8" GWB Walls (Level 4 Finish) @ PT-F	1,320.90 SF	4.25	5,613.83
52	F/I 5/8" GWB Walls (Two Layers on Each Side) (Level 4 Finish) @ PT-C	2,046.24 SF	3.50	7,161.84
53	F/I 5/8" GWB Walls (Level 4 Finish) @ PT-A	15,399.16 SF	4.25	65,446.43
54	F/I 5/8" GWB Ceilings (Level 4 Finish)	33.69 SF	3.50	117.92
55	F/I Wood Blocking Above Storefronts	231.95 LF	15.00	3,479.25
56	F/I Wood Blocking for Vertical Slats	15.47 LF	15.00	232.05
57	F/I Wood Blocking for Upper Cabinets & Free Floating Shelves	15.53 LF	15.00	232.95
58	F/I Wood Blocking for Bath Accessories (Per Bath)	7.00 EA	200.00	1,400.00
59	F/I Sound Attenuation Blanket Insulation @ PT-A	7,699.58 SF	2.00	15,399.16
60	F/I Blanket Insulation @ Shaft Wall(s)	346.08 SF	2.00	692.16
61	F/I Sound Attenuation Blanket Insulation @ PT-D	1,159.75 SF	2.00	2,319.50
62	F/I Sound Attenuation Blanket Insulation @ PT-F	1,320.90 SF	2.00	2,641.80
63	F/I 5/8" GWB Soffit(s) Above Storefront(s) PT-D	2,551.45 SF	7.00	17,860.15
64	I/O Bath Accessories	7.00 BATH	600.00	4,200.00
65	I/O Fire Extinguisher Cabinet	1.00 EA	200.00	200.00
66	I/O Interior HM Door, Frame & HW (Single)	16.00 EA	250.00	4,000.00
67	I/O Interior HM Doors, Frame & HW (Pair)	4.00 EA	250.00	1,000.00
68	F/I 3-5/8" Metal Stud Framing @ Shaft Wall(s)	346.08 SF	6.50	2,249.52
69	F/I 3-5/8" 18 Ga. Metal Stud Framing @ PT-A	7,699.58 SF	6.50	50,047.27
70	F/I 3-5/8" 18 Ga. Metal Stud Framing @ PT-F	1,320.90 SF	6.50	8,585.85
71	F/I 3-5/8" Metal Stud Framing	33.69 SF	6.50	218.99
72	F/I 3-5/8" 18 Ga. Metal Framed Soffit(s) Above Storefront(s) PT-D	1,159.75 SF	9.50	11,017.63
73	F/I 3-5/8" 18 Ga. Metal Stud Framing @ PT-C	511.56 SF	7.50	3,836.70
74	Access Panels	4.00 EA	300.00	1,200.00
75	Skim Coat GWB Walls in Preparation for Wallcovering	1,776.00 SF	5.00	8,880.00
76	F/I Acoustical Sealant @ PT-F	188.70 LF	1.50	283.05
77	F/I Acoustical Sealant @ PT-A	2,199.88 LF	1.50	3,299.82
78	F/I Acoustical Sealant @ PT-C	146.16 LF	1.50	219.24
79	F/I Acoustical Sealant @ Shaft Wall(s)	98.88 LF	1.50	148.32
80	F/I Shaftwall Liner Panel @ Shaft Wall(s)	346.08 SF	12.00	4,152.96
81			**Drywall & Carpentry Total**	**$239,448.78**
82	**09.2500 Acoustical Ceilings**			

Line	Description	Quantity	Unit Cost	Total
83	F/I ACT Ceiling Tiles [Armstrong #1942]	2,688.29 SF	6.50	17,473.89
84	F/I ACT Grid [Armstrong 9/16 Silhouette XL]	2,688.29 SF	5.00	13,441.45
85			**Acoustical Ceilings Total**	**$30,915.34**
86	**09.3013 Tile & Stone**			
87	F/I Schluter Strips @ Inside & Outside Corners	45.00 EA	120.00	5,400.00
88	F/I WT-2 Wall Tile (Full Height) [Cancas DOMTPB1310 Tropic Bianco 2x10]	663.03 SF	35.00	23,206.05
89	F/I WT-2 Wall Tile (4' High) [Cancas DOMTPB1310 Tropic Bianco 2x10]	751.52 SF	35.00	26,303.20
90	F/I Saddle/Threshold(s)	4.00 EA	150.00	600.00
91	F/I Waterproofing for Wall Tile	1,414.55 SF	5.25	7,426.39
92	RFI#10 F/I WT-1 @ Pantry Backsplash	24.00 SF	35.00	840.00
93	Template, Fabricate & Install ST-1 Solid Surface Countertop [Daltile One Quartz OQ42 Freedom Calacatta 3CM Polished]	66.22 SF	150.00	9,933.00
94	Template, Fabricate & Install ST-1 Solid Surface Countertop [Daltile One Quartz OQ42 Freedom Calacatta 3CM Polished]	55.02 SF	150.00	8,253.00
95			**Tile & Stone Total**	**$81,961.64**
96	**09.6000 Flooring**			
97	RFI #1 - Level Floors as Required	5,874.31 SF	2.00	11,748.62
98	F/I WB-1 Base [Patcraft TBD]	1,182.44 LF	5.50	6,503.42
99	F/I CONC Concrete Grind & Sealer	4,125.09 SF	7.50	30,938.18
100	F/I CPT-1 Carpet Tile [Patcraft Urban Relief TBD]	566.56 SY	75.00	42,492.00
101	F/I LVT [Mannington Amtico Beswick Oak AROW 8850]	1,238.82 SF	13.50	16,724.07
102	F/I LVT -> Concrete Transition Strip	6.37 LF	50.00	318.50
103	F/I Carpet -> Concrete Transition Strip	336.53 LF	50.00	16,826.50
104	F/I LVT -> Turf Transition Strip	48.80 LF	50.00	2,440.00
105			**Flooring Total**	**$127,991.29**
106	**09.6400 Wood Flooring**			
107	RFI #43 F/I Wood Flooring @ Elevator Lobby	154.31 SF	21.50	3,317.67
108			**Wood Flooring Total**	**$3,317.67**
109	**09.7200 Wall Coverings**			
110	F/I WC-2 Wallcovering [Carnegie Ion 6151W Color 38]	46.97 SY	75.00	3,522.75
111	F/I WC-1 Wallcovering [Carnegie Pave 8202 Color 2]	14.00 SY	150.00	2,100.00
112	F/I WC-3 Wallcovering [MDC MNX1054 Keane Morning Fog Natural Textiles 1]	136.37 SY	75.00	10,227.75
113			**Wall Coverings Total**	**$15,850.50**
114	**09.9100 Painting**			
115	Apply Intumescent Paint to Exposed Steel Columns (3-Hour Rating)	10.00 EA	2,500.00	25,000.00
116	Prep & Paint Existing Radiator Enclosures	175.75 LF	34.00	5,975.50
117	Paint GWB Walls	14,177.28 SF	1.30	18,430.46
118	Paint Existing GWB Walls	7,755.86 SF	1.30	10,082.62
119	Paint GWB Ceilings	164.56 SF	1.50	246.85
120	Paint/Stain Wood Door + HM Frame (Single)	14.00 EA	225.00	3,150.00
121	Paint HM Door & Frame (Single)	2.00 EA	175.00	350.00

Line	Description	Quantity	Unit Cost	Total
122	Paint HM Door & Frame (Pair)	4.00 EA	175.00	700.00
123	Prep & Paint Underside of Exposed Concrete Deck & Exposed Piping/Ductwork	7,870.65 SF	4.25	33,450.26
124	Paint GWB Soffit(s) Above Storefront(s)	1,391.70 SF	2.15	2,992.16
125			**Painting Total**	**$100,377.85**
126			**Finishes Total**	**$599,863.07**
127	**10 Specialties**			
128	**10.0000 Petrified Moss Wall (By Owner)**			
129	Specialties	1.00 EA	0.00	0.00
130			**Petrified Moss Wall (By Owner) Total**	**$0.00**
131	**10.2800 Bath Accessories**			
132	F/O Grab Bars (Snap Flange) [American Specialties Model #Snap Flange Matte Black]	4.00 EA	55.00	220.00
133	F/O Mirror Over Sink (24" x 30") [Bobrick Model #290.MBLK Matte Black]	2.00 EA	140.00	280.00
134	F/O Toilet Seat Cover Dispenser [Bobrick Model #221.MBLK Matte Black]	4.00 EA	55.00	220.00
135	F/O Paper Towel Dispenser/Waste Receptacle [Bobrick Model #B-36903 Matte Black]	2.00 EA	415.00	830.00
136	F/O Paper Towel Dispenser/Waste Receptacle [Kohler Model #Verticyl K-2882 w/ Bissonnet Trap #135551 White/Polished Chrome]	2.00 EA	225.00	450.00
137	F/O Surface-Mounted Sanitary Napkin Disposal (Trimline Series) [Bobrick Model #Trimline Series Matte Black]	2.00 EA	135.00	270.00
138	F/O Full-Length Mirror (71" x 28") [Neutype Model #Rachel 71x28 Black]	2.00 EA	150.00	300.00
139	F/O Toilet Tissue Dispenser w/ Shelf (Cubicle Multi Roll) [Bobrick Model #Cubicle Multi Roll Matte Black]	4.00 EA	55.00	220.00
140	F/O Soap Dispenser [Bobrick Model #B-2012-MBLK Matte Black]	2.00 EA	55.00	110.00
141			**Bath Accessories Total**	**$2,900.00**
142	**10.2900 Urinal Screens**			
143	F/I SS Urinal Screen(s)	2.00 EA	2,200.00	4,400.00
144			**Urinal Screens Total**	**$4,400.00**
145	**10.4400 Fire Protection Specialties**			
146	Fire Extinguisher Cabinet + FE	1.00 EA	350.00	350.00
147			**Fire Protection Specialties Total**	**$350.00**
148			**Specialties Total**	**$7,650.00**
149	**12 Furnishing**			
150	**12.2000 Window Treatments**			
151	F/I RB-1 Roller Blinds [Hunter Douglas White Sheerwave 2000 5% Openness]	102.95 LF	165.00	16,986.75
152			**Window Treatments Total**	**$16,986.75**
153	**12.5619 Upholstered Seating**			
154	F/I Foam Cushion [3" Resilience Polyurethane Foam, Tapered to Seat Geometry]	21.64 LF	200.00	4,328.00
155	F/I Fabrics FB-1 - FB-2	21.64 LF	250.00	5,410.00
156			**Upholstered Seating Total**	**$9,738.00**
157			**Furnishing Total**	**$26,724.75**

Line	Description	Quantity	Unit Cost	Total
158	**21 Fire Suppression**			
159	**21.0000 Sprinkler**			
160	Sprinkler	1.00 EA	0.00	0.00
161			**Sprinkler Total**	**$0.00**
162			**Fire Suppression Total**	**$0.00**
163	**22 Plumbing**			
164	**22.0000 Plumbing (By Owner)**			
165	Plumbing Item	0.00 EA	0.00	0.00
166			**Plumbing (By Owner) Total**	**$0.00**
167			**Plumbing Total**	**$0.00**
168	**23 Heating, Ventilating and Air-Conditioning**			
169	**23.0000 HVAC (By Owner)**			
170	HVAC Item	0.00 EA	0.00	0.00
171			**HVAC (By Owner) Total**	**$0.00**
172			**Heating, Ventilating and Air-Conditioning Total**	**$0.00**
173	**26 Electrical**			
174	**26.0000 Electric**			
175	Electric	4.00 EA	0.00	0.00
176			**Electric Total**	**$0.00**
177			**Electrical Total**	**$0.00**
178	**Sub-Total (Base Cost)**			**$892,631.17**

Estimate Summary

Material [$2,356]
Labor [$0]
SubContractor [$890,275]
Equipment [$0]
Other [$0]

Description		Total
Sub-Total (Base Cost)		$892,631.17
Sub-Total (Direct Cost)		$892,631.17
General Conditions	12.0000%	107,115.74
Fee	6.0000%	59,984.81
Insurance	2.5000%	26,493.29
Sub-Total ()		$1,086,225.02
Alternate #1: F/I Epoxy Flooring in lieu of Sealed Concrete		19,500.00
Total Estimate		$1,105,725.02