Estimate: 250068 Consalvo Residence

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**02 Existing Conditions**			
2	**02.1500 Containers/Waste Removal**			
3	30-Yard Containers	12.00 EA	850.00	10,200.00
4			**Containers/Waste Removal Total**	**$10,200.00**
5			**Existing Conditions Total**	**$10,200.00**
6	**03 Concrete**			
7	**03.1000 Concrete**			
8	Form & Pour Concrete Footings	7.63 CY	625.00	4,768.75
9	Form & Pour Concrete Footings	15.14 CY	630.00	9,538.20
10	Form & Pour Concrete Frost Wall(s)	14.50 CY	625.00	9,062.50
11	Form & Pour Concrete Full-Height Foundation Wall(s)	64.75 CY	630.00	40,792.50
12	Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.	54.15 CY	585.00	31,677.75
13	Form & Pour Concrete 8" Concrete Apron @ Garage. F/I All Applicable Rebar, Vapor Barrier & Mesh.	8.65 CY	600.00	5,190.00
14	Form & Pour 30"x30"x12" Spread Footings	3.75 CY	1,050.00	3,937.50
15	Pump Truck	2.00 EA	1,800.00	3,600.00
16	F/O Sonotube Forms	19.00 EA	20.35	386.65
17	F/O Quikrete 80lb Bag	69.16 BAG	6.50	449.54
18	I/O Sonotube Deck Footings (Per Hour)	57.00 HR	75.00	4,275.00
19			**Concrete Total**	**$113,678.39**
20			**Concrete Total**	**$113,678.39**
21	**04 Masonry**			
22	**04.5710 Brick**			
23	F/I 2" Rigid Insulation	4,359.65 SF	2.50	10,899.13
24	F/I Full-Brick Veneer ($10/SF Material Allowance)	4,359.65 SF	36.00	156,947.45
25			**Brick Total**	**$167,846.58**
26			**Masonry Total**	**$167,846.58**
27	**06 Wood , Plastic and Composites**			
28	**06.2000 Finish Carpentry**			
29	F/I Tray Ceiling @ Master Bedroom	263.61 SF	20.00	5,272.20
30	F/I Tray Ceiling @ Dining Room	159.58 SF	20.00	3,191.60
31	I/O Interior Wood Door & F/I Trim	24.00 EA	225.00	5,400.00
32	I/O Barn Style Door	4.00 EA	400.00	1,600.00
33	F/I Base Molding	1,357.07 LF	9.00	12,213.63
34	F/I Door Casing	731.00 LF	9.00	6,579.00
35	F/I Door Casing	128.99 LF	8.00	1,031.92
36	F/I Window Casing	328.14 LF	9.00	2,953.26
37			**Finish Carpentry Total**	**$38,241.61**
38	**06.2200 Millwork**			
39	F/I Lower Cabinets @ Kitchen ($300/LF Material Allowance)	20.98 LF	425.00	8,916.50
40	F/I Lower Cabinets @ Pantry ($300/LF Material Allowance)	4.96 LF	425.00	2,108.00

Line	Description	Quantity	Unit Cost	Total
41	F/I Lower Cabinets @ Laundry ($300/LF Material Allowance)	13.64 LF	425.00	5,797.00
42	F/I Upper Cabinets @ Kitchen ($300/LF Material Allowance)	16.49 LF	375.00	6,183.75
43	F/I Upper Cabinets @ Laundry ($300/LF Material Allowance)	14.41 LF	375.00	5,403.75
44	F/I Kitchen Islands @ Kitchen ($450/LF Material Allowance)	9.09 LF	575.00	5,226.75
45	F/I Full-Height Cabinets @ Kitchen ($450/LF Material Allowance)	2.89 LF	625.00	1,806.25
46	F/I Full-Height Cabinets @ Laundry ($450/LF Material Allowance)	2.05 LF	625.00	1,281.25
47	F/I Vanities ($350/LF Material Allowance)	21.69 LF	475.00	10,302.75
48			**Millwork Total**	**$47,026.00**
49	**06.2300 Closet Interiors**			
50	F/I Closet Interiors (Hat Shelf & Rod)	29.07 LF	75.00	2,180.25
51	F/I Closet Interiors (Master WIC)	50.18 LF	325.00	16,308.50
52	F/I Closet Interiors (Pantry)	25.88 LF	225.00	5,823.00
53	F/I Closet Interiors (Linen Closet)	1.74 LF	175.00	304.50
54			**Closet Interiors Total**	**$24,616.25**
55	**06.4001 Wood Framing Materials**			
56	F/O 2x4 PT	780.84 LF	1.90	1,480.47
57	F/O 2x4 DF	1,561.68 LF	1.63	2,548.67
58	F/O 2x4 Studs	4,639.30 LF	1.61	7,459.99
59	F/O 2x6 PT	637.32 LF	2.29	1,460.73
60	F/O 2x6 DF	1,656.77 LF	1.85	3,061.70
61	F/O 2x6 Studs	4,626.50 LF	1.85	8,549.78
62	F/O 2x10 DF	991.79 LF	4.10	4,070.31
63	F/O (2) 2x12 DF Headers	36.04 LF	3.80	137.10
64	F/O (3) 2x12 DF Headers	14.34 LF	3.80	54.56
65	F/O 6"x6"x12' PT Post	7.00 EA	57.95	405.65
66	F/O 1-3/4" x 9-1/4" LVL Window Header	15.76 LF	7.43	117.05
67	F/O 1-3/4" x 9-1/2" LVL	50.72 LF	7.43	376.72
68	F/O 1-3/4"x14" LVL 1.9E	974.30 LF	11.56	11,259.01
69	F/O 1-3/4" x 16" 2.0E LVL	49.92 LF	15.81	789.00
70	F/O 1-3/4" X 18" LVL 19.E	79.28 LF	13.20	1,046.54
71	F/O 4x8x1/2" CDX Fir Plywood	3,829.60 SF	1.98	7,600.32
72	F/O 4x8x5/8" CDX Fir Plywood	4,622.36 SF	2.02	9,338.07
73	F/O 4x8x5/8" CDX Fir Plywood	2,040.44 SF	2.22	4,522.21
74	F/O 4x8x3/4" TG Advantech Plywood	1,181.74 SF	2.09	2,470.05
75	F/O Termite shield (6" x 25' Aluminum Roll)	382.96 LF	0.85	325.85
76	F/O FormSealR 5-1/2" x 50' Sill Seal	382.96 LF	0.31	120.00
77	F/O Lolly Column	13.00 EA	215.00	2,795.00
78	F/O Open-Web Wood Floor Trusses	3,626.16 SF	9.62	34,883.66
79	F/O Wood Roof Trusses (Scissor)	6,662.80 SF	15.00	99,942.00
80	F/O Simpson ABU66Z Post Base	26.00 EA	50.00	1,300.00
81	F/O 1"x8"x8' Fascia Board	474.47 LF	1.26	599.28

Line	Description	Quantity	Unit Cost	Total
82			**Wood Framing Materials Total**	**$206,713.72**
83	**06.4002 Wood Framing Labor**			
84	I/O Lolly Columns	15.00 EA	75.00	1,125.00
85	I/O Door D19	1.00 EA	300.00	300.00
86	I/O Door D20	1.00 EA	300.00	300.00
87	I/O Interior Framed Wall	9,708.80 SF	3.00	29,126.40
88	I/O Floor Framing (Joists & Subfloor)	1,181.74 SF	4.50	5,317.83
89	I/O Exterior Wall Framing & Sheathing @ 1st Floor	3,829.60 SF	4.50	17,233.20
90	I/O Roof Trusses & Sheathing	6,662.80 SF	6.00	39,976.80
91	I/O Wood Floor Trusses	3,626.16 SF	3.00	10,878.48
92	Crane Rental (Per Week)	2.00 WK	2,500.00	5,000.00
93	I/O Deck Post	26.00 EA	45.00	1,170.00
94	I/O Residential Exterior Door & Hardware	4.00 EA	400.00	1,600.00
95	I/O Window(s)	18.00 EA	200.00	3,600.00
96	I/O LVL/PSL Beams (Larger Beams (=> 12") w/Bracing | Notching)	702.48 LF	8.00	5,619.84
97			**Wood Framing Labor Total**	**$121,247.55**
98	**06.4300 Wood Stairs And Railings**			
99	F/I White Oak Stairs w/Poplar Strings & Risers @ Garage	2.00 EA	303.03	606.06
100	F/I White Oak Stairs w/Poplar Strings & Risers	31.00 EA	303.03	9,393.94
101			**Wood Stairs And Railings Total**	**$10,000.00**
102	**06.6600 Cedar Decking & Framing**			
103	F/O 2x8 PT (Deck Outer Joist)	303.65 LF	3.14	954.68
104	F/O 2x8 PT (Deck Joist)	1,162.25 LF	3.14	3,654.11
105	F/O Simpson Strong Tie LU28 2x8 Deck Joist Hangers	116.04 EA	2.59	273.90
106	F/O 2x12 PT Deck Girder	138.28 LF	4.67	645.47
107	F/O 9" Grace Vycor Plus Deck Flashing	110.66 LF	0.99	101.18
108	F/I 5/4"x6"x12' STK Cedar Decking	1,544.55 SF	17.54	27,083.72
109	F/O 1/2" X 6" Lag Bolt	41.44 EA	0.55	22.79
110	I/O Deck Framing	1,549.67 SF	10.00	15,496.70
111			**Cedar Decking & Framing Total**	**$48,232.55**
112			**Wood , Plastic and Composites Total**	**$496,077.68**
113	**07 Thermal and Moisture Protection**			
114	**07.1000 Waterproofing**			
115	F/I Foundation Waterproofing [Rub-R-Wall Membrane w/2" XPS (R-10) Foam Board Application]	3,189.29 SF	6.30	20,092.53
116			**Waterproofing Total**	**$20,092.53**
117	**07.2000 Insulation**			
118	F/I R-19 Fiberglass Batt	4,078.80 SF	1.19	4,853.77
119	F/I R-25 Fiberglass Batt	3,829.60 SF	2.00	7,659.20
120	F/I R-49 Cellulose Spray-Foam	4,622.36 SF	9.20	42,525.71
121	F/I R-49 Spray-Foam	2,040.44 SF	9.20	18,772.05

Line	Description	Quantity	Unit Cost	Total
122			**Insulation Total**	**$73,810.73**
123	**07.3000 Roofing**			
124	F/I 3-Tab Asphalt Roof Shingles + Ice & Water Shield/Drip Edge & Ridge Cap	6,662.80 SF	5.35	35,645.98
125			**Roofing Total**	**$35,645.98**
126	**07.6600 Gutters & Leaders**			
127	F/I 5" K-Style Gutters	197.68 LF	8.50	1,680.28
128	F/I 5" K-Style Leaders	105.97 LF	8.50	900.75
129			**Gutters & Leaders Total**	**$2,581.03**
130	**07.9510 Siding**			
131	F/I Versawrap Column Wrap(s)	10.00 EA	395.00	3,950.00
132	F/I James Hardie Board & Batten	1,015.78 SF	12.50	12,697.25
133	F/I 1"x4"x12' Azek Trim	426.80 LF	10.77	4,598.06
134	F/I 1"x6"x12' Azek Trim	74.24 LF	15.13	1,122.96
135	F/I 1"x10'x12' Azek Trim	609.33 LF	16.56	10,091.87
136	F/I 12" Vinyl Soffits	474.86 LF	8.48	4,025.88
137	F/I Tyvek Housewrap	3,829.60 SF	1.49	5,692.60
138			**Siding Total**	**$42,178.62**
139			**Thermal and Moisture Protection Total**	**$174,308.89**
140	**08 Openings**			
141	**08.1400 Wood Doors & HW**			
142	F/O Solid-Core Wood Door ($550/Each Allowance)	21.00 EA	550.00	11,550.00
143	F/O Solid-Core Wood Doors (Pair) ($1,100/Each Allowance)	2.00 EA	1,100.00	2,200.00
144	F/O Door Hardware ($200/Each Allowance)	25.00 EA	200.00	5,000.00
145	F/O Barn Style Door ($3,500/Each Allowance)	3.00 EA	3,500.00	10,500.00
146	F/O Barn Style Door (Pair) ($5,500/Each Allowance)	1.00 EA	5,500.00	5,500.00
147			**Wood Doors & HW Total**	**$34,750.00**
148	**08.1600 Residential Entry Doors & HW**			
149	F/O Residential Fiberglass Entry Door (36"x80"x6-9/16") ($1000/Each Allowance Placeholder]	3.00 EA	1,000.00	3,000.00
150	F/O Residential Wood Entry Door (36"x80"x9-1/6") ($1,500 Allowance Placeholder]	1.00 EA	1,500.00	1,500.00
151	F/O Residential Entry Door Deadlock/Door Knob Combo [$50/Each Allowance Placeholder]	4.00 EA	50.00	200.00
152			**Residential Entry Doors & HW Total**	**$4,700.00**
153	**08.3700 Garage Doors (Budget)**			
154	F/I Garage Doors	3.00 EA	7,500.00	22,500.00
155			**Garage Doors (Budget) Total**	**$22,500.00**
156	**08.5000 Windows**			
157	F/O Andersen 400 Series Windows	361.36 SF	70.00	25,295.20
158	F/O Exterior Door D19	1.00 EA	3,000.00	3,000.00
159	F/O Exterior Door D20	1.00 EA	3,000.00	3,000.00

Line	Description	Quantity	Unit Cost	Total
160	F/O Mulled Exterior Doors @ Deck [Andersen FWGD151080-4 + FWTD1-4010 (4)]	1.00 EA	15,000.00	15,000.00
161			**Windows Total**	**$46,295.20**
162	**08.8500 Shower Enclosures**			
163	F/I Shower Enclosure	1.00 EA	2,250.00	2,250.00
164	F/I Shower Enclosure	2.00 EA	3,600.00	7,200.00
165			**Shower Enclosures Total**	**$9,450.00**
166			**Openings Total**	**$117,695.20**
167	**09 Finishes**			
168	**09.2300 Drywall & Carpentry**			
169	F/I 1/2" GWB Walls	15,767.93 SF	2.40	37,843.03
170	F/I 1/2" GWB Walls w/Vapor Barrier	3,708.00 SF	3.40	12,607.20
171	F/I 1/2" GWB Ceilings	3,275.68 SF	2.45	8,025.42
172	F/I 1/2" GWB Ceilings	6,626.36 SF	3.00	19,879.08
173	F/I 5/8" GWB Ceilings	1,299.91 SF	3.00	3,899.73
174	I/O Bath Accessories	4.00 BATH	500.00	2,000.00
175			**Drywall & Carpentry Total**	**$84,254.46**
176	**09.3013 Tile & Stone**			
177	F/I Floor Tile @ Powder Room ($8/SF Material Allowance)	21.93 SF	23.80	521.91
178	F/I Floor Tile @ Bath 3 ($8/SF Material Allowance)	73.34 SF	23.80	1,745.46
179	F/I Floor Tile @ Bath 2 ($8/SF Material Allowance)	49.74 SF	23.80	1,183.78
180	F/I Floor Tile @ Bath 2 Shower ($8/SF Material Allowance)	14.23 SF	23.80	338.65
181	F/I Floor Tile @ Master Bath ($8/SF Material Allowance)	174.21 SF	23.80	4,146.19
182	F/I Floor Tile @ Master Bath Shower ($8/SF Material Allowance)	22.13 SF	19.40	429.31
183	F/I Floor Tile @ Mudroom ($8/SF Material Allowance)	36.57 SF	23.80	870.39
184	F/I Wall Tile @ Bath 3 Shower Walls ($4/SF Material Allowance)	104.20 SF	19.40	2,021.48
185	F/I Wall Tile @ Powder Room Sink Wall ($4/SF Material Allowance)	35.70 SF	19.40	692.58
186	F/I Full-Height Wall Tile @ Master Bath Walls ($4/SF Material Allowance)	777.70 SF	19.40	15,087.38
187	F/I 4' H Wall Tile @ Bath 2 ($4/SF Material Allowance)	106.88 SF	19.40	2,073.48
188	F/I Full-Height Wall Tile @ Bath 2 Shower ($4/SF Material Allowance)	108.10 SF	19.40	2,097.14
189	F/I 4' High Wall Tile @ Bath 2 ($4/SF Material Allowance)	174.88 SF	19.40	3,392.68
190	F/I Marble Saddles	6.00 EA	150.00	900.00
191	F/I Tile Flooring @ Entry Vestibule ($10/SF Material Allowance)	87.77 SF	26.00	2,282.05
192	F/I Mud Job at Shower	2.00 EA	600.00	1,200.00
193	F/I Waterproofing for Wall Tile	990.00 SF	4.50	4,455.00
194	F/I Waterproofing for Floor Tile	210.57 SF	4.50	947.58
195			**Tile & Stone Total**	**$44,385.06**
196	**09.6400 Wood Flooring**			
197	F/I Wood Flooring ($10/SF Material Allowance)	3,428.90 SF	18.50	63,434.65
198			**Wood Flooring Total**	**$63,434.65**
199	**09.9100 Painting**			

Line	Description	Quantity	Unit Cost	Total
200	Paint GWB Walls	19,013.45 SF	1.30	24,717.48
201	Paint Base Molding	1,357.07 LF	3.50	4,749.75
202	Paint GWB Ceilings	11,083.78 SF	1.50	16,625.67
203	Paint Door Casing	60.94 LF	5.00	304.70
204	Paint Door Casing (Per LF)	65.99 LF	5.00	329.95
205	Paint/Stain Wood Doors & Casing	24.00 EA	225.00	5,400.00
206	Paint Window Casing	328.14 LF	5.00	1,640.70
207	Prime & Paint Residential Fiberglass Entry Door	4.00 EA	350.00	1,400.00
208			**Painting Total**	**$55,168.25**
209			**Finishes Total**	**$247,242.42**
210	**10 Specialties**			
211	**10.2800 Bath Accessories (Budget)**			
212	Bath Accessories Budget (High-End Residential Master Bath)	1.00 EA	2,000.00	2,000.00
213	Bath Accessories Budget (High-End Residential Guest Bath/Powder Room)	3.00 EA	1,000.00	3,000.00
214			**Bath Accessories (Budget) Total**	**$5,000.00**
215	**10.3100 Fireplace (Budget)**			
216	Fireplace Allowance	1.00 LS	15,000.00	15,000.00
217			**Fireplace (Budget) Total**	**$15,000.00**
218			**Specialties Total**	**$20,000.00**
219	**11 Equipment**			
220	**11.3100 Appliances (Budget)**			
221	F/O Wall Oven	1.00 EA	1,500.00	1,500.00
222	F/O Washer	1.00 EA	2,200.00	2,200.00
223	F/O Dryer	1.00 EA	2,100.00	2,100.00
224	F/O Refrigerator	1.00 EA	5,000.00	5,000.00
225	F/O Dishwasher	1.00 EA	1,500.00	1,500.00
226	F/O Range	1.00 EA	6,000.00	6,000.00
227	F/O Microwave Drawer	1.00 EA	1,500.00	1,500.00
228			**Appliances (Budget) Total**	**$19,800.00**
229			**Equipment Total**	**$19,800.00**
230	**12 Furnishing**			
231	**12.3600 Countertops**			
232	Template, Fabricate & Install Solid Surface Countertops @ Kitchen ($55/SF Material Allowance)	79.69 SF	120.00	9,562.80
233	Template, Fabricate & Install Solid Surface Countertops @ Pantry($55/SF Material Allowance)	10.61 SF	120.00	1,273.20
234	Template, Fabricate & Install Solid Surface Countertops @ Laundry($55/SF Material Allowance)	36.29 SF	120.00	4,354.80
235	Template, Fabricate & Install Solid Surface Countertops @ Vanities ($55/SF Material Allowance)	36.15 SF	120.00	4,338.00
236	Template, Fabricate & Install Solid Surface Backsplash @ Kitchen($55/SF Material Allowance)	71.79 SF	120.00	8,614.80

Line	Description	Quantity	Unit Cost	Total
237			**Countertops Total**	**$28,143.60**
238			**Furnishing Total**	**$28,143.60**
239	**22 Plumbing**			
240	**22.0000 Plumbing**			
241	F/I Gas Connection to Wall Oven	1.00 EA	2,500.00	2,500.00
242	I/O Residential Toilet	4.00 EA	2,500.00	10,000.00
243	I/O Bath Lav (Sink) & Faucet	6.00 EA	2,500.00	15,000.00
244	I/O Custom Shower	2.00 EA	3,500.00	7,000.00
245	I/O Standard Bathtub	1.00 EA	2,500.00	2,500.00
246	I/O Freestanding Bathtub	1.00 EA	3,000.00	3,000.00
247	I/O Sink & Faucet	2.00 EA	2,500.00	5,000.00
248	I/O Appliance	2.00 EA	700.00	1,400.00
249	I/O Dishwasher	3.00 EA	800.00	2,400.00
250	F/I Refrigerator Waterline	1.00 EA	800.00	800.00
251	F/I Gas Piping & Connection for Range	1.00 EA	2,500.00	2,500.00
252	F/I Residential Hot Water Heater (HWH)	1.00 EA	4,500.00	4,500.00
253			**Plumbing Total**	**$56,600.00**
254	**22.4000 Plumbing Fixtures (Budget)**			
255	F/O Kitchen Sink	1.00 EA	1,500.00	1,500.00
256	F/O Pantry Sink	1.00 EA	1,200.00	1,200.00
257	F/O Kitchen Faucet	1.00 EA	1,500.00	1,500.00
258	F/O Pantry Faucet	1.00 EA	1,500.00	1,500.00
259	F/O Lav Sink	6.00 EA	600.00	3,600.00
260	F/O Lav Faucet	6.00 EA	500.00	3,000.00
261	F/O Residential Toilet	4.00 EA	500.00	2,000.00
262	F/O Standard Bathtub	1.00 EA	1,000.00	1,000.00
263	F/O Free-Standing Bathtub	1.00 EA	2,000.00	2,000.00
264	F/O Standard Shower Kit	1.00 EA	1,200.00	1,200.00
265	F/O Standard Shower Kit	1.00 EA	1,000.00	1,000.00
266	F/O Custom Shower Kit	2.00 EA	2,800.00	5,600.00
267	F/O Tub Filler/Faucet	1.00 EA	1,325.00	1,325.00
268			**Plumbing Fixtures (Budget) Total**	**$26,425.00**
269			**Plumbing Total**	**$83,025.00**
270	**23 Heating, Ventilating and Air-Conditioning**			
271	**23.0000 HVAC (By Owner)**			
272	HVAC	1.00 EA	0.00	0.00
273			**HVAC (By Owner) Total**	**$0.00**
274			**Heating, Ventilating and Air-Conditioning Total**	**$0.00**
275	**26 Electrical**			
276	**26.0000 Electric**			
277	Electric Budget (Per SF)	3,809.00 SF	10.50	40,000.00

Line	Description	Quantity	Unit Cost	Total
278			**Electric Total**	**$40,000.00**
279	**26.5000 Lighting Fixtures**			
280	Lighting Fixture Budget (Hi Hats Only)	3,809.00 SF	2.75	10,474.75
281			**Lighting Fixtures Total**	**$10,474.75**
282			**Electrical Total**	**$50,474.75**
283	**27 Communications**			
284	**27.1020 Audio Visual (NIC)**			
285	Audio/Visual	1.00 EA	0.00	0.00
286			**Audio Visual (NIC) Total**	**$0.00**
287			**Communications Total**	**$0.00**
288	**28 Safety And Security**			
289	**28.4610 Security (NIC)**			
290	Security	1.00 EA	0.00	0.00
291			**Security (NIC) Total**	**$0.00**
292			**Safety And Security Total**	**$0.00**
293	**31 Sitework**			
294	**31.0000 Earthwork**			
295	Excavate Foundation (Slab on Grade)	1.95 DAY	2,600.00	5,070.00
296	Excavate Foundation (Frost Walls)	4.51 DAY	2,600.00	11,726.00
297	Backfill Frost Walls	2.71 DAY	2,600.00	7,046.00
298	Backfill Slab & Compact	2.43 DAY	2,600.00	6,318.00
299	F/I Crushed Stone	109.63 CY	105.00	11,511.15
300			**Earthwork Total**	**$41,671.15**
301	**31.1100 Drainage & Stormwater**			
302	F/I 4" Footing Drain	432.33 LF	22.00	9,511.26
303	F/I 4" Drain @ Foundation Walls	316.88 LF	22.00	6,971.36
304	F/I 4" Under Slab Drain	417.31 LF	22.00	9,180.82
305			**Drainage & Stormwater Total**	**$25,663.44**
306	**31.2500 Erosion And Sedimentation Controls**			
307	F/I Silt Fence	250.00 LF	6.00	1,500.00
308	F/I Construction Entrance	1.00 EA	2,000.00	2,000.00
309			**Erosion And Sedimentation Controls Total**	**$3,500.00**
310			**Sitework Total**	**$70,834.59**
311	**32 Exterior Improvements**			
312	**32.9300 Landscaping (NIC)**			
313	Landscaping	1.00 EA	0.00	0.00
314			**Landscaping (NIC) Total**	**$0.00**
315			**Exterior Improvements Total**	**$0.00**
316	**Sub-Total (Base Cost)**			**$1,599,327.10**

Estimate Summary



Material [$222,469]
Labor [$0]
SubContractor [$1,314,010]
Equipment [$0]
Other [$62,848]

Description		Total
Sub-Total (Base Cost)		$1,599,327.10
Material	10.0000%	22,246.93
Labor	30.0000%	0.00
SubContractor	5.0000%	65,700.48
Other	5.0000%	3,142.41
Sub-Total (Direct Cost)		$1,690,416.92
General Conditions	10.0000%	169,041.69
Overhead & Profit	7.5000%	139,459.40
Insurance	2.5000%	49,972.95
Total Estimate		$2,048,890.96