Estimate: 24005602 DentaPrime Rev. 3

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**03 Concrete**			
2	**03.1000 Concrete**			
3	F/I Concrete Curb @ Ovens/Sinters RM 122	1.00 EA	1,200.00	1,200.00
4			**Concrete Total**	**$1,200.00**
5			**Concrete Total**	**$1,200.00**
6	**06 Wood , Plastic and Composites**			
7	**06.2200 Millwork**			
8	F/I Custom Table @ Meeting Room 129	3.64 LF	700.00	2,548.00
9	F/I Custom Ovens/Sinters Cabinetry	11.30 LF	750.00	8,475.00
10	F/I Cabinetry @ Lab 133	11.86 LF	700.00	8,302.00
11	F/I Custom Lab Admin Desk	1.66 LF	950.00	1,577.00
12	F/I Custom Sandblaster Desk	1.39 LF	950.00	1,320.50
13	F/I Custom Scanner Desk	1.83 LF	950.00	1,738.50
14	F/I Custom Designer Desks	7.09 LF	950.00	6,735.50
15	F/I Custom 3D Printer Operator Desk	6.93 LF	950.00	6,583.50
16	F/I Custom CAD CAM Operator Desk	3.50 LF	950.00	3,325.00
17	F/I Custom Contract Desks @ Contract Room 124	6.86 LF	950.00	6,517.00
18	F/I Custom Desks @ Office 128	10.23 LF	450.00	4,603.50
19	F/I Custom Printer Cabinets @ Office 128	2.71 LF	950.00	2,574.50
20	F/I Fixed ADA Bench	2.00 EA	1,800.00	3,600.00
21	F/I CT Operator Desk	3.58 LF	950.00	3,401.00
22	F/I Custom Reception Desk	1.00 EA	18,000.00	18,000.00
23	F/I Custom Patient Lockers	1.00 EA	1,800.00	1,800.00
24	F/I Custom Trash Receptacle	1.00 EA	1,600.00	1,600.00
25	F/I Custom Tables & Stools @ Canteen 109	4.38 LF	700.00	3,066.00
26	F/I MDF Backboard @ Gypsum Cabinets	38.08 SF	70.00	2,665.60
27	F/I Lower Cabinets @ Treatment RM 6	4.46 LF	600.00	2,676.00
28	F/I Lower Cabinets @ Treatment RM 3	4.44 LF	600.00	2,664.00
29	F/I Lower Cabinets @ Treatment RM 5	4.47 LF	600.00	2,682.00
30	F/I Lower Cabinets @ Treatment RM 4	4.47 LF	600.00	2,682.00
31	F/I Lower Cabinets @ Treatment RM 2	4.47 LF	600.00	2,682.00
32	F/I Lower Cabinets @ Treatment RM 1	4.47 LF	600.00	2,682.00
33	F/I Lower Cabinets @ Isoproponal Room 132	7.73 LF	600.00	4,638.00
34	F/I Lower Cabinets @ Gypsum Room 103	31.78 LF	600.00	19,068.00
35	F/I Lower Cabinets @ Sterilization RM 114	9.51 LF	600.00	5,706.00
36	F/I Lower Cabinets @ Treatment RM 6	4.47 LF	600.00	2,682.00
37	F/I Upper Cabinets @ Treatment RM 3	4.49 LF	600.00	2,694.00
38	F/I Upper Cabinets @ Treatment RM 5	4.47 LF	600.00	2,682.00
39	F/I Upper Cabinets @ Treatment RM 4	4.47 LF	600.00	2,682.00
40	F/I Upper Cabinets @ Treatment RM 2	4.47 LF	600.00	2,682.00
41	F/I Upper Cabinets @ Treatment RM 1	4.47 LF	600.00	2,682.00

Line	Description	Quantity	Unit Cost	Total
42	F/I Upper Cabinets @ Gypsum Room 103	13.95 LF	550.00	7,672.50
43	F/I Upper Cabinets @ Sterilization RM 114	32.38 LF	550.00	17,809.00
44	F/I Upper Cabinets @ Canteen 109	16.90 LF	550.00	9,295.00
45	F/I Lower Cabinets @ Canteen 109	6.24 LF	600.00	3,744.00
46			**Millwork Total**	**$188,537.10**
47			**Wood , Plastic and Composites Total**	**$188,537.10**
48	**07 Thermal and Moisture Protection**			
49	**07.4200 Wall Panels**			
50	F/I Black Composite Wall Panels @ Treatment RM 1	84.20 SF	60.00	5,052.00
51	F/I Black Composite Wall Panels @ Gypsum RM	19.30 SF	60.00	1,158.00
52			**Wall Panels Total**	**$6,210.00**
53	**07.8400 Firestopping**			
54	Allowance to Fireproof Vertical Steel Beams Prior to Enclosing (2/A501)2/	1.00 LS	7,500.00	7,500.00
55			**Firestopping Total**	**$7,500.00**
56			**Thermal and Moisture Protection Total**	**$13,710.00**
57	**08 Openings**			
58	**08.1100 Doors, Frames & HW**			
59	F/O Hardware Set #3 (Storeroom Lock Doors)	3.00 EA	1,300.00	3,900.00
60	F/O Hardware Set #1 (Privacy Doors)	3.00 EA	1,250.00	3,750.00
61	F/O Hardware Set #4 (Storeroom Lock Double Doors)	2.00 EA	1,550.00	3,100.00
62	F/O Type B Solid-Core Wood Doors (Pair)	6.00 EA	750.00	4,500.00
63	F/O Type A Solid-Core Wood Doors	4.00 EA	750.00	3,000.00
64			**Doors, Frames & HW Total**	**$18,250.00**
65	**08.3000 Lead-Lined Doors/Windows, Frames & HW**			
66	F/O Lead-Lined Aluminum Door Frame	1.00 EA	2,200.00	2,200.00
67	F/O Hardware Set #2 (Interlocked Door CT Room)	1.00 EA	2,000.00	2,000.00
68	F/I Lead-Lined Windows	45.60 SF	130.00	5,928.00
69	F/O Type C Solid-Core Lead-Lined Doors	1.00 EA	2,800.00	2,800.00
70			**Lead-Lined Doors/Windows, Frames & HW Total**	**$12,928.00**
71	**08.8200 Arch. Metal & Glass**			
72	F/I Aluminum Door Frames Prepped To Receive Wood Doors	9.00 EA	1,323.16	11,908.45
73	F/I GL-2 6MM Back-Painted Cladding @ Gypsum Room 103	38.83 SF	135.49	5,261.22
74	F/I GL-2 6MM Back-Painted Cladding @ CT Rooms	212.81 SF	135.49	28,834.44
75	F/I GL-2 6MM Back-Painted Cladding @ Canteen 109	415.43 SF	135.49	56,288.19
76	F/I GL-3 Bath Mirrors	16.93 SF	57.57	974.70
77	F/I GL-2 Bath Mirrors	9.51 SF	57.57	547.51
78	1: Reconfigure Existing Vestibule Doors, Sidelites and Operators	2.00 EA	1,693.65	3,387.29
79	2: F/I 95% Opaque Film on Existing Vestibule Doors	1.00 EA	1,481.94	1,481.94
80	F/I GL-2 6MM Back-Painted Cladding @ Unisex Restrooms	298.49 SF	135.49	40,443.55
81	F/I GL-2 6MM Back-Painted Cladding @ Sterilization RM 114	128.79 SF	135.49	17,450.25
82	F/I GL-2 6MM Back-Painted White Safety Glass @ Hallway 134F	406.13 SF	135.49	55,028.10

Line	Description	Quantity	Unit Cost	Total
83	F/I Hardware Set #7 (Automatic Glass Sliding Doors)	12.00 EA	793.90	9,526.76
84	F/I Hardware Set #6 (Glass Sliding Doors)	3.00 EA	793.90	2,381.69
85	F/O Hardware Set #5 (Glass Swing Doors)	10.00 EA	793.90	7,938.96
86	F/I GL-1 Interior Storefront System w/White Opaque Film	3,808.11 SF	158.78	604,648.92
87	F/I GL-2 6MM Back-Painted White Safety Glass w/FPE 4 Sides @ 9'10"	1,140.60 SF	135.49	154,544.24
88	F/I GL-3 1/2" Clear Mirror @ 9'10	548.02 SF	62.00	33,977.79
89			**Arch. Metal & Glass Total**	**$1,034,624.00**
90	**08.8700 Glazing Films**			
91	F/I Smart Folio Film	549.00 SF	258.60	141,968.75
92	F/I MAT Folio Film	109.80 SF	184.71	20,281.25
93			**Glazing Films Total**	**$162,250.00**
94			**Openings Total**	**$1,228,052.00**
95	**09 Finishes**			
96	**09.2300 Drywall & Carpentry**			
97	F/I Mullion Caps w/Rubber Gaskets Where Interior Walls Meet Storefronts (B/A-500.00)	3.00 EA	500.00	1,500.00
98	F/I "Ceiling Trim" at Exposed Round Columns	51.92 LF	40.00	2,076.80
99	I/O TVs	2.00 EA	250.00	500.00
100	Clad Concrete Curb at Ovens/Sinsters RM 122 w/Drywall	1.00 EA	1,967.86	1,967.86
101	Skim Coat Exposed GWB Walls to Provide Level 5 Finish	2,770.75 SF	5.00	13,853.75
102	F/I Ceiling Blocking for Dental Columns	6.00 EA	109.50	657.01
103	I/O Dental Columns	5.00 EA	250.00	1,250.00
104	F/I 5/8" Lead-Lined GWB Walls	2,608.26 SF	36.08	94,099.28
105	F/I 5/8" Durock (Or Similar)	933.23 SF	3.94	3,672.93
106	F/I 5/8" GWB Walls	7,830.44 SF	5.25	41,091.21
107	F/I Hung GWB Ceilings	59.34 SF	23.61	1,401.27
108	F/I Lead-Lined GWB Ceilings	60.03 SF	45.92	2,756.38
109	F/I Wood Blocking	601.57 LF	8.21	4,940.48
110	F/I F.R. Vertical Wood Blocking (5/A-501)	40.00 LF	13.69	547.51
111	F/I Sound Attenuation Blanket Insulation	3,448.87 SF	2.62	9,049.19
112	F/I 3.5" Sound Attenuation Blanket	1,836.40 SF	2.62	4,818.37
113	F/I 5/8" GWB Soffit Fascia @ 7'1" AFF w/F-Trim Molding (C/A-500)	72.32 SF	26.24	1,897.54
114	I/O Bath Accessories	2.00 BATH	750.00	1,500.00
115	I/O Fire Extinguisher Cabinets	8.00 EA	200.00	1,600.00
116	I/O Interior Door, Frame & HW	12.00 EA	288.75	3,465.00
117	F/I 1-5/8" Metal Stud Framing	933.23 SF	6.56	6,121.55
118	F/I 3-5/8" Metal Stud Framing	5,213.67 SF	8.53	44,459.00
119	F/I 3-5/8" Metal Stud Soffit Framing	71.60 SF	11.15	798.43
120	F/I 5/8" Plywood Walls @ Electrical	95.88 SF	4.60	441.05
121			**Drywall & Carpentry Total**	**$244,464.60**
122	**09.2500 Acoustical Ceilings**			

Line	Description	Quantity	Unit Cost	Total
123	F/I Sound Batt Insulation Above Ceilings	2,054.87 SF	4.36	8,956.45
124	F/I MTL ACT Ceilings + Insulation [15MM T Profile Lay-In System Grid #S45] + OWA Tecta 2x2 Unperforated Tile + Soniguard Insulation	2,054.87 SF	40.68	83,593.55
125			**Acoustical Ceilings Total**	**$92,550.00**
126	**09.3013 Tile & Stone**			
127	F/I Stone Tile Floors at Entrance	139.90 SF	52.00	7,274.80
128	Template, Fabricate & Install ST-1 Water Skirting @ Gympsum RM Cabinets	1.76 SF	165.00	290.40
129	Template, Fabricate & Install ST-1 Solid Surface Backsplash @ Gypsum Room 103	29.89 SF	185.00	5,529.65
130	Template, Fabricate & Install ST-1 Chemical Resistant Backsplashes @ Treatment Rooms	13.41 SF	165.00	2,212.65
131	Template, Fabricate & Install ST-1 Chemical Resistant Backsplashes @ Gypsum RM	27.77 SF	165.00	4,582.05
132			**Tile & Stone Total**	**$19,889.55**
133	**09.6000 Flooring**			
134	F/I 1/2" Cement Board Substrate	3,765.47 SF	4.00	15,061.88
135	F/I VF-1 Vinyl Sheet Flooring Integral Base w/Aluminum	849.74 LF	20.00	16,994.80
136	F/I VF-1 Vinyl Sheet Flooring [Matter Surfaces Purline Pure White	3,734.09 SF	16.00	59,745.44
137	Standard Floor Prep	3,765.47 SF	0.75	2,824.10
138			**Flooring Total**	**$94,626.22**
139	**09.6900 Raised Access Flooring**			
140	F/I Raised Access Flooring System (Steel)	3,925.00 SF	15.00	58,875.00
141			**Raised Access Flooring Total**	**$58,875.00**
142	**09.9100 Painting**			
143	7: Black Out Behind Existing Glass Partition	1.00 EA	250.00	250.00
144	Paint Back of Millwork Panel (Glossy White) @ Storage 104	17.32 SF	10.00	173.20
145	Paint GWB Walls	8,589.31 SF	1.30	11,166.10
146	Paint Existing GWB Walls @ 9'10"	1,153.47 SF	1.30	1,499.51
147	Paint GWB Ceilings	119.37 SF	1.50	179.06
148	Paint/Stain New Doors & Frames	12.00 EA	175.00	2,100.00
149	Paint Exposed Round Columns	519.20 SF	1.30	674.96
150	Paint "Ceiling Molding" @ Exposed Round Columns	51.92 LF	3.50	181.72
151	Paint Exposed Ceilings	1,103.30 SF	3.25	3,585.73
152	Paint Existing GWB Ceilings	413.76 SF	1.30	537.89
153	Paint GWB Soffit Fascia	49.23 SF	3.00	147.69
154			**Painting Total**	**$20,495.86**
155			**Finishes Total**	**$530,901.23**
156	**10 Specialties**			
157	**10.2600 FRP Panels**			
158	F/I Marlite FRP 4'x8' Panels	90.40 SF	17.00	1,536.80
159			**FRP Panels Total**	**$1,536.80**
160	**10.2800 Bath Accessories**			

Line	Description	Quantity	Unit Cost	Total
161	F/O Coat Hook [Kohler Purist K-1143 P.C.]	4.00 EA	72.00	288.00
162	F/O Paper Towel Dispenser & Waste Receptacle [Bobrick Trimline B-36903 SS]	2.00 EA	380.00	760.00
163	F/O Toilet Tissue Holder [Kohler Devonshire K-14377 P.C.]	3.00 EA	45.00	135.00
164	F/O 18" Vertical Grab Bar [Kohler Purist K-11896-S]	2.00 EA	330.00	660.00
165	F/O 36" Grab Bar [Kohler Purist K-11896-S P.SS]	2.00 EA	300.00	600.00
166	F/O 42" Grab Bar [Kohler Purist K-11896-S P. SS]	1.00 EA	320.00	320.00
167			**Bath Accessories Total**	**$2,763.00**
168	**10.4400 Fire Protection Specialties**			
169	Fire Extinguisher Cabinet + FE	8.00 EA	350.00	2,800.00
170			**Fire Protection Specialties Total**	**$2,800.00**
171	**10.5110 Lockers**			
172	F/I Lockers @ Patient Area	8.00 EA	650.00	5,200.00
173	F/I Lockers @ Women's Lockers 107	9.00 EA	650.00	5,850.00
174	F/I Lockers @ Men's Lockers 106	5.00 EA	650.00	3,250.00
175			**Lockers Total**	**$14,300.00**
176			**Specialties Total**	**$21,399.80**
177	**12 Furnishing**			
178	**12.2000 Window Treatments**			
179	F/I MechoShade Window Treatments	16.00 EA	385.00	6,160.00
180			**Window Treatments Total**	**$6,160.00**
181	**12.3600 Countertops**			
182	Template, Fabricate & Install ST-1 Chemical Resistant Countertops @ Treatment Rooms	49.08 SF	165.00	8,098.20
183			**Countertops Total**	**$8,098.20**
184			**Furnishing Total**	**$14,258.20**
185	**21 Fire Suppression**			
186	**21.0000 Sprinkler**			
187	F/I New Sprinkler Piping	600.00 LF	12.50	7,500.00
188	F/I New Sprinkler Heads & Piping	45.00 EA	350.00	15,750.00
189	Sprinkler Shop Drawings	1.00 LS	2,500.00	2,500.00
190	Sprinkler Permits, Filing, Inspections, Signoff & Hydrostatic Testing	1.00 LS	5,000.00	5,000.00
191			**Sprinkler Total**	**$30,750.00**
192			**Fire Suppression Total**	**$30,750.00**
193	**22 Plumbing**			
194	**22.0000 Plumbing**			
195	Plumbing	1.00 LS	194,000.00	194,000.00
196			**Plumbing Total**	**$194,000.00**
197			**Plumbing Total**	**$194,000.00**
198	**23 Heating, Ventilating and Air-Conditioning**			
199	**23.0000 HVAC**			
200	Provide Shop Drawings & As-Builds	1.00 LS	0.00	0.00

Line	Description	Quantity	Unit Cost	Total
201	Provide Certified Air Testing and Balancing	1.00 LS	0.00	0.00
202	F/I Stand-Alone Controls	1.00 LS	0.00	0.00
203	F/I Vibration Isolation as Needed for Specified Equipment	1.00 LS	0.00	0.00
204	F/I Refrigerant and Drain Piping	1.00 LS	0.00	0.00
205	F/I Sheetmetal Ductwork	1.00 LS	0.00	0.00
206	F/I Condensate Pumps as Needed	1.00 LS	0.00	0.00
207	F/I Electric Wall Heaters	1.00 EA	0.00	0.00
208	F/I Mechanical Louvers	3.00 EA	0.00	0.00
209	F/I Exhaust Fans	3.00 EA	0.00	0.00
210	F/I VRF Branch Boxes	3.00 EA	0.00	0.00
211	F/I VRF Indoor AC Units	30.00 EA	0.00	0.00
212	F/I VRF AC Condensing Units	2.00 EA	0.00	0.00
213	F/I Drafting & Coordination Services for Ductwork	1.00 EA	0.00	0.00
214	HVAC	3,528.00 SF	133.08	469,506.24
215			**HVAC Total**	**$469,506.24**
216			**Heating, Ventilating and Air-Conditioning Total**	**$469,506.24**
217	**26 Electrical**			
218	**26.0000 Electric & Lighting**			
219	Main Service and Panels	3,528.00 SF	15.50	54,684.00
220	Power Outlets and Conduits	3,528.00 SF	6.00	21,168.00
221	Dedicated Circuits for Dental Equipment	3,528.00 SF	4.50	15,876.00
222	Lighting Controls and Wiring	3,528.00 SF	3.50	12,348.00
223	Mechanical Wiring	3,528.00 SF	4.50	15,876.00
224	F/O Lighting Fixture Package + Electrical Subcontractor Markup (10%)	1.00 LS	125,489.18	125,489.18
225	Lighting Fixture Installation	3,528.00 SF	11.65	41,101.20
226	Smart Folio Power Supply, Wiring, Connections & Control System	549.00 SF	16.00	8,784.00
227			**Electric & Lighting Total**	**$295,326.38**
228			**Electrical Total**	**$295,326.38**
229	**27 Communications**			
230	**27.1000 Low Voltage & Security**			
231	Low-Voltage & Security Budget	3,528.00 SF	8.00	28,224.00
232			**Low Voltage & Security Total**	**$28,224.00**
233	**27.1010 Access Control**			
234	Card Readers	4.00 EA	1,300.00	5,200.00
235			**Access Control Total**	**$5,200.00**
236			**Communications Total**	**$33,424.00**
237	**28 Safety And Security**			
238	**28.4600 Fire Alarm**			
239	Fire Alarm Budget	3,528.00 SF	6.50	22,932.00
240			**Fire Alarm Total**	**$22,932.00**
241			**Safety And Security Total**	**$22,932.00**

Line	Description	Quantity	Unit Cost	Total
242	**Sub-Total (Base Cost)**			**$3,043,996.95**

Estimate Summary



Description		Total
Sub-Total (Base Cost)		$3,043,996.95
Sub-Total ()		$3,043,996.95
General Conditions	10.0000%	304,399.70
Fee	6.0000%	200,903.80
Insurance	2.0000%	70,986.01
Total Estimate		$3,620,286.45