Estimate: 25045 East Jewett Project

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**01 General Requirements**			
2	**01.0050 General Requirements**			
3	General Supervision (Per Week)	5.20 WK	3,200.00	16,640.00
4	Supervision (Per Week)	52.00 WK	2,400.00	124,800.00
5	General Labor (Per Week)	9.00 WK	1,400.00	12,600.00
6	Project Manager II (Per Week)	15.00 WK	2,400.00	36,000.00
7	Blueprints (Per Page)	400.00 EA	6.00	2,400.00
8	Assistant Project Manager (Per Week)	5.00 WK	2,000.00	10,000.00
9	Misc. Materials (.005% Revenue)	1.00 LS	6,000.00	6,000.00
10	Temporary Toilet(s) (Per Month)	12.00 MO	225.00	2,700.00
11	Equipment Rental	1.00 LS	5,000.00	5,000.00
12			**General Requirements Total**	**$216,140.00**
13			**General Requirements Total**	**$216,140.00**
14	**03 Concrete**			
15	**03.1000 Concrete**			
16	F/I Cantilevered Mortar @ Footings	355.84 LF	8.00	2,846.72
17	Cut Expansion Joints Throughout	1.00 LS	2,400.00	2,400.00
18	Form & Pour Concrete Footings	39.01 CY	585.00	22,820.85
19	Form & Pour Concrete Foundation Wall(s)	58.02 CY	585.00	33,941.70
20	Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.	61.71 CY	585.00	36,100.35
21	Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.	0.16 CY	2,500.00	400.00
22	Form & Pour Bench. F/I All Applicable Rebar	1.18 CY	2,500.00	2,950.00
23	Form & Pour Spread Footings	1.28 CY	850.00	1,088.00
24	Concrete Pumps	7.00 EA	1,800.00	12,600.00
25			**Concrete Total**	**$115,147.62**
26			**Concrete Total**	**$115,147.62**
27	**04 Masonry**			
28	**04.4300 Stone Masonry**			
29	F/I Stone Base For Column Attachment With Metal Dowels	1.00 EA	1,500.00	1,500.00
30	F/I Dimensional Black Stone Tiles On Pedestals ($20/SF Material Allowance)	164.45 SF	40.00	6,578.00
31			**Stone Masonry Total**	**$8,078.00**
32			**Masonry Total**	**$8,078.00**
33	**05 Metal**			
34	**05.0050 Structural Steel**			
35	F/I HSS3x3x5/16 Steel Column	314.23 LB	9.00	2,828.07
36			**Structural Steel Total**	**$2,828.07**
37			**Metal Total**	**$2,828.07**
38	**06 Wood , Plastic and Composites**			
39	**06.2000 Finish Carpentry**			

Line	Description	Quantity	Unit Cost	Total
40	I/O Interior Wood Door & F/I Trim	9.00 EA	800.00	7,200.00
41	I/O Interior Door Hardware	9.00 EA	50.00	450.00
42	I/O Exterior Door Hardware	3.00 EA	75.00	225.00
43	F/I Base Molding	889.99 LF	9.00	8,009.91
44	F/I Door Casing	357.00 LF	9.00	3,213.00
45	F/I Window Casing	444.20 LF	9.00	3,997.80
46			**Finish Carpentry Total**	**$23,095.71**
47	**06.2200 Millwork (Allowance)**			
48	F/I Full Height Cabinets With Doors @ Loft Bedroom Closet With Pax Ikea Interiors	8.37 LF	1,125.00	9,416.25
49	F/I Millwork Bench & Cabinets @ Loft Closet	10.52 LF	550.00	5,786.00
50	F/I Millwork Bookshelves @ Loft Bedroom 3	18.41 LF	650.00	11,966.50
51	F/I Millwork Walk In Closet @ Bedroom 1	12.34 LF	600.00	7,404.00
52	F/I Millwork Bench & Cubbies @ Entrance Hall	11.93 LF	450.00	5,368.50
53	F/I 2X3 Knee Wall @ Backside Of Kitchen Island	13.41 LF	25.00	335.25
54	F/I Inset Rail @ Stairs Constructed Of Millwork Panels To Match Wall Panels	13.41 LF	250.00	3,352.50
55	F/I Millwork @ Panels @ Loft Bedroom 3	87.20 SF	40.00	3,488.00
56	F/I Millwork Panels @ Loft Knee Wall	73.96 SF	40.00	2,958.40
57	F/I Millwork Panels @ Loft Bedroom Bookshelves	43.30 SF	40.00	1,732.00
58	F/I Millwork Apron @ Loft Bedroom Desk & Bookshelves	7.35 SF	100.00	735.00
59	F/I Millwork (SF from Plan View)	587.46 SF	40.00	23,498.40
60	F/I Millwork Countertop @ Loft Bedroom 3	22.12 SF	100.00	2,212.00
61	F/I Millwork (SF)	0.95 SF	40.00	38.00
62	F/I Upper Cabinets @ Kitchen	10.86 LF	550.00	5,973.00
63	F/I Lower Cabinets @ Kitchen	10.85 LF	600.00	6,510.00
64	F/I Kitchen Island	13.32 LF	1,300.00	17,316.00
65	F/I Full-Height Millwork Closets	13.66 LF	1,125.00	15,367.50
66	F/I Full-Height Millwork Closets @ Bedroom 1	5.11 LF	1,125.00	5,748.75
67	F/I Full-Height Millwork Closets @ Bedroom 2	7.67 LF	1,125.00	8,628.75
68	F/I Full-Height Cabinets @ Entry Hall	7.10 LF	1,125.00	7,987.50
69	F/I Full-Height Cabinets @ Kitchen	3.33 LF	1,125.00	3,746.25
70	F/I Vanities	18.61 LF	500.00	9,305.00
71	F/I Millwork Panels @ Loft Bath Wall	23.40 SF	40.00	936.00
72	F/I Millwork Panels	1,299.87 SF	40.00	51,994.80
73	F/I Mirror With 1/8" Wood Frame	13.07 SF	100.00	1,307.00
74	F/I Millwork Panels @ Kitchen	6.80 SF	100.00	680.00
75	F/I Millwork Panels @ Kitchen Refrigerator	17.97 SF	100.00	1,797.00
76	F/I Millwork Wall Panels	24.04 SF	40.00	961.60
77	F/I Millwork Ceiling Panels	132.26 SF	40.00	5,290.40
78			**Millwork (Allowance) Total**	**$221,840.35**
79	**06.2300 Closet Interiors**			

Line	Description	Quantity	Unit Cost	Total
80	F/I Closet Interiors (Linen Closet)	5.71 LF	175.00	999.25
81			**Closet Interiors Total**	**$999.25**
82	**06.4001 Wood Framing Materials**			
83	F/O 4" SIP Panel @ Terrace	163.11 SF	12.00	1,957.32
84	F/O 8" PT Railing Posts @ Walkway	4.00 EA	250.00	1,000.00
85	F/I Warmboard Material	485.32 SF	18.32	8,888.64
86	F/O 2x4 PT	203.15 LF	1.90	385.18
87	F/O 2x4 DF	406.30 LF	1.63	663.08
88	F/O 2x4 Studs	1,303.40 LF	1.61	2,095.87
89	F/O 2x6 PT	435.74 LF	2.29	998.71
90	F/O 2x6 DF	1,469.47 LF	1.85	2,715.58
91	F/O 2x6 Studs	4,544.26 LF	1.85	8,397.79
92	F/O 1-3/4"x9-1/2" 1.55E LSL Studs	335.01 LF	7.20	2,412.08
93	F/O 2x10 DF	63.11 LF	7.20	454.39
94	F/O 2x10 DF	1,097.38 LF	4.10	4,503.64
95	F/O 2x10 PT	14.25 LF	4.50	64.13
96	F/O 6"x6"x12' PT Post	10.00 EA	57.95	579.50
97	F/O 10"x10"x10' Wood Post	1.00 EA	226.50	226.50
98	F/O 5-1/4"x5-1/4"x10' PSL Post	3.00 EA	226.50	679.50
99	F/O 5-1/4"x7"x10' PSL Post	1.00 EA	226.50	226.50
100	F/O 1-3/4" x 9-1/2" LVL	100.59 LF	7.43	747.18
101	F/O 1-3/4" x 11-7/8" LVL	28.46 LF	8.66	246.58
102	F/O 1-3/4"x14" LVL 1.9E	85.52 LF	11.56	988.27
103	F/O 1-3/4" x 16" 2.0E LVL	271.70 LF	15.83	4,300.05
104	F/O 1-3/4"x20" LVL	106.75 LF	24.12	2,574.81
105	F/O 4x8x1/2" CDX Fir Plywood	4,450.09 SF	2.03	8,972.60
106	F/O 4x8x1/2" CDX Fir Plywood	1,064.18 SF	1.87	2,005.64
107	F/O 4x8x1/2" CDX Fir Plywood Both Sides	135.72 SF	4.69	636.00
108	F/O 4x8x5/8" CDX Fir Plywood	3,036.63 SF	2.25	6,812.68
109	F/O 4x8x5/8" CDX Fir Plywood	741.85 SF	2.06	1,526.98
110	F/O 4x8x3/4" TG Advantech Plywood	1,647.18 SF	2.08	3,458.07
111	F/O 16" Pro 560 TJI (Per LF)	458.22 LF	12.58	5,766.24
112	F/O Termite shield (6" x 25' Aluminum Roll)	343.02 LF	1.11	343.00
113	F/O FormSealR 5-1/2" x 50' Sill Seal	343.02 LF	0.38	144.00
114	F/O Simpson HUCQ210-3 Hold Downs	2.00 EA	56.58	113.16
115	F/O Simpson HDU11 Hold Downs	2.00 EA	56.58	113.16
116	F/O Simpson MGU5.50-SDS	1.00 EA	56.58	56.58
117	F/O Simpson HDU5 Hold Downs	4.00 EA	51.87	207.46
118	F/O Wood Truss Roof (Common)	741.85 SF	10.00	7,418.50
119	F/O Wood Roof Trusses (Scissor)	2,974.18 SF	15.00	44,612.70
120	F/O Simpson ABU66Z Post Base	10.00 EA	50.00	500.00

Line	Description	Quantity	Unit Cost	Total
121	F/O Simpson ECCQ5-6SDS2.5 Column Cap	3.00 EA	50.00	150.00
122	F/O Simpson MSTC52 Straps	3.00 EA	165.00	495.00
123			**Wood Framing Materials Total**	**$128,437.07**
124	**06.4002 Wood Framing Labor**			
125	I/O 4" SIP Panels @ Terrace	163.11 SF	8.00	1,304.88
126	I/O Interior Framed Wall	2,755.19 SF	3.00	8,265.57
127	I/O Floor Framing (Joists & Subfloor)	1,647.18 SF	4.50	7,412.31
128	I/O Exterior Wall Framing & Sheathing @ 1st Floor	4,313.64 SF	4.50	19,411.39
129	I/O Exterior Wall Framing & Sheathing @ 2nd Floor	1,200.63 SF	5.50	6,603.48
130	I/O Exterior Wall Framing & Sheathing @ Parapet Wall Both Sides	135.72 SF	7.00	950.04
131	I/O Roof Framing & Sheathing	3,778.48 SF	5.50	20,781.66
132	I/O Install Warmboard Panels	485.32 SF	4.00	1,941.28
133	Crane Rental (Per Week)	2.00 WK	2,500.00	5,000.00
134	I/O Deck Post	14.00 EA	45.00	630.00
135	I/O Residential Exterior Door(s)	3.00 EA	400.00	1,200.00
136			**Wood Framing Labor Total**	**$73,500.61**
137	**06.4300 Wood Stairs And Railings**			
138	F/I White Oak Stairs	14.00 EA	475.00	6,650.00
139			**Wood Stairs And Railings Total**	**$6,650.00**
140	**06.6600 Exterior Wood Railing**			
141	F/I 42" Pine Treated Deck Railing	16.18 LF	30.89	499.80
142			**Exterior Wood Railing Total**	**$499.80**
143			**Wood , Plastic and Composites Total**	**$455,022.79**
144	**07 Thermal and Moisture Protection**			
145	**07.1000 Waterproofing**			
146	F/I Foundation Waterproofing [Membrane Applied Waterproofing With Drainage Tile/Matt]	1,601.28 SF	6.30	10,088.06
147			**Waterproofing Total**	**$10,088.06**
148	**07.2000 Insulation**			
149	F/I R-28 Mineral Wool Insulation	843.82 SF	3.50	2,953.37
150	F/I 4" Atlas Rigged Roof Insulation [ACFOAM-III R-23.6]	553.94 SF	4.75	2,631.21
151	F/I 4" Atlas Rigged Roof Insulation [ACFOAM-III R-23.6]	843.82 SF	4.75	4,008.15
152	F/I 3.5" Atlas Rigid Roof Insulation [ACFoam-III R-20.5]	190.06 SF	6.00	1,140.36
153	F/I Insulation & Air Seal @ Window(s)/Exterior Door(s)	3.00 EA	25.00	75.00
154	F/I Sound Deadening Mineral Wool Insulation	989.46 SF	1.50	1,484.19
155	F/I Mineral Wool Insulation	266.66 SF	1.50	399.99
156	F/I Sound Deadening Insulation	295.79 SF	1.50	443.69
157	F/I Mineral Wool Insulation	322.34 SF	1.51	486.73
158	F/I Mineral Wool Insulation	455.51 SF	1.51	687.82
159	F/I R-21 Mineral Wool Insulation	215.43 SF	3.25	700.15
160	F/I R-21 Mineral Wool Insulation	1,523.93 SF	3.25	4,952.77

Line	Description	Quantity	Unit Cost	Total
161	F/I Mineral Wool Insulation	243.61 SF	1.51	367.85
162	F/I R-21 Mineral Wool Insulation	2,525.00 SF	3.25	8,206.25
163	F/I R-38 Mineral Wool Insulation	249.38 SF	4.00	997.52
164	F/I R-22 Mineral Wool Insulation	1,850.77 SF	3.50	6,477.70
165			**Insulation Total**	**$36,012.75**
166	**07.3000 Roofing**			
167	F/I Scupper	2.00 EA	250.00	500.00
168	F/I Thru Wall Scupper @ Terrace	2.00 EA	250.00	500.00
169	F/I 4" Atlas Rigged Roof Insulation [ACFOAM-III R-23.6]	1,850.77 SF	4.75	8,791.16
170	F/I 5/8" APA Plywood Coverboard	1,850.77 EA	4.20	7,773.23
171	F/I Snow Guards Utilizing Blackened Wooden Log On Brackets	143.72 LF	50.00	7,186.00
172	F/I TPO Roof at Parapet Walls @ Terrace	52.03 SF	18.00	936.54
173	F/I 1-Ply TPO Roof Membrane	172.02 SF	14.00	2,408.28
174	F/I Black Steel Metal Roofing	3,784.73 SF	20.15	76,262.33
175	F/I .040 Aluminum Coping @ Terrace Parapet Walls	38.26 LF	40.00	1,530.40
176			**Roofing Total**	**$105,887.94**
177	**07.6600 Gutters & Leaders**			
178	F/I 5" Gutters	217.01 LF	15.00	3,255.15
179	F/I 5" Leaders	251.38 LF	15.00	3,770.70
180			**Gutters & Leaders Total**	**$7,025.85**
181	**07.9510 Siding**			
182	F/I Eave Trim	251.12 LF	26.00	6,529.12
183	F/I EnergyShield XR Rigid Insulation Using Cladiator 2" Slotted-Z Every 24"	4,460.00 SF	10.00	44,600.00
184	F/I Furring Strips Behind Siding	162.62 SF	2.00	325.24
185	F/I Tyvek Housewrap	5,157.00 SF	1.53	6,566.20
186	F/I Fluid Applied Moisture Barrier	249.38 SF	2.50	623.45
187	F/I Tyvek Tape	5,157.00 SF	0.43	2,208.09
188	Wood Plank @ Underside Of Roof Overhang ($21/SF Budget)	74.64 SF	32.15	2,399.68
189	F/I Accoya Wood Siding ($21/SF Budget)	4,458.38 SF	29.15	129,961.78
190	F/I Accoya Wood Siding @ Top Of Parapet Walls ($21/SF Budget)	31.74 SF	32.15	1,020.44
191			**Siding Total**	**$194,234.00**
192			**Thermal and Moisture Protection Total**	**$353,248.60**
193	**08 Openings**			
194	**08.1400 Wood Doors, EZY Jambs, & HW**			
195	F/O Solid-Core Wood Door With EZY Jambs ($2200/Ea Allowance)	5.00 EA	2,200.00	11,000.00
196	F/O Hollow Metal Door With EZY Jamb ($1200/Ea Allowance)	3.00 EA	1,200.00	3,600.00
197	F/O HM Door & Frame ($850/Ea Allowance)	1.00 EA	850.00	850.00
198	F/O Door Hardware ($150 Allowance Each)	9.00 EA	150.00	1,350.00
199			**Wood Doors, EZY Jambs, & HW Total**	**$16,800.00**
200	**08.1600 Residential Entry Doors & HW**			

Line	Description	Quantity	Unit Cost	Total
201	F/O Residential Wood Entry Door (36"x80"x9-1/6") ($5,200 Allowance Placeholder]	1.00 EA	5,200.00	5,200.00
202	F/O Residential Wood Entry Door (54"x84"x9-1/6") ($10,000 Allowance Placeholder]	2.00 EA	10,000.00	20,000.00
203	F/O Residential Entry Door Deadlock/Door Knob Combo [$150/Each Allowance Placeholder]	1.00 EA	250.00	250.00
204	F/O Residential Entry Door Deadlock/Door Knob Combo [$250/Each Allowance Placeholder]	2.00 EA	250.00	500.00
205	F/O Doorbell	1.00 EA	555.00	555.00
206			**Residential Entry Doors & HW Total**	**$26,505.00**
207	**08.3700 Garage Doors**			
208	Garage Door With Opener	1.00 EA	12,500.00	12,500.00
209			**Garage Doors Total**	**$12,500.00**
210	**08.5000 Windows**			
211	D015 Exterior Sliding French Door Pair 5'10"x9'0"	1.00 EA	5,000.00	5,000.00
212	D014 Exterior Sliding French Door Pair 9'6"x9'0"	1.00 EA	12,000.00	12,000.00
213	D013 Exterior Sliding French Door Pair 7'9"x7'10"	1.00 EA	8,000.00	8,000.00
214	D012 Exterior Sliding French Door Pair 10'6"x7'10"	1.00 EA	20,000.00	20,000.00
215	Window (Per SF)	253.69 SF	125.00	31,711.25
216			**Windows Total**	**$76,711.25**
217	**08.8500 Shower Enclosures**			
218	Shower Enclosure	3.00 EA	2,250.00	6,750.00
219			**Shower Enclosures Total**	**$6,750.00**
220			**Openings Total**	**$139,266.25**
221	**09 Finishes**			
222	**09.2300 Drywall & Carpentry**			
223	F/I Permabase Heatshield Cement Board UL Certified	226.88 SF	3.25	737.36
224	F/I 5/8" GWB Walls (Level 4 Finish) Above Fireplace From 8' A.F.F. To Sloped Ceiling	285.80 SF	3.00	857.40
225	F/I 5/8" GWB Walls (Level 4 Finish)	9,794.93 SF	3.00	29,384.79
226	F/I 5/8" GWB Walls (Level 4 Finish)	928.20 SF	3.00	2,784.60
227	F/I 5/8" GWB Walls	55.20 SF	3.00	165.60
228	F/I 5/8" GWB Ceilings (Level 4 Finish)	2,734.47 SF	3.00	8,203.41
229	I/O Bath Accessories	4.00 BATH	400.00	1,600.00
230	F/I Acoustical Sealant	537.27 LF	1.00	537.27
231			**Drywall & Carpentry Total**	**$44,270.43**
232	**09.3013 Tile & Stone**			
233	F/I Floor Tile ($7/SF Material Allowance)	797.27 SF	24.70	19,692.57
234	F/I Wall Tile ($7/SF Material Allowance)	660.41 SF	24.70	16,312.14
235	F/I Mud Job at Shower	3.00 EA	500.00	1,500.00
236	F/I Blackened Steel Surround @ Fire Place Tile Boarder	41.70 LF	17.00	708.90
237	F/I Waterproofing for Wall Tile	296.42 SF	5.00	1,482.10
238	F/I Waterproofing for Floor Tile	797.27 SF	5.00	3,986.35

Line	Description	Quantity	Unit Cost	Total
239			**Tile & Stone Total**	**$43,682.06**
240	**09.6000 Concrete Sealer**			
241	Concrete Sealer @ Garage Slab [Foundation Armour Penetrating Solvent Based Siloxane]	475.02 SF	4.85	2,303.85
242			**Concrete Sealer Total**	**$2,303.85**
243	**09.6400 Wood Flooring**			
244	F/I Engineered Treated Wood Flooring @ WC4 ($13/SF Material Allowance)	42.86 SF	24.10	1,032.93
245	F/I Pre-Finished Engineered Wood Flooring ($13/SF Material Allowance)	448.73 SF	22.50	10,096.43
246			**Wood Flooring Total**	**$11,129.36**
247	**09.9100 Painting**			
248	Paint Smooth Wood Siding	4,500.00 SF	5.00	22,500.00
249	Paint GWB Walls	9,708.79 SF	1.30	12,621.43
250	Paint Base Molding	889.99 LF	3.50	3,115.03
251	Paint GWB Ceilings	1,647.18 SF	1.50	2,470.77
252	Paint GWB Cathedral Ceilings	1,850.77 SF	2.00	3,701.54
253	Paint Door Casing	51.00 LF	5.00	255.00
254	Paint/Stain Wood Doors & Casing	9.00 EA	225.00	2,025.00
255	Paint Window Casing	444.20 LF	5.00	2,221.00
256	Prime & Paint Residential Fiberglass Entry Door	3.00 EA	350.00	1,050.00
257			**Painting Total**	**$49,959.77**
258			**Finishes Total**	**$151,345.47**
259	**10 Specialties**			
260	**10.2800 Bath Accessories**			
261	Bath Accessories Budget	2.00 EA	2,000.00	4,000.00
262	Bath Accessories Budget	2.00 EA	700.00	1,400.00
263			**Bath Accessories Total**	**$5,400.00**
264	**10.3100 Fireplaces**			
265	Stuv Fire Box	1.00 EA	13,800.00	13,800.00
266			**Fireplaces Total**	**$13,800.00**
267			**Specialties Total**	**$19,200.00**
268	**11 Equipment**			
269	**11.3100 Appliances**			
270	F/O APP-2 Refrigerator	1.00 EA	5,000.00	5,000.00
271	F/O APP-4 Dishwasher	1.00 EA	2,500.00	2,500.00
272	F/O APP-1 Combination Wall Oven	1.00 EA	2,500.00	2,500.00
273	F/O Pitt Floating Gas Burners	1.00 EA	7,500.00	7,500.00
274	F/O APP-5 Vent Hood Insert 30"	1.00 EA	1,300.00	1,300.00
275	F/O APP-3 Microwave	1.00 EA	1,500.00	1,500.00
276			**Appliances Total**	**$20,300.00**
277			**Equipment Total**	**$20,300.00**
278	**12 Furnishing**			

Line	Description	Quantity	Unit Cost	Total
279	**12.3600 Countertops**			
280	Template, Fabricate & Install Solid Surface Countertops ($65/SF Material Allowance)	34.13 SF	130.00	4,436.90
281	Template, Fabricate & Install Solid Surface Backsplash ($65/SF Material Allowance)	37.89 SF	130.00	4,925.70
282	Template, Fabricate & Install Solid Surface Countertop ($65/SF Material Allowance)	81.34 SF	130.00	10,574.20
283	Template, Fabricate & Install Solid Surface Backsplash ($65/SF Material Allowance)	7.72 SF	130.00	1,003.60
284			**Countertops Total**	**$20,940.40**
285			**Furnishing Total**	**$20,940.40**
286	**22 Plumbing**			
287	**22.0000 Plumbing**			
288	F/I Hose Bib	3.00 EA	550.00	1,650.00
289	I/O Residential Toilet	4.00 EA	1,200.00	4,800.00
290	I/O Bath Lav (Sink) & Faucet	6.00 EA	1,100.00	6,600.00
291	I/O Standard Shower	3.00 EA	1,200.00	3,600.00
292	I/O Freestanding Bathtub	2.00 EA	3,000.00	6,000.00
293	I/O Sink & Faucet	1.00 EA	1,200.00	1,200.00
294	I/O Dishwasher	1.00 EA	800.00	800.00
295	F/I Refrigerator Waterline	1.00 EA	700.00	700.00
296	F/I Gas Piping & Connection	2.00 EA	900.00	1,800.00
297	F/I Floor Drain 3"	4.00 EA	1,200.00	4,800.00
298	F/I Residential Hot Water Heater (HWH)	1.00 EA	3,600.00	3,600.00
299	F/I 50-Gallon 40,000 BTU 40.4GPH Hot Water Heater (HWH)	2.00 EA	4,650.00	9,300.00
300			**Plumbing Total**	**$44,850.00**
301	**22.4000 Plumbing Fixtures**			
302	F/O Kitchen Sink	1.00 EA	1,200.00	1,200.00
303	F/O Kitchen Faucet	1.00 EA	500.00	500.00
304	F/O LAV Sink	6.00 EA	600.00	3,600.00
305	F/O Lav Faucet	6.00 EA	250.00	1,500.00
306	F/O Residential Toilet	4.00 EA	500.00	2,000.00
307	F/O Free-Standing Bathtub	2.00 EA	2,500.00	5,000.00
308	F/O Standard Shower Kit	5.00 EA	1,500.00	7,500.00
309	F/O Tub Filler/Faucet	2.00 EA	1,725.00	3,450.00
310			**Plumbing Fixtures Total**	**$24,750.00**
311			**Plumbing Total**	**$69,600.00**
312	**23 Heating, Ventilating and Air-Conditioning**			
313	**23.0000 HVAC**			
314	F/I Programmable Thermostats	4.00 EA	500.00	2,000.00
315	Duct Exhaust Fan	4.00 EA	300.00	1,200.00
316	F/I Radiant Tubing for Radiant System	485.32 SF	7.50	3,639.90
317	F/I Combi Boiler for Radiant Heating	1.00 EA	13,500.00	13,500.00

Line	Description	Quantity	Unit Cost	Total
318	F/I Radiant Tubing in Slab @ Zone 1	1,315.53 SF	7.50	9,866.48
319	F/I Radiant Tubing in Slab @ Zone 2	448.56 SF	7.50	3,364.20
320	F/I Radiant Tubing in Slab @ Zone 3	326.84 SF	7.50	2,451.30
321	F/I Radiant Manifolds (Single-Zone)	4.00 EA	1,800.00	7,200.00
322	F/I Split Unit + Condenser (Including Hyper Heat)	3.00 EA	7,000.00	21,000.00
323	Ancillary Split Unit	4.00 EA	4,000.00	16,000.00
324			**HVAC Total**	**$80,221.88**
325			**Heating, Ventilating and Air-Conditioning Total**	**$80,221.88**
326	**26 Electrical**			
327	**26.0000 Electric**			
328	F/I LED Linear Light Inside Stair Rail Slot	13.34 LF	50.00	667.00
329	F/I Home Run + Arc-Fault Breaker	20.00 EA	275.00	5,500.00
330	F/I Duplex Receptacle	32.00 EA	105.00	3,360.00
331	F/I GFI Receptacle	18.00 EA	105.00	1,890.00
332	F/I Weatherproof GFI Receptacle	2.00 EA	220.00	440.00
333	F/I Dedicated Equipment Duplex 20amp	15.00 EA	275.00	4,125.00
334	Wire 60 Amp AC Condenser Unit	3.00 EA	1,300.00	3,900.00
335	I/O Linear Lighting Fixture	48.62 LF	50.00	2,431.00
336	I/O Lighting Fixture (Residential)	127.00 EA	200.00	25,400.00
337	F/I Residential Exhaust Fan	4.00 EA	250.00	1,000.00
338	F/I Single-Pole Switch	12.00 EA	95.00	1,140.00
339	F/I 3-Way Switch	15.00 EA	90.00	1,350.00
340	F/I LED Dimmer Switch	13.00 EA	150.00	1,950.00
341	F/I EV Charger	1.00 EA	1,700.00	1,700.00
342	F/I 200Amp Panel	1.00 EA	4,000.00	4,000.00
343			**Electric Total**	**$58,853.00**
344	**26.5000 Lighting Fixtures**			
345	F/O LE3 Exterior Path Lighting Fixture Budget	6.00 EA	250.00	1,500.00
346	F/O LE2 Exterior Lighting Fixture Budget	22.00 EA	250.00	5,500.00
347	F/O LE1 Exterior Wall Sconce Lighting Fixture Budget	33.00 EA	250.00	8,250.00
348	F/O L3 Recessed Lighting Fixture Budget	20.00 EA	85.00	1,700.00
349	F/O L5A Wall Sconce Lighting Fixture Budget	7.00 EA	500.00	3,500.00
350	F/O L5B Lighting Fixture Budget	9.00 EA	250.00	2,250.00
351	F/O L1 Architectural Surface Mounted Lighting Fixture Budget @ Living Room	1.00 EA	600.00	600.00
352	F/O L6B Wall Mounted Lighting Fixture Budget	1.00 EA	250.00	250.00
353	F/O L8B Ceiling Mounted Linear Lighting Fixture Budget	2.00 EA	200.00	400.00
354	F/O L7 Bedroom Ceiling Mounted Lighting Fixture Budget	2.00 EA	300.00	600.00
355	L8A Garage Lighting Fixture Budget	4.00 EA	150.00	600.00
356	F/O LE1 Exterior Lighting Fixture Budget	5.00 EA	250.00	1,250.00
357	F/O L9A Wall Mounted Lighting Fixture Budget	2.00 EA	250.00	500.00

Line	Description	Quantity	Unit Cost	Total
358	F/O L11 Wall Wash Lighting Fixture Budget	10.00 EA	250.00	2,500.00
359	F/O L10 Ceiling Lighting Fixture Budget	3.00 EA	250.00	750.00
360	F/O LED Linear Light	3.57 LF	60.00	214.20
361	F/O LED Linear Light Inside Stair Rail Slot	13.43 LF	60.00	805.80
362	F/O L4 Linear Lighting Fixture	19.12 LF	60.00	1,147.20
363	F/O L2 Linear Lighting Fixture	4.40 LF	60.00	264.00
364	F/O Under Cabinet Linear Lighting Fixture	7.18 LF	60.00	430.80
365	F/O L6A Cove Linear Lighting Fixture	14.35 LF	60.00	861.00
366			**Lighting Fixtures Total**	**$33,873.00**
367			**Electrical Total**	**$92,726.00**
368	**28 Safety And Security**			
369	**28.4600 Fire Alarm**			
370	F/I Smoke/Carbon Monoxide Detector Combo	5.00 EA	200.00	1,000.00
371			**Fire Alarm Total**	**$1,000.00**
372	**28.4610 Security (Equipment Not Included)**			
373	F/I Door Sensor	4.00 EA	250.00	1,000.00
374	F/I Door Lock	4.00 EA	250.00	1,000.00
375	F/I Glass Break Sensor	9.00 EA	250.00	2,250.00
376	F/I Cameras	1.00 EA	250.00	250.00
377			**Security (Equipment Not Included) Total**	**$4,500.00**
378			**Safety And Security Total**	**$5,500.00**
379	**31 Sitework**			
380	**31.0000 Earthwork**			
381	Excavate Foundation (Slab on Grade)	1.42 DAY	2,600.00	3,692.00
382	Excavate Foundation (Frost Walls)	3.21 DAY	2,600.00	8,346.00
383	Backfill Frost Walls	3.21 DAY	2,600.00	8,346.00
384	Backfill Slab & Compact	1.76 DAY	2,600.00	4,576.00
385	2" Rigid Insulation Below Grade	2,330.33 SF	2.50	5,825.83
386	F/I Crushed Stone	77.96 CY	105.00	8,185.80
387	2" Rigid Insulation Below Grade Vertical	913.75 SF	2.70	2,467.13
388	Trenching, Sand and Backfill Utility Trench for Underground Electric (2' Deep w/1' Sand)	67.70 LF	16.00	1,083.20
389			**Earthwork Total**	**$42,521.96**
390	**31.1100 Drainage & Stormwater**			
391	F/I 4" Footing Drain to Daylight	500.38 LF	18.00	9,006.84
392			**Drainage & Stormwater Total**	**$9,006.84**
393			**Sitework Total**	**$51,528.80**
394	**32 Exterior Improvements**			
395	**32.1200 Paving**			
396	F/I 8" Subbase	4,386.22 SF	3.00	13,158.66
397	F/I 6" Base Course (Two 3" Lifts)	4,386.22 SF	5.25	23,027.66

Line	Description	Quantity	Unit Cost	Total
398	F/I 2" Top Course (Mix I-4/I-5)	4,386.22 SF	3.50	15,351.77
399			**Paving Total**	**$51,538.09**
400	**32.1400 Hardscaping**			
401	F/I 2'6"x5'0" Bluestone Walkway Stones + Pea Gravel & Drainage	71.00 EA	500.00	35,500.00
402			**Hardscaping Total**	**$35,500.00**
403	**32.9300 Landscaping (Not Included)**			
404	6'-7' Tree	2.00 EA	0.00	0.00
405			**Landscaping (Not Included) Total**	**$0.00**
406			**Exterior Improvements Total**	**$87,038.09**
407	**33 Utilities**			
408	**33.2000 Well (Allowance)**			
409	Well Allowance (400' Deep with 20' of Casing)	1.00 EA	14,800.00	14,800.00
410			**Well (Allowance) Total**	**$14,800.00**
411	**33.3100 Septic Systems**			
412	F/I Raised Septic System (Design TBD)	1.00 EA	30,000.00	30,000.00
413	F/I Sanitary Piping from House to Septic	67.70 LF	50.00	3,385.00
414			**Septic Systems Total**	**$33,385.00**
415	**33.5600 Propane (Not Included)**			
416	Above Ground Propane Tank (Includes Gas Check, Regulator, etc.)	1.00 EA	0.00	0.00
417			**Propane (Not Included) Total**	**$0.00**
418			**Utilities Total**	**$48,185.00**
419	**97 Notes/Exclusions/RFIs/Etc.**			
420	**97.0000 Notes/RFIs/Exclusions/Allowances:**			
421	Note: All millwork wall panels are 3/4" plywood with 1/4" Solid Wood For the Finish	1.00 EA	0.00	0.00
422			**Notes/RFIs/Exclusions/Allowances: Total**	**$0.00**
423			**Notes/Exclusions/RFIs/Etc. Total**	**$0.00**
424	**Sub-Total (Base Cost)**			**$1,936,316.97**

Estimate Summary



Material [$423,459]
Labor [$0]
SubContractor [$1,176,045]
Equipment [$0]
Other [$336,812]

Description		Total
Sub-Total (Base Cost)		$1,936,316.97
Labor	30.0000%	0.00
Equipment	10.0000%	0.00
Sub-Total (Direct Cost)		$1,936,316.97
Overhead & Profit	15.0000%	290,447.55
Insurance	3.0000%	66,802.94
Total Estimate		$2,293,567.45