Estimate: 250045 Relic Spa

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**01 General Requirements**			
2	**01.0050 General Conditions**			
3	Supervision	20.00 WK	3,000.00	60,000.00
4	General Labor (Per Week)	20.00 WK	1,400.00	28,000.00
5	Project Manager	5.00 WK	3,500.00	17,500.00
6			**General Conditions Total**	**$105,500.00**
7			**General Requirements Total**	**$105,500.00**
8	**02 Existing Conditions**			
9	**02.1000 Demolition**			
10	Demolition	6,600.00 SF	6.50	42,900.00
11			**Demolition Total**	**$42,900.00**
12			**Existing Conditions Total**	**$42,900.00**
13	**03 Concrete**			
14	**03.1000 Concrete**			
15	Form & Pour 1'x1' Concrete Footings (Sequenced for Underpinning)	9.42 CY	1,000.00	9,420.00
16	Form & Pour 12" Concrete Foundation Wall(s) (Sequenced for Underpinning)	47.09 CY	1,000.00	47,090.00
17	Patch Concrete Slab	40.00 SF	20.00	800.00
18	Hand-Dig Fill from Trench & Remove from Jobsite	20.00 LF	17.00	340.00
19	F/I Gravel Subbase in Trench	40.00 SF	8.00	320.00
20			**Concrete Total**	**$57,970.00**
21	**03.1500 Concrete Cutting**			
22	Sawcut Existing Slab for Pool. Flip & Haul Concrete Off Site.	582.46 SF	12.00	6,989.52
23	Sawcut Existing Slab (2' Wide) For Underground Utilities. Flip & Haul Concrete Off Site.	20.00 LF	125.00	2,500.00
24			**Concrete Cutting Total**	**$9,489.52**
25			**Concrete Total**	**$67,459.52**
26	**05 Metal**			
27	**05.0050 Structural Steel**			
28	F/O Steel Reinforcing Plate for Women's L.R. Bench	13.34 LF	30.00	400.20
29	F/O Steel Brackets @ Steam Bench	16.18 LF	15.00	242.70
30			**Structural Steel Total**	**$642.90**
31			**Metal Total**	**$642.90**
32	**06 Wood , Plastic and Composites**			
33	**06.2200 Millwork**			
34	F/I Reception Desk	6.75 LF	1,200.00	8,100.00
35	F/I Lower Cabinets (Mid-Grade)	32.56 LF	550.00	17,908.00
36	F/I Upper Cabinets (Mid-Grade)	8.79 LF	550.00	4,834.50
37			**Millwork Total**	**$30,842.50**
38			**Wood , Plastic and Composites Total**	**$30,842.50**
39	**07 Thermal and Moisture Protection**			
40	**07.3000 Roofing**			

Line	Description	Quantity	Unit Cost	Total
41	Roofing Allowance	1.00 LS	5,000.00	5,000.00
42			**Roofing Total**	**$5,000.00**
43			**Thermal and Moisture Protection Total**	**$5,000.00**
44	**08 Openings**			
45	**08.1100 HM Doors, Frames & HW**			
46	F/O HM Frame (Single)	4.00 EA	365.00	1,460.00
47	F/O Solid-Core Wood Door	4.00 EA	550.00	2,200.00
48	F/O Door Hardware (Commercial Exterior)	4.00 EA	1,075.00	4,300.00
49			**HM Doors, Frames & HW Total**	**$7,960.00**
50	**08.8200 Arch. Metal & Glass**			
51	F/I Frameless Storefront Door & HW	4.00 EA	2,850.00	11,400.00
52	F/I Interior Storefront (½" Clear Tempered with Top & Bottom Channel)	283.60 SF	90.00	25,524.00
53			**Arch. Metal & Glass Total**	**$36,924.00**
54	**08.8300 Mirrors**			
55	F/I Frameless Glass Mirrors	49.11 SF	70.00	3,437.70
56			**Mirrors Total**	**$3,437.70**
57			**Openings Total**	**$48,321.70**
58	**09 Finishes**			
59	**09.2300 Drywall & Carpentry**			
60	I/O Steel Reinforcement Plate @ Women's L.R. Bench	13.34 LF	15.00	200.10
61	I/O Steel Brackets @ Steam Bench	16.18 LF	15.00	242.70
62	F/I One (1) Layer of 3/4" Plywood + One (1) Layer of 5/8" Cement Board @ Women's L.R. Bench	84.31 SF	15.00	1,264.65
63	F/I 5/8" GWB Walls	13,529.04 SF	2.75	37,204.86
64	F/I Hung GWB Ceilings	915.98 SF	13.00	11,907.74
65	F/I Wood Blocking	35.45 LF	12.00	425.40
66	F/I Wood Blocking for Bath Accessories (Per Bath)	2.00 EA	150.00	300.00
67	F/I Blanket Insulation	7,485.84 SF	1.50	11,228.76
68	F/I 3.5" Sound Attenuation Blanket	425.40 SF	1.35	574.29
69	I/O Bath Accessories	2.00 BATH	500.00	1,000.00
70	I/O Interior HM Door, Frame & HW (Single)	4.00 EA	275.00	1,100.00
71	F/I C-Channel Structural Metal Framing @ Women's L.R. Bench	47.31 SF	45.00	2,128.95
72	F/I 3-5/8" Metal Stud Framing	7,911.24 SF	5.50	43,511.82
73			**Drywall & Carpentry Total**	**$111,089.27**
74	**09.2500 Acoustical Ceilings**			
75	F/I ACT Ceilings @ Kitchen [Armstrong Kitchen Zone or Equal]	204.97 SF	13.00	2,664.61
76	F/I ACT Ceilings @ Pool Area [Armstrong AQUA or Equal]	1,499.38 SF	14.00	20,991.32
77	F/I ACT Ceilings	276.12 SF	13.00	3,589.56
78			**Acoustical Ceilings Total**	**$27,245.49**
79	**09.3013 Tile & Stone**			
80	F/I Linear Floor Drains	12.31 LF	150.00	1,846.50

Line	Description	Quantity	Unit Cost	Total
81	F/I Tile Base ($7/LF Material Allowance)	812.64 LF	12.70	10,320.50
82	F/I Floor Tile @ 2nd Floor Reception Area	544.02 SF	26.00	14,144.50
83	F/I Floor Tile @ 2nd Floor ($10/SF Material Allowance)	1,681.72 SF	26.00	43,724.70
84	F/I Floor Tile @ Entrance ($10/SF Material Allowance)	81.32 SF	26.00	2,114.30
85	F/I Floor Tile @ Sauna ($10/SF Material Allowance)	134.56 SF	26.00	3,498.60
86	F/I Chemical-Resistant Floor Tile @ Pool Area ($10/SF Material Allowance)	1,565.87 SF	26.00	40,712.65
87	F/I Wall Tile (Material Allowance)	5,549.66 SF	22.70	125,977.31
88	F/I Wall Tile @ Pool Area [Glazed Ceramic w/Waterproof Coating] ($10/SF Material Allowance)	1,403.10 SF	26.00	36,480.60
89	F/I Mud Job at Shower	5.00 EA	500.00	2,500.00
90	F/I Waterproofing for Wall Tile	6,952.76 SF	5.25	36,502.00
91	F/I Waterproofing for Floor Tile	3,382.15 SF	5.25	17,756.29
92			**Tile & Stone Total**	**$335,577.95**
93	**09.6000 Flooring**			
94	F/I 4" Vinyl Base	728.04 LF	3.50	2,548.14
95	Clean & Seal Existing Concrete Slab (2 Coats)	394.36 SF	4.85	1,912.65
96	F/I Carpet Tile @ Mezzanine Corridor & Office	43.37 SY	70.00	3,035.90
97	F/I Carpet Tile @ Lounge Area	53.77 SY	70.00	3,763.90
98	F/I LVT (Luxury Vinyl Tile) Flooring	813.71 SF	9.50	7,730.25
99	F/I Rubber Sports Flooring (Seamless, Resilient, and Shock-Absorbing)	504.71 SF	6.00	3,028.26
100			**Flooring Total**	**$22,019.10**
101	**09.6700 Fluid-Applied Flooring**			
102	F/I Integral Epoxy Cove Base	32.84 LF	14.00	459.76
103	F/I Epoxy Resin Flooring	81.01 SF	14.00	1,134.14
104			**Fluid-Applied Flooring Total**	**$1,593.90**
105	**09.9100 Painting**			
106	Paint GWB Walls	9,303.90 SF	1.30	12,095.07
107	Paint Existing GWB Walls (Plan View)	6,776.76 SF	1.30	8,809.79
108	Paint GWB Ceilings	915.98 SF	1.30	1,190.77
109	Paint/Stain Wood Door + HM Frame (Single)	4.00 EA	225.00	900.00
110	Paint Existing HM Door & Frame (Single)	7.00 EA	200.00	1,400.00
111			**Painting Total**	**$24,395.63**
112			**Finishes Total**	**$521,921.34**
113	**10 Specialties**			
114	**10.2800 Bath Accessories**			
115	Grab Bar [ASI 3701-18P (18")]	2.00 EA	20.50	41.00
116	Grab Bar [ASI 3701-36P (36")]	2.00 EA	23.17	46.34
117	Grab Bar [ASI 3701-42P (42")]	2.00 EA	24.00	48.00
118	Coat Hook [ASI 0751 48"]	2.00 EA	9.22	18.44
119	Automatic Hand Dryer [Excel Xlerator Thin Air TA-SI WG Stainless]	2.00 EA	264.00	528.00
120	Hand Dryer Wall Guard [World]	2.00 EA	55.00	110.00

Line	Description	Quantity	Unit Cost	Total
121	Mirror (18"x30") [Bobrick B-166]	2.00 EA	51.59	103.18
122	Trash Receptacle [ASI 04773]	2.00 EA	148.46	296.92
123	Baby Changing Station [ASI 0915 Vertical]	2.00 EA	210.00	420.00
124	Sanitary Napkin Disposal [ASI 0852]	1.00 EA	20.29	20.29
125			**Bath Accessories Total**	**$1,632.17**
126	**10.2900 Toilet Partitions**			
127	F/I Toilet Partitions	4.00 EA	3,900.00	15,600.00
128			**Toilet Partitions Total**	**$15,600.00**
129	**10.5110 Lockers**			
130	F/I Wood Veneer Lockers	29.00 EA	900.00	26,100.00
131			**Lockers Total**	**$26,100.00**
132			**Specialties Total**	**$43,332.17**
133	**11 Equipment**			
134	**11.3100 Appliances**			
135	Washer (High-End)	1.00 EA	2,500.00	2,500.00
136	Dryer (High-End)	1.00 EA	2,400.00	2,400.00
137			**Appliances Total**	**$4,900.00**
138			**Equipment Total**	**$4,900.00**
139	**12 Furnishing**			
140	**12.3600 Countertops**			
141	Template, Fabricate & Install Solid Surface Countertops @ Women's L.R. Bench	22.10 SF	100.00	2,210.00
142	Template, Fabricate & Install Solid Surface Countertops @ Reception Desk	11.92 SF	100.00	1,192.00
143	Template, Fabricate & Install Solid Surface Countertops	93.46 SF	100.00	9,346.00
144	Template, Fabricate & Install Solid Surface Bench @ Steam Room	29.37 SF	100.00	2,937.00
145	Template, Fabricate & Install Solid Surface Countertops @ Towel Disposal Areas	23.37 SF	100.00	2,337.00
146			**Countertops Total**	**$18,022.00**
147	**12.4416 Shower Curtains**			
148	F/I Shower Curtains	5.00 EA	300.00	1,500.00
149			**Shower Curtains Total**	**$1,500.00**
150			**Furnishing Total**	**$19,522.00**
151	**13 Special Construction**			
152	**13.1100 Pools**			
153	Cold Plunge	1.00 LS	30,000.00	30,000.00
154	Pools	1.00 LS	150,000.00	150,000.00
155	F/I Reinforcement Mesh to Stabilize Pool Perimeter	702.00 SF	2.00	1,404.00
156	F/I 3" Shotcrete to Stabilize Pool Perimeter	702.00 SF	12.00	8,424.00
157			**Pools Total**	**$189,828.00**
158	**13.2416 Saunas**			
159	F/I Cedar Sauna Kit (Walls+Ceilings+Benches+Labor)	224.81 SF	84.19	18,926.75

Line	Description	Quantity	Unit Cost	Total
160			**Saunas Total**	**$18,926.75**
161			**Special Construction Total**	**$208,754.75**
162	**21 Fire Suppression**			
163	**21.0000 Sprinkler (Not Included)**			
164	Sprinkler	0.00 EA	0.00	0.00
165			**Sprinkler (Not Included) Total**	**$0.00**
166			**Fire Suppression Total**	**$0.00**
167	**22 Plumbing**			
168	**22.0000 Plumbing**			
169	Plumbing Disconnects Prior to Demolition	1.00 LS	2,500.00	2,500.00
170	Pool-Specific Plumbing	1.00 LS	9,500.00	9,500.00
171	Cold Plunge Specific Plumbing	1.00 LS	4,500.00	4,500.00
172	Connect Pool & Cold Plunge to Existing Water Supply & Drainage System	1.00 LS	2,500.00	2,500.00
173	F/I Tankless Hot Water Heaters (8GPM High-Efficiency)	4.00 EA	5,400.00	21,600.00
174	I/O Commercial Toilet	4.00 EA	1,500.00	6,000.00
175	I/O Bath Lav (Sink) & Faucet	4.00 EA	1,100.00	4,400.00
176	I/O Standard Shower	4.00 EA	1,200.00	4,800.00
177	I/O Custom Shower	1.00 EA	2,500.00	2,500.00
178	I/O Exam Room Sink & Faucet	3.00 EA	1,400.00	4,200.00
179	I/O Wall-Mounted Urinal (Including Rough-In)	1.00 EA	1,600.00	1,600.00
180	I/O Washer	1.00 EA	700.00	700.00
181	I/O Dryer	1.00 EA	700.00	700.00
182			**Plumbing Total**	**$65,500.00**
183	**22.4000 Plumbing Fixtures**			
184	F/O LAV Sink	4.00 EA	600.00	2,400.00
185	F/O Lav Faucet	4.00 EA	250.00	1,000.00
186	F/O Standard Shower Kit	4.00 EA	1,000.00	4,000.00
187	F/O Custom Shower Kit	1.00 EA	2,500.00	2,500.00
188	F/O Commercial Wall-Mounted Toilet + Flushometer	4.00 EA	625.00	2,500.00
189	F/O Wall-Mounted Urinal	1.00 EA	800.00	800.00
190	F/O Exam Room Sink & Faucet	3.00 EA	1,100.00	3,300.00
191			**Plumbing Fixtures Total**	**$16,500.00**
192			**Plumbing Total**	**$82,000.00**
193	**23 Heating, Ventilating and Air-Conditioning**			
194	**23.0000 HVAC**			
195	HVAC (20-Ton System w/Dehumidification, Ventilation, ERVs, etc.)	6,600.00 SF	29.00	191,400.00
196			**HVAC Total**	**$191,400.00**
197			**Heating, Ventilating and Air-Conditioning Total**	**$191,400.00**
198	**26 Electrical**			
199	**26.0000 Electric**			
200	Pool-Specific Electrical	1.00 LS	9,000.00	9,000.00

Line	Description	Quantity	Unit Cost	Total
201	Electric (Per SF Budget)	6,600.00 SF	22.00	145,200.00
202	Electrical Disconnects Prior to Demo (Medium)	1.00 EA	1,700.00	1,700.00
203			**Electric Total**	**$155,900.00**
204	**26.5000 Lighting Fixtures**			
205	Lighting Fixture (Per SF Budget)	6,600.00 SF	4.00	26,400.00
206			**Lighting Fixtures Total**	**$26,400.00**
207			**Electrical Total**	**$182,300.00**
208	**28 Safety And Security**			
209	**28.4600 Fire Alarm**			
210	Fire Alarm (Per SF Budget)	6,600.00 SF	5.50	36,300.00
211			**Fire Alarm Total**	**$36,300.00**
212			**Safety And Security Total**	**$36,300.00**
213	**31 Sitework**			
214	**31.0000 Sitework**			
215	Excavate Foundation	0.12 DAY	2,800.00	336.00
216	Excavate Foundation (Frost Walls) (Sequenced for Underpinning)	1.57 DAY	9,500.00	14,915.00
217	Backfill Frost Walls	1.57 DAY	2,800.00	4,396.00
218	Backfill Stone & Compact	0.15 DAY	2,800.00	420.00
219	F/I 4" Crushed Stone	4.44 CY	115.00	510.60
220			**Sitework Total**	**$20,577.60**
221	**31.1050 Fill Export**			
222	Export Fill	1,146.46 CY	12.00	13,757.52
223			**Fill Export Total**	**$13,757.52**
224	**31.1100 Drainage & Stormwater**			
225	F/I Subsurface Drainage @ Pool	1.00 LS	3,000.00	3,000.00
226	F/I Channel Drains @ Pool Deck	1.00 LS	4,500.00	4,500.00
227			**Drainage & Stormwater Total**	**$7,500.00**
228			**Sitework Total**	**$41,835.12**
229	**Sub-Total (Base Cost)**			**$1,632,932.00**

Estimate Summary



Material [$126,638]
Labor [$0]
SubContractor [$1,396,838]
Equipment [$0]
Other [$109,456]

Description		Total
Sub-Total (Base Cost)		$1,632,932.00
Material	10.0000%	12,663.84
Labor	5.0000%	0.00
SubContractor	5.0000%	69,841.91
Equipment	5.0000%	0.00
Other	5.0000%	5,472.78
Sub-Total (Direct Cost)		$1,720,910.52
Contingency (10%)	10.0000%	172,091.05
General Requirements	2.0000%	37,860.03
Overhead & Profit	10.0000%	193,086.16
Total Estimate		$2,123,947.76