Montana Contracting
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 03/18/2025

Sophia Porrino

Re: Cairo Development Project Rev. 3

Budget Proposal

Montana Contracting will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$14,615,421**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia

Montana Contracting

Accepted By: _____

Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 03/18/2025

Estimate: 2500503 Cairo Development Project Rev. 3

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/ACRE
03 Concrete			
03.1000 Concrete	$206,667	1.41%	3,444.46
05 Metal			
05.0050 Structural Steel	$299,250	2.05%	4,987.50
06 Wood , Plastic and Composites			
06.4000 Dock & Waterfall Deck	$119,700	0.82%	1,995.00
13 Special Construction			
13.1213 Suspension Bridges	$132,678	0.91%	2,211.30
13.1223 Pedestrian Bridges	$99,162	0.68%	1,652.70
13.2416 Saunas	$243,600	1.67%	4,060.00
13.3413 Modular Cabins	$6,987,750	47.81%	116,462.50
22 Plumbing			
22.0000 Plumbing	$81,900	0.56%	1,365.00
26 Electrical			
26.0000 Electric	$865,306	5.92%	14,421.77
26.5000 Lighting Fixtures	$39,375	0.27%	656.25
31 Sitework			
31.0000 Sitework	$631,781	4.32%	10,529.68
31.1100 Drainage & Stormwater	$301,613	2.06%	5,026.88
31.1200 Water Service	$274,733	1.88%	4,578.88
31.2500 Erosion And Sedimentation Controls	$39,375	0.27%	656.25
32 Exterior Improvements			
32.0001 Roads	$333,921	2.28%	5,565.35
33 Utilities			
33.2000 Well	$20,200	0.14%	336.67
33.3100 Septic/Sewer System	$485,100	3.32%	8,085.00
35 Waterway & Marine Construction			
35.4000 Dams and Levees	$534,660	3.66%	8,911.00
Sub-Total (Direct Cost)	**$11,696,770**	**80.03%**	**194,946.17**
Contingency (5%)	$584,839	4.00%	9,747.31
General Conditions	$982,529	6.72%	16,375.48
Fee	$994,810	6.81%	16,580.17
Insurance	$356,474	2.44%	5,941.23
Sub-Total ()	**$14,615,421**	**100.00%**	**243,590.36**
	$0	0.00%	0.00
Total Estimate	**$14,615,421**	**100%**	**243,590.36**

Montana Contracting
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Estimate Description: Cairo Development Project Rev. 3

Scope of Work

Description
03.1000 Concrete
Form & Pour 6" Slab on Grade @ Mirror Cabins
Form & Pour Concrete Piers (8 Piers Per Unit I 2' Diameter I 6' Deep)
Form & Pour 4" Slab on Grade @ Saunas
05.0050 Structural Steel
Fabricate & Erect Steel Frames for Cabins
06.4000 Dock & Waterfall Deck
F/I Dock
F/I Waterfall Deck
13.1213 Suspension Bridges
F/I Cable Bridge
13.1223 Pedestrian Bridges
F/I Dam Bridge (Concrete or Steel)
13.2416 Saunas
Pre-Fabricated Saunas
Assembly & Setup
13.3413 Modular Cabins
Construct & Deliver Modular Cabins (Mid-High End)
Construct & Deliver Mirror Cabins
Crane Rental & Setting of Cabins
22.0000 Plumbing
Cabin Plumbing Connections
Steam & Drainage for Saunas
26.0000 Electric
Cabin Electrical Connections
F/I 2" Conduit for Underground Electrical Service (Schedule 40 PVC)
F/I Primary Electrical Service (1,500-2,000 Amps)
F/I Electrical Panels (400-600 Amps Each)
Unit Electrical Wiring (100-15A Each)
I/O Exterior Lighting Fixtures
F/I 150 kW Diesel Backup Generator
Provide Temp Power for Trailers
Cabin Submetering
F/I Transformers & CT Cabinet

Montana Contracting
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Line-Voltage Wiring to Sewer Ejectror Pumps
F/I Line-Voltage Wiring to Duplex Pumps at Leaching Field
Electrical Connections for Saunas
26.5000 Lighting Fixtures
F/O Exterior Lighting Fixtures (Budget)
31.0000 Sitework
Surveying and On-Site Layout
Mobilization of Equipment
F/I Cabin Umbilicus'
Trail Construction
Water Main Trenching
Sewer Main Trenching
Electrical Conduit Trenching
Fiber Optic Trenching
Excavate for Piers (8 Piers Per Unit I 2' Diameter I 6' Deep)
F/I Crushed Stone Subbase @ Mirror Cabins
F/I 2" Rigid Insulation Below Grade @ Mirror Cabins
Excavate Slabs @ Mirror Cabins
Backfill Slab & Compact @ Mirror Cabins
Total Cut Volume
Subgrade Excavation & Grading for Roads
Backfill Slab & Compact @ Saunas
F/I Crushed Stone @ Saunas
2" Rigid Insulation Below Grade @ Saunas
Excavate Foundation (Slab on Grade) @ Saunas
31.1100 Drainage & Stormwater
Detention Basin Excavation
Stormwater Piping Installation
24" x 48" Catch Basin
Riprap Erosion Protection
31.1200 Water Service
Water Main Testing
Water Main Installation (8” PVC)
F/I Grinder Pumps at Each Cluster of Cabins
31.2500 Erosion And Sedimentation Controls
F/I Silt Fence

Montana Contracting
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Construction Entrance
32.0001 Roads
New Roads
Upgrade Pre-Existing Roads
33.2000 Well
Well Drilling
Well Casing
Well Drive Shoe
Well Grout
Well Pump System
33.3100 Septic/Sewer System
F/I 5,000 Gallon Septic Tank
Leach Field Installation
Distribution Box & Connections
Sewer Piping (6"-8" PVC)
Sanitary Service Connections @ Cabins
35.4000 Dams and Levees
Mobilization
Clearing & Grubbing
Dirt Road Improvement [Grader + Compactor + Gravel]
Excavation & Demolition of Existing Spillway (Assuming Repairs are Not Possible)
Form & Pour 12' Reinforced Concrete Spillway
F/I Riprap Stilling Basin
Repair and Slipline Existing 15" Pipes w/New Valves
Conduct Seepage Testing & Install New Drain System
Regrade 550' Embankment from 2:1 to 3:1 Slope. Compact and Grade Accordingly.
Raise Water Level by 3'-4'
Tree Removal