Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 07/08/2025

Jane Slavin
JSA Architecture & Design Group, LLC

Re: Sam's Window Tinting Design

Budget

Montana Contracting Corp. provides budgetary pricing to furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$470,028**

Attachments:
Schedule of Values

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia

Montana Contracting Corp.

Accepted By: _____

Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 07/08/2025

Estimate: 25034 Sam's Window Tinting Design

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
01 General Requirements			
01.0050 General Requirements	$28,840	6.14%	6.40
02 Existing Conditions			
02.1000 Demolition	$23,770	5.06%	5.27
02.1500 Containers/Waste Removal	$3,200	0.68%	0.71
03 Concrete			
03.1000 Concrete	$3,500	0.74%	0.78
03.1500 Concrete Cutting	$11,680	2.48%	2.59
04 Masonry			
04.1000 Masonry	$3,236	0.69%	0.72
04.5710 Brick	$5,107	1.09%	1.13
05 Metal			
05.7610 Lintels	$3,963	0.84%	0.88
06 Wood , Plastic and Composites			
06.2200 Millwork	$3,870	0.82%	0.86
07 Thermal and Moisture Protection			
07.3000 Roofing (Not Included)	$0	0.00%	0.00
08 Openings			
08.1100 HM Doors, Frames & HW	$10,455	2.22%	2.32
08.3323 Overhead Doors	$20,001	4.26%	4.44
08.8200 Arch. Metal & Glass	$37,845	8.05%	8.39
09 Finishes			
09.2300 Drywall & Carpentry	$31,196	6.64%	6.92
09.2500 Acoustical Ceilings	$14,651	3.12%	3.25
09.3013 Tile & Stone	$25,313	5.39%	5.61
09.6000 Flooring	$20,266	4.31%	4.49
09.9100 Painting	$21,420	4.56%	4.75
10 Specialties			
10.2900 Toilet Partitions	$5,800	1.23%	1.29
11 Equipment			
11.3100 Appliances	$4,600	0.98%	1.02
12 Furnishing			
12.3600 Countertops	$2,002	0.43%	0.44
22 Plumbing			
22.0000 Plumbing	$21,450	4.56%	4.76
22.4000 Plumbing Fixtures	$5,225	1.11%	1.16
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$32,264	6.86%	7.16
26 Electrical			
26.0000 Electric	$36,870	7.84%	8.18
26.5000 Lighting Fixtures	$20,291	4.32%	4.50

Description	Total	Percent of Cost	Cost/SF
31 Sitework			
31.1100 Oil Separator / Trench Drains (Not Included)	$0	0.00%	0.00
32 Exterior Improvements			
32.1600 Concrete Curbs	$1,514	0.32%	0.34
Sub-Total (Direct Cost)	**$398,329**	**84.75%**	**88.34**
Overhead & Profit (21	$83,649	17.80%	18.55
Sub-Total ()	**$481,978**	**102.54%**	**106.89**
Discount	-$11,950	-2.54%	-2.65
Total Estimate	**$470,028**	**100%**	**104.24**

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 07/08/2025

Estimate: 25034 Sam's Window Tinting Design

Takeoff

Description	Quantity	Unit
01 General Requirements		
01.0050 General Requirements		
Supervision (50% Allocation)	5.50	WK
General Labor & Cleanup	2.00	WK
Blueprints (Per Page)	40.00	EA
Assistant Project Manager (10% Allocation)	1.00	WK
Misc. Materials	1.00	LS
Temporary Toilet(s)	3.00	MO
Project Management (20% Allocation)	2.50	WK
02 Existing Conditions		
02.1000 Demolition		
Remove Toilet Partitions	3.00	EA
Remove Front Window	1.00	EA
Remove Front Planter	1.00	LS
Remove Interior Partitions	380.55	LF
Remove Millwork	8.51	LF
Remove Floor Tile	988.44	SF
Remove Wall Tile & Backing	356.48	SF
Remove Flooring	464.63	SF
Remove ACT Ceilings, Lights & Diffusers	4,552.84	SF
Remove Plumbing Fixtures	5.00	EA
Remove Doors & Frames	10.00	EA
Remove Exterior Storefront	12.16	LF
02.1500 Containers/Waste Removal		
30-Yard Containers	3.00	EA
20-Yard Masonry Container	1.00	EA
03 Concrete		
03.1000 Concrete		
Misc. Concrete Patching	1.00	LS
03.1500 Concrete Cutting		
Sawcut Opening for New Storefronts	90.00	LF
Sawcut for Front Facade Storefront	24.15	LF
Sawcut For Trench Drain	8.00	LF
Sawcut Existing CMU Walls for New Overhead Doors	60.00	LF
04 Masonry		
04.1000 Masonry		
Masonry Patching	1.00	LS
F/I CMU Block [8"x8"x16"] @ Front Window	35.46	BLOCK
04.5710 Brick		
Toothing in Brick @ New Openings	1.00	LS
F/I Standard Brick @ Front Facade	372.37	BRICK

Description	Quantity	Unit
05 Metal		
05.7610 Lintels		
F/I Lintels Above Storefronts and Overhead Doors	60.97	LF
06 Wood , Plastic and Composites		
06.2200 Millwork		
F/I Reception Desk (Not Included)	0.00	LF
F/I Lower Cabinets @ Break Room	8.60	LF
07 Thermal and Moisture Protection		
07.3000 Roofing (Not Included)		
Roofing (Not Included)	1.00	EA
08 Openings		
08.1100 HM Doors, Frames & HW		
F/O HM Frame (Single)	7.00	EA
F/O HM Door	1.00	EA
Solid-Core Wood Door	6.00	EA
F/O Door Hardware (Commercial Interior)	6.00	EA
F/O Door Hardware (Commercial Exterior)	1.00	EA
08.3323 Overhead Doors		
F/I Overhead Coiling Doors	3.00	EA
08.8200 Arch. Metal & Glass		
F/I Exterior Storefront Door & HW	1.00	EA
F/I Interior Storefront	220.92	SF
F/I Exterior Storefront	95.52	SF
F/I Waiting Area Storefront Door & HW	1.00	EA
09 Finishes		
09.2300 Drywall & Carpentry		
F/I 5/8" GWB Walls	4,027.10	SF
F/I Blanket Insulation	2,196.60	SF
I/O Interior HM Door, Frame & HW (Single)	6.00	EA
I/O Exterior HM Door, Frame & HW (Single)	1.00	EA
F/I 3-5/8" Metal Stud Framing	2,196.60	SF
F/I Acoustical Sealant	732.20	LF
09.2500 Acoustical Ceilings		
F/I ACT Ceilings [$5/SF Material Allowance]	1,167.45	SF
09.3013 Tile & Stone		
F/I Tile Base ($8/LF Material Allowance)	68.81	LF
F/I Floor Tile ($7/SF Material Allowance]	786.11	SF
Wall Tile (Full Height @ Wet Walls Only) ($7/SF Material Allowance]	148.56	SF
F/I Marble Saddles	2.00	EA
F/I Waterproofing for Wall Tile	148.56	SF
09.6000 Flooring		

Description	Quantity	Unit
F/I 4" Vinyl Base	236.91	LF
Concrete Sealer (2 Coats)	3,342.00	SF
F/I LVT (Luxury Vinyl Tile) Flooring	322.77	SF
09.9100 Painting		
Powerwash Existing Brick Throughout	3,500.00	SF
Paint GWB Walls	2,928.80	SF
Paint Existing Walls	2,249.28	SF
Paint/Stain Wood Door + HM Frame (Single)	6.00	EA
Paint HM Door & Frame (Single)	1.00	EA
Paint Exposed Metal Decking	3,342.17	SF
10 Specialties		
10.2900 Toilet Partitions		
F/I Toilet Partitions	1.00	EA
F/I Urinal Screen	1.00	EA
11 Equipment		
11.3100 Appliances		
F/O Refrigerator	1.00	LS
F/O Washer	1.00	EA
F/O Dryer	1.00	EA
12 Furnishing		
12.3600 Countertops		
Template, Fabricate & Install Solid Surface Countertops @ Break Room ($50/SF Material Allowance)	16.61	SF
22 Plumbing		
22.0000 Plumbing		
Disconnect Existing Plumbing Fixtures	5.00	EA
I/O Commercial Toilet	2.00	EA
I/O Bath Lav (Sink) & Faucet	2.00	EA
I/O Sink & Faucet	1.00	EA
I/O Wall-Mounted Urinal	1.00	EA
I/O Washer	1.00	EA
I/O Dryer	1.00	EA
F/I Hot Water Heater	1.00	EA
22.4000 Plumbing Fixtures		
F/O Pantry Sink	1.00	EA
F/O Pantry Faucet	1.00	EA
F/O LAV Sink	2.00	EA
F/O Lav Faucet	2.00	EA
F/O Commercial Floor-Mounted Toilet + Flushometer	2.00	EA
F/O Wall-Mounted Urinal	1.00	EA
23 Heating, Ventilating and Air-Conditioning		
23.0000 HVAC		

Description	Quantity	Unit
F/I Diffusers, Grills & Registers	1.00	LS
F/I Bathroom Exhaust Fan	1.00	EA
F/I Wash Bay Exhaust Fan	1.00	LS
F/I Wrap Room Exhaust/Dust Control Fan	1.00	LS
F/I Condensate Piping, Hangers & Supports	1.00	LS
F/I Ductwork Insulated	1,108.64	LB
HVAC Startup & Commissioning	1.00	EA
26 Electrical		
26.0000 Electric		
Life Safety Budget (Exit Signs, Bonding, Panel Tie-Ins & Relocations)	4,509.00	SF
Special Equipment Budget (Wash Bay Fan, Wrap Exhaust, Restroom Fans, etc.)	4,509.00	SF
Electrical Disconnects Prior to Demo (Medium)	1.00	EA
General Power Budget (Outlets, Circuits, GFCIs, Switches, etc.)	4,509.00	SF
26.5000 Lighting Fixtures		
Lighting Budget (Shop High-Bays, Office Troffers, Exterior Wall Packs)	4,509.00	SF
31 Sitework		
31.1100 Oil Separator / Trench Drains (Not Included)		
Trench Drains	0.00	LF
32 Exterior Improvements		
32.1600 Concrete Curbs		
F/I Concrete Curb Under Exterior Storefronts	15.94	LF