MONTANA
CONTRACTING

A Custom Builder Creating Distinguished Homes

As you consider building a new home or renovating your current home, you are entering one of the most exciting times of your life. At Montana Contracting we will be there to help with the many decisions you will be making. The best floor plan, the right style, careful choice of materials and finishes, all brought together to create a home as distinct and unique as you are.

MONTANA
CONTRACTING

About Us

Montana Contracting Corp. is a full–service general contractor, construction manager and residential developer. With over 35 years of experience providing quality high-end residential and commercial renovations, Montana Contracting is equipped to handle simple improvements to full scale renovations including ground up projects. We offer our clients a wide variety of construction and building related services anchored by decades of proven success and reliability.

Letter from the President

From Montana's inception in 1984 our firm has grown from a family-owned and operated home builder to a diverse construction management firm building ground-up developments, corporate interiors and hospitality projects. Through our growth and success we have not forgotten the core values and ethics that Montana was founded on. At Montana Contracting, we recognize the challenges in today's marketplace and the expectations of our clientele. We believe in honesty and integrity, doing the right things for the right reasons, and treating people fairly. Each project is pursued with the sense of urgency, excellence and professionalism that our clients expect and deserve.

MONTANA
CONTRACTING

Core Values

Family First
“The homemaker has the ultimate career. All other careers exist for one purpose only – and that is to support the ultimate career.” - C.S. Lewis

Mutual Respect
"True greatness will be achieved through the abundant mind that works selflessly - with mutual respect, for mutual benefit.: - Steven Covey

Collaboration
"Individual commitment to a group effort — that is what makes a team work, a company work, a society work, a civilization work." - Vince Lombardi

Absolute Ownership
"Responsibility equals accountability equals ownership. And a sense of ownership is the most powerful weapon a team or organization can have." - Pat Summitt

Attitude
"Your living is determined not so much by what life brings to you as by the attitude you bring to life; not so much by what happens to you as by the way your mind looks at what happens." - Khalil Gibran

Montana Contracting
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Date: 05/02/2025

Colin Brice
Mapos Design and Architecture Studio

Re: South Hill - The Woodland

Budget Proposal

Montana Contracting will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$1,989,820**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto

Montana Contracting

Accepted By: _____

Date of Acceptance: _____

MONTANA
HOME BUILDERS

Status: Active Estimates
Contact:
Date: 05/02/2025

Estimate: 25022 South Hill - The Woodland

Estimate Totals

Description	Total Estimate	Job %	Cost/Unit
00 Main House	$1,009,844	50.75%	531.50
01 Guest House	$241,803	12.15%	127.26
02 Garage	$151,261	7.60%	79.61
03 Sauna	$48,524	2.44%	25.54
04 Pool	$287,587	14.45%	151.36
05 Outdoor Shower	$7,499	0.38%	3.95
06 General Conditions	$243,301	12.23%	128.05
Total Estimate	**$1,989,820**	**100%**	**1,047.27**

MONTANA
HOME BUILDERS

Status: Active Estimates
Contact:
Date: 05/02/2025

Estimate: 25022 South Hill - The Woodland

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$209,472	10.53%	110.25
03 Concrete			
03.1000 Concrete	$69,234	3.48%	36.44
03.3500 Polished/Sealed Concrete	$25,166	1.26%	13.25
05 Metal			
05.5000 Metal Fabrications	$4,144	0.21%	2.18
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$25,499	1.28%	13.42
06.2200 Millwork	$23,845	1.20%	12.55
06.2300 Closet Interiors	$4,320	0.22%	2.27
06.4001 Wood Framing Materials	$89,757	4.51%	47.24
06.4002 Wood Framing Labor	$76,070	3.82%	40.04
06.6600 Decking	$4,932	0.25%	2.60
07 Thermal and Moisture Protection			
07.2000 Insulation	$59,511	2.99%	31.32
07.2400 Exterior Insulation & Finish Systems (EIFS)	$7,723	0.39%	4.06
07.3000 Roofing	$94,175	4.73%	49.57
07.6600 Gutters & Leaders	$2,541	0.13%	1.34
07.9510 Siding	$138,355	6.95%	72.82
08 Openings			
08.1400 Wood Doors & HW	$18,911	0.95%	9.95
08.1600 Residential Entry Doors & HW	$13,530	0.68%	7.12
08.3700 Garage Doors	$16,400	0.82%	8.63
08.5000 Windows	$58,309	2.93%	30.69
08.8500 Shower Enclosures	$5,586	0.28%	2.94
09 Finishes			
09.2300 Drywall & Carpentry	$44,648	2.24%	23.50
09.3013 Tile & Stone	$15,528	0.78%	8.17
09.6400 Wood Flooring	$2,576	0.13%	1.36
09.9100 Painting	$57,072	2.87%	30.04
10 Specialties			
10.2800 Bath Accessories	$12,357	0.62%	6.50
10.3100 Fireplaces	$2,563	0.13%	1.35
11 Equipment			
11.3100 Appliances	$6,313	0.32%	3.32
11.3200 Outdoor Kitchens/BBQs	$30,369	1.53%	15.98
12 Furnishing			
12.3600 Countertops	$7,769	0.39%	4.09
13 Special Construction			
13.1100 Pools	$200,746	10.09%	105.66

Description	Total	Percent of Cost	Cost/Unit
13.2416 Saunas	$6,148	0.31%	3.24
22 Plumbing			
22.0000 Plumbing	$51,916	2.61%	27.32
22.4000 Plumbing Fixtures	$15,565	0.78%	8.19
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$37,156	1.87%	19.56
23.0500 HVAC Testing & Compliance	$820	0.04%	0.43
26 Electrical			
26.0000 Electric	$67,865	3.41%	35.72
26.5000 Lighting Fixtures	$14,087	0.71%	7.41
27 Communications			
27.1000 Tel/Data	$923	0.05%	0.49
28 Safety And Security			
28.4600 Fire Alarm	$769	0.04%	0.40
31 Sitework			
31.0000 Earthwork	$49,865	2.51%	26.24
31.1100 Drainage & Stormwater	$11,408	0.57%	6.00
32 Exterior Improvements			
32.0000 Exterior Improvements	$1,219	0.06%	0.64
32.0001 Roads	$37,864	1.90%	19.93
32.1400 Hardscaping	$39,379	1.98%	20.73
33 Utilities			
33.2000 Well (Allowance)	$17,789	0.89%	9.36
33.3100 Septic Systems	$32,957	1.66%	17.35
Sub-Total (Direct Cost)	**$1,713,147**	**86.10%**	**901.66**
Overhead & Profit	$256,972	12.91%	135.25
Insurance	$19,701	0.99%	10.37
Total Estimate	**$1,989,820**	**100%**	**1,047.27**

Montana Contracting
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Notes and Clarifications:

1. Pricing is valid for thirty (30) calendar days.
2. All work to be performed during normal working hours. Overtime is not included.
3. Pricing is based on using open shop labor.
4. Permits and fees are not included.
5. Surveying fees are not included. Montana will coordinate stakeouts.
6. Temporary heating is not included. If required, will be billed on time and material basis.
7. Winter additive, ground thawing and/or blankets for concrete is not included.
8. Temporary heat is not included.
9. Pricing for excavation is based on bottom of footing depths indicated on drawings. If additional excavation is required to reach virgin soil additional charges for machine time, labor, concrete, waterproofing and backfilling may be incurred.
10. Rock removal is not included.
11. Snow/ice removal is not included.
12. Dewatering is not included.
13. Removal of unsuitable soils is not included.
14. Landscaping, including topsoil and seeding, is not included.
15. Tree and stump removal is not included.
16. Window treatments are not included.
17. Pricing for well is based on being 60' from the house with a maximum depth of 300'. An additional cost of $20 will be billed for each additional foot thereafter.
18. Pricing for well casing is based on a maximum depth of 50' . An additional cost of $36 will be billed for each additional foot thereafter.
19. Pricing for underground electric is based on a 300' max run.
20. Pricing for septic is based on an above-ground system no further than 100'.
21. Island @ main house kitchen is not included. It is not on the ground floor plan but is shown on the RCP.
22. Appliances for the main house are install only except for the range exhaust hood which will be furnished and installed.
23. Guest house appliances are furnish and install.
24. The roof composition of the additional structures outside the main house are included as wood framing, insulation, plywood sheathing, and GWB.
25. ZIP sheathing is not included.