Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 01/20/2026

Don Petruncola
Tinkelman Architcture

Re: Westerly Development

Budget

Montana Contracting Corp. provides budgetary pricing to furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$10,992,854**

Attachments:
Schedule of Values

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia

Montana Contracting Corp.

Accepted By: _____

Date of Acceptance: _____

Estimate: 25070 Westerly Development

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**01 General Requirements**			
2	**01.0050 General Requirements**			
3	Travel & Auto Expenses (Included in General Conditions)	0.00 EA	0.00	0.00
4	General Supervision (Included in General Conditions)	0.00 WK	0.00	0.00
5	Supervision (Included in General Conditions)	0.00 WK	0.00	0.00
6	Project Coordinator (65% Allocation)	39.00 WK	3,000.00	117,000.00
7	Blueprints & Reproduction	1.00 LS	10,000.00	10,000.00
8	Construction Office Setup	1.00 EA	6,000.00	6,000.00
9	Jobsite Trailer (Included in General Conditions)	0.00 MO	0.00	0.00
10	Project Management (33% Allocation)	20.00 WK	4,000.00	80,000.00
11	Water (Included in General Conditions)	0.00 EA	0.00	0.00
12	Project Executive (Included in General Conditions)	0.00 EA	0.00	0.00
13	Procore Allocation	1.00 LS	20,000.00	20,000.00
14	Temporary Toilet(s) (Included in General Conditions)	0.00 MO	0.00	0.00
15	Professional Cleaning	27,000.00 SF	1.50	40,500.00
16	Cleaning & Waste Management (Included in General Conditions)	0.00 EA	0.00	0.00
17	On-Site Communications (Included in General Conditions)	0.00 EA	0.00	0.00
18	Safety (Included in General Conditions)	0.00 EA	0.00	0.00
19	Site Logistics & Controls (Included in General Conditions)	0.00 EA	0.00	0.00
20	Small Tools & Consumables (Included in General Conditions)	0.00 EA	0.00	0.00
21	Temporary Utilities (Included in General Conditions)	0.00 EA	0.00	0.00
22	Equipment Rental (Included in General Conditions)	0.00 MO	0.00	0.00
23			**General Requirements Total**	**$273,500.00**
24	**01.5000 Temporary Fencing**			
25	8' Temporary Construction Fencing	847.14 LF	15.00	12,707.10
26			**Temporary Fencing Total**	**$12,707.10**
27	**01.7000 Surveying**			
28	Construction Surveying	1.00 LS	30,000.00	30,000.00
29			**Surveying Total**	**$30,000.00**
30			**General Requirements Total**	**$316,207.10**
31	**03 Concrete**			
32	**03.1000 Concrete**			
33	Form & Pour 2'x1' Concrete Footings	50.15 CY	585.00	29,337.75
34	Form & Pour12" Concrete Structural Concrete Slab @ Parking Area Ceiling/2nd Floor	184.50 CY	850.00	156,825.00
35	Form & Pour 6" Concrete Slab	107.47 CY	585.00	62,869.95
36	Form & Pour 4'x4'x1'6" Spread Footings	15.36 CY	850.00	13,056.00
37	Form & Pour 2'6"x2'6" Concrete Columns	48.00 CY	850.00	40,800.00
38	F/I Concrete Stair Pan Infill	153.00 EA	125.00	19,125.00
39	Concrete Pumps	4.00 EA	1,800.00	7,200.00
40			**Concrete Total**	**$329,213.70**

Line	Description	Quantity	Unit Cost	Total
41	**03.3005 Concrete Testing**			
42	Concrete Testing	1.00 LS	12,500.00	12,500.00
43			**Concrete Testing Total**	**$12,500.00**
44			**Concrete Total**	**$341,713.70**
45	**04 Masonry**			
46	**04.1000 Masonry**			
47	F/I CMU Block @ Foundation/1st Floor Walls [8"x8"x16"]	9,275.77 BLOCK	26.00	241,170.02
48	F/I CMU Block @ Stair/Elevator Shafts [8"x8"x16"]	7,682.41 BLOCK	26.00	199,742.66
49			**Masonry Total**	**$440,912.68**
50			**Masonry Total**	**$440,912.68**
51	**05 Metal**			
52	**05.0050 Galvanized Steel Dunnage**			
53	F/I Galvanized Steel Dunnage	527.28 SF	33.00	17,400.24
54			**Galvanized Steel Dunnage Total**	**$17,400.24**
55	**05.0100 Misc. Steel**			
56	F/I Roof Ladder	1.00 LS	2,500.00	2,500.00
57	F/I Steel Pan Stairs & Railings	153.00 EA	1,050.00	160,650.00
58	F/I 1-1/2" Pipe Rail with Spindles (Painted) @ Mechanical Pent House	58.61 LF	175.00	10,256.75
59	F/I 1-1/2" Pipe Rail with Spindles (Painted) @ 4th Floor Terraces	73.39 LF	175.00	12,843.25
60	F/I 1-1/2" Pipe Rail with Spindles (Painted) @ 1st Floor Patios	135.81 LF	175.00	23,766.75
61	F/I Elevator Pit Ladder	1.00 EA	1,500.00	1,500.00
62			**Misc. Steel Total**	**$211,516.75**
63			**Metal Total**	**$228,916.99**
64	**06 Wood , Plastic and Composites**			
65	**06.2000 Finish Carpentry**			
66	I/O Interior Wood Door & F/I Trim	169.00 EA	225.00	38,025.00
67	I/O Pocket Door	4.00 EA	360.00	1,440.00
68	I/O Interior Door Hardware	185.00 EA	50.00	9,250.00
69	F/I Base Molding [1x4 Poplar]	5,652.68 LF	8.00	45,221.44
70	F/I Base Molding	421.73 LF	8.00	3,373.84
71	F/I Door Casing [1x3 Poplar]	5,618.00 LF	8.00	44,944.00
72	F/I Window Casing [1x3 Poplar]	2,543.70 LF	9.00	22,893.30
73			**Finish Carpentry Total**	**$165,147.58**
74	**06.2200 Millwork**			
75	F/I Mailroom Shelving	8.70 LF	550.00	4,785.00
76	F/I 36" Vanity With Integral Countertop	30.00 EA	2,300.00	69,000.00
77	F/I Miscellaneous Decorative Millwork @ Common Areas	1.00 LS	50,000.00	50,000.00
78	F/I Lower Cabinets @ Kitchens	65.20 LF	400.00	26,080.00
79	F/I Upper Cabinets @ Kitchens	92.56 LF	400.00	37,024.00
80	F/I Island Cabinets @ Kitchens	70.62 LF	1,075.00	75,916.50
81	F/I Lower Cabinets @ Communal Kitchen	18.92 LF	600.00	11,352.00

Line	Description	Quantity	Unit Cost	Total
82	F/I Upper Cabinets @ Communal Kitchen	19.20 LF	550.00	10,560.00
83	F/I Full-Height Cabinets @ Kitchens	34.49 LF	825.00	28,454.25
84			**Millwork Total**	**$313,171.75**
85	**06.2300 Closet Interiors**			
86	F/I Closet Interiors (Hat Shelf & Rod/Basic Storage)	532.54 LF	60.00	31,952.40
87			**Closet Interiors Total**	**$31,952.40**
88	**06.4001 Wood Framing Materials**			
89	F/O 2x4 PT	3,960.09 LF	1.68	6,652.95
90	F/O 2x4 PT	421.73 LF	1.90	799.60
91	F/O 2x4 DF	7,920.18 LF	1.68	13,305.90
92	F/O 2x4 DF	843.46 LF	1.63	1,376.53
93	F/O 2x4 Studs	30,699.29 LF	1.68	51,574.82
94	F/O 2x4 Studs	3,807.57 LF	1.61	6,122.57
95	F/O 2x6 DF	5,077.77 LF	1.50	7,616.69
96	F/O 2x6 Studs	12,782.87 LF	1.50	19,174.33
97	F/O 4x8x1/2" CDX Fir Plywood	16,944.97 SF	1.77	30,007.44
98	F/O 4x8x5/8" CDX Fir Plywood	13,149.35 SF	2.21	29,071.35
99	F/O 4x8x3/4" TG Advantech Plywood	25,494.18 SF	2.06	52,529.73
100	F/O 11-7/8" TJI 360 I-Joist	2,918.01 LF	9.12	26,612.25
101	F/O Roof Trusses	7,062.99 LF	12.00	84,755.88
102	F/O Open Web Floor Joists	21,964.28 LF	9.00	197,678.52
103			**Wood Framing Materials Total**	**$527,278.56**
104	**06.4002 Wood Framing Labor**			
105	I/O Interior Framed Wall	40,807.02 SF	2.50	102,017.55
106	I/O Interior Framed Wall	5,060.76 SF	3.00	15,182.28
107	I/O Floor Framing (Joists & Subfloor)	29,031.16 SF	4.50	130,640.23
108	I/O Exterior Wall Framing & Sheathing @ 2nd Floor	16,944.97 SF	5.00	84,724.85
109	I/O Roof Trusses & Sheathing	9,417.32 SF	5.00	47,086.60
110	I/O Roof Framing & Sheathing	3,732.03 SF	5.00	18,660.15
111			**Wood Framing Labor Total**	**$398,311.66**
112			**Wood , Plastic and Composites Total**	**$1,435,861.95**
113	**07 Thermal and Moisture Protection**			
114	**07.1000 Waterproofing**			
115	F/I Damproofing at Frost Walls	2,191.00 SF	4.50	9,859.50
116	F/I Crystallline Waterproofing @ Elevator Pit [Aqua-Fin or Equal]	1.00 EA	2,700.00	2,700.00
117			**Waterproofing Total**	**$12,559.50**
118	**07.2000 Insulation**			
119	F/I Tub Trap Insulation (Thermal)	20.00 EA	125.00	2,500.00
120	F/I Sound Deadening Insulation	44,887.72 SF	1.50	67,331.61
121	F/I R-21 Fiberglass Batt @ Exterior Walls	16,944.97 SF	1.51	25,586.90
122	F/I R-21 Closed-Cell @ 1st Floor Exterior Furred 2x4 Walls	5,566.84 SF	4.90	27,277.52

Line	Description	Quantity	Unit Cost	Total
123	F/I R-30 Rockwool Insulation	24,754.19 SF	1.99	49,260.84
124	F/I R-49 Spray-Foam @ Roof	12,970.87 SF	9.10	118,034.91
125			**Insulation Total**	**$289,991.78**
126	**07.3000 Roofing**			
127	Flash Roof--Mounted Condensers on Dunnage	22.00 EA	900.00	19,800.00
128	F/I Overflow Scuppers & Downspouts	2.00 EA	2,500.00	5,000.00
129	F/I 6" K-Style Gutters	500.00 LF	15.00	7,500.00
130	F/I 6" K-Style Leaders	500.00 LF	15.00	7,500.00
131	F/I CertainTeed Landmark Pro Asphalt Roof Shingles + Ice & Water Shield/Drip Edge & Ridge Cap	10,359.06 SF	8.00	82,872.48
132	F/I EPDM Roofing Assembly [Cover Board + Polyiso Insulation + Membrane + Flashings]	3,908.90 SF	26.00	101,631.40
133	F/I EPDM Roofing Assembly @ Overhang	196.33 SF	26.00	5,104.58
134	F/I EPDM Roof at Parapet Walls	574.10 SF	18.00	10,333.80
135	Flash Roof Drain (Provided by Plumber)	8.00 EA	950.00	7,600.00
136	F/I Standing Seam Sheet Metal Roofing	246.57 SF	23.50	5,794.40
137	F/I .050 Aluminum Coping	138.72 LF	55.00	7,629.60
138			**Roofing Total**	**$260,766.26**
139	**07.6200 Sheet Metal Flashing And Trim**			
140	F/I Aluminum Band Fascia @ Facade	409.41 LF	24.50	10,030.55
141	F/I 12" Aluminum Fascia (Breakmetal)	961.23 LF	24.50	23,550.14
142			**Sheet Metal Flashing And Trim Total**	**$33,580.69**
143	**07.7200 Roof Accessories**			
144	F/I Roof Access Hatch	1.00 EA	5,500.00	5,500.00
145			**Roof Accessories Total**	**$5,500.00**
146	**07.7600 Roof Pavers**			
147	F/I Roof Pavers on Adjustable Pedelstals @ 3rd & 4th Floor Terrace	641.65 SF	42.00	26,949.30
148			**Roof Pavers Total**	**$26,949.30**
149	**07.9510 Siding**			
150	James Hardie Fiber Cement Siding + Furring [Gray Slate Panel]	4,751.82 SF	15.00	71,277.30
151	F/I James Hardie Fiber Cement Column Wrap [Gray Slate]	689.40 SF	15.00	10,341.00
152	James Hardie Vertical Lap Siding + Furring [Iron Gray]	8,066.95 SF	17.50	141,171.63
153	James Hardie Lap Siding [Arctic White]	2,970.26 SF	12.00	35,643.12
154	F/I Tyvek Housewrap	16,944.97 SF	1.33	19,063.99
155	F/I Tyvek Tape	16,944.97 SF	0.41	6,945.66
156	F/I Wood Clad Panel Siding [$14/SF Material Allowance]	1,274.25 SF	25.10	31,983.68
157	F/I James Hardie Trim Board	2,519.00 LF	18.00	45,342.00
158			**Siding Total**	**$361,768.38**
159			**Thermal and Moisture Protection Total**	**$991,115.91**
160	**08 Openings**			
161	**08.1100 Doors, Frames & HW**			
162	Master Keying	1.00 LS	3,500.00	3,500.00

Line	Description	Quantity	Unit Cost	Total
163	F/O HM Frame (Single)	61.00 EA	385.00	23,485.00
164	F/O HM Door	32.00 EA	425.00	13,600.00
165	F/O Insulated HM Door	9.00 EA	750.00	6,750.00
166	F/O 1-3/4" Solid-Core Wood Door (Unit Entry)	20.00 EA	1,400.00	28,000.00
167	F/O Door Hardware (Commercial Interior)	24.00 EA	500.00	12,000.00
168	F/O Door Hardware @ Interior Common Doors	4.00 EA	700.00	2,800.00
169	F/O Door Hardware (Egress)	4.00 EA	1,200.00	4,800.00
170	F/O Door Hardware (Exterior)	9.00 EA	1,200.00	10,800.00
171	F/O Unit Entry Door Hardware	20.00 EA	650.00	13,000.00
172			**Doors, Frames & HW Total**	**$118,735.00**
173	**08.1400 Pre-Hung Wood Doors & HW**			
174	F/O 1-3/8" Solid-Core Paint-Grade Wood Door (Single)	133.00 EA	500.00	66,500.00
175	F/O 1-3/8" Solid-Core Paint-Grade Wood Door (Pair)	24.00 EA	1,000.00	24,000.00
176	F/O Pocket Door with Kit	4.00 EA	700.00	2,800.00
177	F/O Interior Door Locksets	185.00 EA	100.00	18,500.00
178			**Pre-Hung Wood Doors & HW Total**	**$111,800.00**
179	**08.5000 Windows**			
180	F/O Type D Windows [Aluminum Clad Bath/Utility Windows]	454.86 SF	70.00	31,840.20
181	F/O Type A Windows [Aluminum Clad Standard Single]	1,073.48 SF	45.00	48,306.60
182	F/O Type C Windows [Aluminum Clad 3-Wide Mulled Units]	789.53 SF	65.00	51,319.45
183	F/O Type B Windows [Aluminum Clad 2-Wide Mulled Units]	986.66 SF	55.00	54,266.30
184	F/O Type E Windows [Aluminum Clad Tall Vertical Fixed Windows]	209.19 SF	60.00	12,551.40
185	F/I Exterior Single Doors [Aluminum Clad]	6.00 EA	1,800.00	10,800.00
186			**Windows Total**	**$209,083.95**
187	**08.8200 Arch. Metal & Glass**			
188	F/I Exterior Storefront Doors, Transoms, Sidelites & HW	4.00 EA	6,400.00	25,600.00
189	F/I Exterior Glass Storefront System	436.24 SF	95.00	41,442.80
190			**Arch. Metal & Glass Total**	**$67,042.80**
191	**08.8500 Shower Enclosures**			
192	F/I Shower Enclosure	30.00 EA	2,000.00	60,000.00
193			**Shower Enclosures Total**	**$60,000.00**
194			**Openings Total**	**$566,661.75**
195	**09 Finishes**			
196	**09.2300 Drywall & Carpentry**			
197	F/I 5/8" GWB Walls (Level 4 Finish)	117,617.58 SF	2.65	311,686.60
198	F/I 7/8" Hat Channel + Two (2) Layers of 5/8" Type X Ceilings (Level 4 Finish)	35,489.49 SF	5.25	186,319.84
199	F/I 5/8" GWB Walls (Level 4 Finish)	5,060.76 SF	3.25	16,447.47
200	I/O Bath Accessories	20.00 BATH	500.00	10,000.00
201	I/O Fire Extinguisher Cabinet	10.00 EA	200.00	2,000.00
202	I/O Interior HM Door, Frame & HW (Single)	48.00 EA	275.00	13,200.00

Line	Description	Quantity	Unit Cost	Total
203	I/O Exterior HM Door, Frame & HW (Single)	13.00 EA	350.00	4,550.00
204			**Drywall & Carpentry Total**	**$544,203.91**
205	**09.3013 Tile & Stone**			
206	F/I Floor Tile @ 2nd Floor Elevator Lobby ($10/SF Material Allowance)	144.23 SF	26.00	3,749.98
207	F/I Floor Tile @ Laundry Rooms ($7/SF Material Allowance)	1,220.58 SF	22.70	27,707.16
208	F/I Floor Tile @ Bathrooms ($7/SF Material Allowance)	1,255.74 SF	22.70	28,505.29
209	F/I Floor Tile @ Community Room & Kitchen ($7/SF Material Allowance)	637.24 SF	22.70	14,465.35
210	F/I Floor Tile @ Lobby Mail Room ($7/SF Material Allowance)	735.21 SF	22.70	16,689.27
211	F/I Floor Tile @ 3rd Floor Elevator Lobby ($10/SF Material Allowance)	106.91 SF	26.00	2,779.66
212	F/I Floor Tile @ 4th Floor Elevator Lobby ($7/SF Material Allowance)	93.00 SF	22.70	2,111.10
213	F/I Wall Tile @ Tubs ($7/SF Material Allowance)	650.18 SF	22.70	14,759.09
214	F/I Wall Tile @ Showers ($7/SF Material Allowance)	629.24 SF	22.70	14,283.75
215	F/I Mud Job at Shower	10.00 EA	500.00	5,000.00
216	F/I Waterproofing for Floor Tile	2,476.32 SF	4.50	11,143.44
217			**Tile & Stone Total**	**$141,194.09**
218	**09.6000 Flooring**			
219	F/I Acoustical Underlayment @ LVT Areas	16,037.34 SF	2.40	38,489.62
220	F/I Walkoff Mat @ Main Entrance ($60/SY Material Allowance]	5.94 SY	91.50	543.51
221	F/I Rolled Rubber Flooring @ Fitness Center ($11/SF Material Allowance)	336.81 SF	20.60	6,938.29
222	F/I Carpet Tile @ Message Room ($50/SY Material Allowance]	12.23 SY	70.00	856.10
223	F/I Broadloom Carpet @ 2nd Floor Corridors ($35/SY Material Allowance]	70.35 SY	53.50	3,763.73
224	F/I Broadloom Carpet @ 3rd Floor Corridors ($35/SY Material Allowance]	78.22 SY	53.50	4,184.77
225	F/I LVT (Luxury Vinyl Tile) Flooring @ Units ($4.50/SF Material Allowance)	16,037.34 SF	8.45	135,515.53
226			**Flooring Total**	**$190,291.55**
227	**09.9100 Painting**			
228	Paint GWB Walls	117,617.58 SF	1.25	147,021.99
229	Paint GWB Walls	5,060.76 SF	1.30	6,578.99
230	Paint Base Molding	5,652.68 LF	3.00	16,958.04
231	Paint Base Molding	421.73 LF	3.50	1,476.06
232	Paint GWB Ceilings	32,584.71 SF	1.25	40,730.90
233	Paint/Stain Wood Doors & Casing	173.00 EA	225.00	38,925.00
234	Paint/Stain Wood Door + HM Frame (Single)	20.00 EA	375.00	7,500.00
235	Paint Window Casing	2,543.70 LF	3.00	7,631.10
236	Paint HM Door & Frame (Single)	41.00 EA	325.00	13,325.00
237			**Painting Total**	**$280,147.08**
238			**Finishes Total**	**$1,155,836.63**
239	**10 Specialties**			
240	**10.0000 Specialties**			
241	F/I Knox Box	1.00 EA	1,500.00	1,500.00
242			**Specialties Total**	**$1,500.00**
243	**10.1400 Signage**			

Line	Description	Quantity	Unit Cost	Total
244	F/I Exterior Identification & Address Signage	1.00 LS	3,500.00	3,500.00
245	F/I Life Safety & Code Signage	1.00 LS	5,000.00	5,000.00
246	F/I ADA & Accessibility Signage	1.00 LS	4,000.00	4,000.00
247	F/I Wayfinding & Operational Signage	1.00 LS	5,000.00	5,000.00
248	F/I Fire Department Connection Signage	1.00 LS	750.00	750.00
249	F/I Roof Load/Snow Load Signage	1.00 EA	750.00	750.00
250	F/I Mechanical/Hazard Signage	1.00 LS	1,000.00	1,000.00
251			**Signage Total**	**$20,000.00**
252	**10.2800 Bath Accessories**			
253	F/O Bath Accessories Budget	20.00 EA	800.00	16,000.00
254			**Bath Accessories Total**	**$16,000.00**
255	**10.4400 Fire Protection Specialties**			
256	Fire Extinguisher Cabinet + FE	10.00 EA	350.00	3,500.00
257			**Fire Protection Specialties Total**	**$3,500.00**
258	**10.5500 Mailboxes**			
259	F/I Centralized Mailbox System	1.00 LS	10,500.00	10,500.00
260			**Mailboxes Total**	**$10,500.00**
261			**Specialties Total**	**$51,500.00**
262	**11 Equipment**			
263	**11.3100 Appliances**			
264	F/O Washer (Front-Load)	20.00 EA	850.00	17,000.00
265	F/O Dryer (Front-Load)	20.00 EA	800.00	16,000.00
266	F/O Refrigerator (18-21 CU)	20.00 EA	1,500.00	30,000.00
267	F/O Refrigerator @ Communal Kitchen	1.00 EA	2,000.00	2,000.00
268	F/O Dishwasher	20.00 EA	850.00	17,000.00
269	F/O 30" Electric Range	20.00 EA	1,100.00	22,000.00
270	F/O Electric Range @ Communal Kitchen	1.00 EA	2,500.00	2,500.00
271	F/O Above Range Microwave @ Communal Kitchen	1.00 EA	450.00	450.00
272	F/O Above Range Microwave	10.00 EA	450.00	4,500.00
273			**Appliances Total**	**$111,450.00**
274	**11.8200 Trash Compactor (Not Included)**			
275	Trash Compactor (Not Included)	0.00 EA	0.00	0.00
276			**Trash Compactor (Not Included) Total**	**$0.00**
277			**Equipment Total**	**$111,450.00**
278	**12 Furnishing**			
279	**12.2000 Window Treatments**			
280	F/I Fabric Roller Window Shades	88.00 EA	350.00	30,800.00
281			**Window Treatments Total**	**$30,800.00**
282	**12.3600 Countertops**			
283	Template, Fabricate & Install Granite Countertops ($55/SF Material Allowance)	368.53 SF	125.00	46,066.25

Line	Description	Quantity	Unit Cost	Total
284	Communal Kitchen Template, Fabricate & Install Granite Countertops ($45/SF Material Allowance)	41.82 SF	110.00	4,600.20
285			**Countertops Total**	**$50,666.45**
286	**12.9313 Site Furnishings**			
287	F/I Bike Rack (Galvanized)	6.00 EA	1,329.00	7,974.00
288	F/I Benches	6.00 EA	2,500.00	15,000.00
289	Miscellaneous Site Furnishings	1.00 LS	10,000.00	10,000.00
290			**Site Furnishings Total**	**$32,974.00**
291			**Furnishing Total**	**$114,440.45**
292	**13 Special Construction**			
293	**13.2800 Recreation Area (Not Included)**			
294	Recreation Area (Not Included)	0.00 LS	0.00	0.00
295			**Recreation Area (Not Included) Total**	**$0.00**
296			**Special Construction Total**	**$0.00**
297	**14 Conveying System**			
298	**14.2000 Elevators**			
299	F/I MRL Traction Passenger Elevator (2,100lb Capacity w/Standard Finishes))	4.00 EA	47,500.00	190,000.00
300			**Elevators Total**	**$190,000.00**
301			**Conveying System Total**	**$190,000.00**
302	**21 Fire Suppression**			
303	**21.0000 Sprinkler (NFPA 13R System)**			
304	F/I Early Response Sprinkler Heads	27,000.00 SF	0.70	18,900.00
305	Design, Shop Drawings & Coordination	27,000.00 SF	0.35	9,450.00
306	F/I Testing, Permits, Inspections and Signoff	1.00 LS	15,000.00	15,000.00
307	F/I FDC & Exterior Tie-In	27,000.00 SF	0.35	9,450.00
308	F/I Standpipes & Riserse	27,000.00 SF	0.60	16,200.00
309	F/I Piping & Fittings	27,000.00 SF	1.55	41,850.00
310	F/I Sprinkler System @ Parking Area	4,600.00 SF	8.00	36,800.00
311			**Sprinkler (NFPA 13R System) Total**	**$147,650.00**
312			**Fire Suppression Total**	**$147,650.00**
313	**22 Plumbing**			
314	**22.0000 Plumbing**			
315	F/I Water Meter, Backflow Preventer, and Main Service Tie-In	1.00 LS	18,000.00	18,000.00
316	F/I Sanitary & Vent Piping	27,000.00 SF	3.75	101,250.00
317	F/I Domestic Water Distribution (Risers & Branches)	27,000.00 SF	3.25	87,750.00
318	F/I Storm/Roof Drain Piping	27,000.00 SF	0.60	16,200.00
319	F/I Hose Bibs	6.00 EA	550.00	3,300.00
320	I/O Residential Toilet	30.00 EA	250.00	7,500.00
321	I/O Bath Lav (Sink) & Faucet	30.00 EA	250.00	7,500.00
322	I/O Standard Shower	10.00 EA	750.00	7,500.00
323	I/O Standard Bathtub	20.00 EA	650.00	13,000.00

Line	Description	Quantity	Unit Cost	Total
324	I/O Sink & Faucet	20.00 EA	275.00	5,500.00
325	I/O Appliance	40.00 EA	175.00	7,000.00
326	I/O Dishwasher	20.00 EA	250.00	5,000.00
327	F/I Refrigerator Waterline	10.00 EA	250.00	2,500.00
328	F/I Sump Pump	1.00 EA	6,800.00	6,800.00
329	F/I Residential Hot Water Heater (50-Gallon Electric)	20.00 EA	3,200.00	64,000.00
330	F/I Hot Water Heater @ Common Area Kitchen (20-Gallon Electric)	1.00 EA	2,500.00	2,500.00
331	F/I Roof Drain	8.00 EA	1,500.00	12,000.00
332			**Plumbing Total**	**$367,300.00**
333	**22.4000 Plumbing Fixtures**			
334	F/O Kitchen Sink	20.00 EA	525.00	10,500.00
335	F/O Kitchen Faucet	20.00 EA	475.00	9,500.00
336	F/O Lav Sink	30.00 EA	400.00	12,000.00
337	F/O Lav Faucet	30.00 EA	300.00	9,000.00
338	F/O Residential Toilet	30.00 EA	500.00	15,000.00
339	F/O Standard Bathtub	20.00 EA	850.00	17,000.00
340	F/O Standard Shower Kit	30.00 EA	425.00	12,750.00
341			**Plumbing Fixtures Total**	**$85,750.00**
342			**Plumbing Total**	**$453,050.00**
343	**23 Heating, Ventilating and Air-Conditioning**			
344	**23.0000 HVAC**			
345	F/I Controls, Start-Up, TAB, Permits & Closeout	27,000.00 SF	1.05	28,350.00
346	F/I Roof Condensers (1 per unit + 2 amenity)	27,000.00 SF	4.25	114,750.00
347	F/I Refrigerant Piping, Risers, Line Sets, Insulation, Firestopping Allowance	27,000.00 SF	3.25	87,750.00
348	F/I Ductwork and Air Distribution	27,000.00 SF	3.10	83,700.00
349	F/I Ventilation and Exhaust Systems	27,000.00 SF	1.60	43,200.00
350	F/I In-Unit Equipment (Air Handler/Fan Coil)	27,003.64 SF	3.75	101,263.65
351			**HVAC Total**	**$459,013.65**
352			**Heating, Ventilating and Air-Conditioning Total**	**$459,013.65**
353	**26 Electrical**			
354	**26.0000 Electric**			
355	F/I Underground Electrical Service + Distribution (120/208V, 1200A Service)	320.00 LF	295.00	94,400.00
356	F/I Switch Gear (1200A 120/208V, Utility Transformer by Utility)	1.00 LS	50,000.00	50,000.00
357	F/I Conduit & Wire for Site Lighting	1.00 LS	20,000.00	20,000.00
358	F/I Electrical Power @ Common Areas	5,044.97 SF	10.00	50,449.70
359	F/I Electrical Power @ Units	21,686.24 SF	12.00	260,234.88
360	F/I EV Charging Station	3.00 EA	7,500.00	22,500.00
361	Wire Mechanical Equipment	1.00 LS	55,000.00	55,000.00
362	I/O Bollard Style Lighting Fixture Budget	9.00 EA	650.00	5,850.00
363	I/O Exterior Light Poles	5.00 EA	2,400.00	12,000.00

Line	Description	Quantity	Unit Cost	Total
364	I/O Surface-Mounted Exterior Lighting Fixtures	14.00 EA	450.00	6,300.00
365	F/I 100Amp Panel @ Each Unit Including Risers	20.00 EA	3,200.00	64,000.00
366	F/I 200Amp Panel For Building Service Including Feeders	2.00 EA	8,000.00	16,000.00
367			**Electric Total**	**$656,734.58**
368	**26.3600 Generators & Transfer Switches**			
369	F/I Generator + ATS (Not Included)	0.00 EA	0.00	0.00
370			**Generators & Transfer Switches Total**	**$0.00**
371	**26.5000 Lighting Fixtures**			
372	F/O Lighting Fixtures @ Units	21,686.24 SF	4.75	103,009.64
373	F/O Lighting Fixtures @ Common Areas	10,002.77 SF	1.50	15,004.16
374	F/O Bollard Style Lighting Fixtures	9.00 EA	1,200.00	10,800.00
375	F/O Light Poles	5.00 EA	2,500.00	12,500.00
376	F/O Surface Mounted Exterior Lighting Fixture	14.00 EA	350.00	4,900.00
377			**Lighting Fixtures Total**	**$146,213.80**
378			**Electrical Total**	**$802,948.38**
379	**27 Communications**			
380	**27.1000 Low Voltage**			
381	F/I Low-Voltage Rough-In (Data/TV)	27,000.00 SF	3.00	81,000.00
382			**Low Voltage Total**	**$81,000.00**
383	**27.5123 Residential Intercommunications & Entry System**			
384	F/I Residential Intercommunications & Entry System	1.00 LS	24,000.00	24,000.00
385			**Residential Intercommunications & Entry System Total**	**$24,000.00**
386			**Communications Total**	**$105,000.00**
387	**28 Safety And Security**			
388	**28.4600 Fire Alarm (Advanced Multi-Criteria)**			
389	F/I Notification Devices	27,000.00 SF	0.80	21,600.00
390	F/I Wiring, Conduit & Backboxes	27,000.00 SF	1.25	33,750.00
391	Testing, Programming, Inspections & Closeout	27,000.00 SF	0.70	18,900.00
392	F/I Advanced Multi-Criteria Detection Devices	27,000.00 SF	2.65	71,550.00
393	F/I Fire Alarm Control Panel & Head End	27,000.00 SF	0.80	21,600.00
394			**Fire Alarm (Advanced Multi-Criteria) Total**	**$167,400.00**
395	**28.4610 Security**			
396	F/I Security System	1.00 EA	25,000.00	25,000.00
397			**Security Total**	**$25,000.00**
398			**Safety And Security Total**	**$192,400.00**
399	**31 Sitework**			
400	**31.0000 Earthwork**			
401	Soil Compaction Tests	1.00 LS	7,500.00	7,500.00
402	Excavate Foundation (Slab on Grade)	4.44 DAY	6,000.00	26,640.00
403	Excavate Foundation @ Trash Enclosure (Slab on Grade)	0.11 DAY	6,000.00	660.00
404	Excavate Foundation (Frost Walls)	8.36 DAY	6,000.00	50,160.00

Line	Description	Quantity	Unit Cost	Total
405	Backfill Frost Walls	4.18 DAY	6,000.00	25,080.00
406	Backfill Slab & Compact	5.55 DAY	6,000.00	33,300.00
407	Backfill Slab & Compact @ Trash Enclosure	0.14 DAY	6,000.00	840.00
408	F/I 2" Rigid Insulation Below Grade	6,000.00 SF	2.75	16,500.00
409	F/I 2" Rigid Insulation Below Grade Vertical	2,410.10 SF	2.70	6,507.27
410	Trenching & Backfill for Sanitary Sewer Piping	317.77 LF	16.00	5,084.32
411	Trenching, Sand and Backfill Utility Trench for Underground Water Service	432.05 LF	22.00	9,505.10
412	Stumping & Strip Topsoil and Stockpile on Site for Later Use	47,752.53 SF	0.75	35,814.40
413	Import of Structural Fill	2,666.67 CY	28.00	74,666.76
414			**Earthwork Total**	**$292,257.85**
415	**31.1050 Fill Export (Not Included)**			
416	Fill Export (Not Included)	0.00 CY	0.00	0.00
417			**Fill Export (Not Included) Total**	**$0.00**
418	**31.1100 Drainage & Stormwater**			
419	Drainage & Stormwater Budget	1.00 LS	300,000.00	300,000.00
420			**Drainage & Stormwater Total**	**$300,000.00**
421	**31.1150 Sanitary Sewer**			
422	F/I 6" PVC SDR-35 Piping (Including Trenching & Backfill)	317.77 LF	150.00	47,665.50
423	Road Demo and Restoration for Sewer Connection + Traffic Control & Steel Plates	1.00 EA	6,000.00	6,000.00
424			**Sanitary Sewer Total**	**$53,665.50**
425	**31.1200 Water & Fire Service**			
426	F/I 2" Copper Service Line From Street To Building	280.46 LF	250.00	70,115.00
427	F/I 6" Sprinkler Water Service From Street To Building	432.05 LF	350.00	151,217.50
428	F/I Fire Hydrant w/Valve Assembly	1.00 EA	8,500.00	8,500.00
429			**Water & Fire Service Total**	**$229,832.50**
430	**31.1300 Site Clearing**			
431	Site Clearing	47,752.53 SF	1.25	59,690.66
432			**Site Clearing Total**	**$59,690.66**
433	**31.2300 Rock Hammering (Not Included)**			
434	Rock Hammering (Not Included)	1.00 LS	0.00	0.00
435			**Rock Hammering (Not Included) Total**	**$0.00**
436	**31.2500 Erosion And Sedimentation Controls**			
437	F/I Silt Fence	1,500.00 LF	6.00	9,000.00
438	F/I Construction Entrance	1.00 EA	5,500.00	5,500.00
439			**Erosion And Sedimentation Controls Total**	**$14,500.00**
440			**Sitework Total**	**$949,946.51**
441	**32 Exterior Improvements**			
442	**32.1200 Paving**			
443	F/I 8" Subbase	22,726.35 SF	2.50	56,815.88
444	F/I 6" Base Course (Two 3" Lifts)	22,726.35 SF	5.00	113,631.75

Line	Description	Quantity	Unit Cost	Total
445	F/I 2" Top Course (Mix I-4/I-5)	22,726.35 SF	3.25	73,860.64
446			**Paving Total**	**$244,308.27**
447	**32.1400 Hardscaping**			
448	F/I Unit Pavers	779.68 SF	27.00	21,051.36
449			**Hardscaping Total**	**$21,051.36**
450	**32.1500 Fencing**			
451	F/I 4' Chain-Link Fencing @ Top Of Retaining Wall	253.39 LF	50.00	12,669.50
452	F/I 8' Vinyl Double Gate @ Trash Enclosure	1.00 EA	1,500.00	1,500.00
453	F/I 8' Vinyl Fencing @ Trash Enclosure	53.44 LF	55.00	2,939.20
454			**Fencing Total**	**$17,108.70**
455	**32.1600 Site Concrete**			
456	F/I Concrete Curb	1,465.05 LF	29.00	42,486.45
457	F/I 4" Sidewalk w/6"Aggregate Base	1,577.36 SF	14.50	22,871.72
458	F/I Monolithic Sidewalk	1,668.02 SF	16.50	27,522.33
459	F/I Light Poll Bases	5.00 EA	2,200.00	11,000.00
460	F/I 5" Bollards @ Trash Enclosure	6.00 EA	1,650.00	9,900.00
461			**Site Concrete Total**	**$113,780.50**
462	**32.1723 Pavement Markings**			
463	Basic Striping (4” standard yellow/white lines, water-based paint)	1.00 LS	6,000.00	6,000.00
464			**Pavement Markings Total**	**$6,000.00**
465	**32.3200 Retaining Walls**			
466	F/I Block Retaining Wall Up To 3' In Elevation Change	1,304.84 SF	65.00	84,814.60
467			**Retaining Walls Total**	**$84,814.60**
468	**32.9300 Landscaping (Not Included)**			
469	Landscaping (Not Included)	0.00 EA	0.00	0.00
470			**Landscaping (Not Included) Total**	**$0.00**
471	**32.9620 Site Signage**			
472	F/I Parking/Traffic Signs	7.00 EA	500.00	3,500.00
473			**Site Signage Total**	**$3,500.00**
474			**Exterior Improvements Total**	**$490,563.43**
475	**Sub-Total (Base Cost)**			**$9,545,189.13**

Estimate Summary



Description		Total
Sub-Total (Base Cost)		$9,545,189.13
Sub-Total (Direct Cost)		$9,545,189.13
Permits & Fees (Not Included)		0.00
General Conditions	6.5000%	620,437.29
CM Fee	5.5000%	559,109.45
Insurance	2.5000%	268,118.40
Total Estimate		$10,992,854.27