Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 09/12/2025

Katina Bermeo
Bermeo Group INC
119 Main Street
Nyack, NY 10960

Re: 32 South Franklin St. Nyack NY

Budget Proposal

Montana Contracting Corp. hereby proposes all materials, labor and supervision in accordance with drawings dated for the sum of **$2,465,608**

Attachments:
Schedule of Values

Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto

Montana Contracting Corp.

Accepted By: _____

Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 09/12/2025

Estimate: 25044 32 South Franklin St. Nyack NY

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$169,420	6.87%	24.73
02 Existing Conditions			
02.1000 Demolition	$49,053	1.99%	7.16
02.1500 Containers/Waste Removal	$8,670	0.35%	1.27
03 Concrete			
03.1000 Concrete	$75,875	3.08%	11.08
05 Metal			
05.0100 Handrails & Egress Ladders	$22,881	0.93%	3.34
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$58,867	2.39%	8.59
06.2200 Millwork	$105,513	4.28%	15.40
06.2300 Closet Interiors	$7,567	0.31%	1.10
06.4001 Wood Framing Materials	$103,611	4.20%	15.13
06.4002 Wood Framing Labor	$89,816	3.64%	13.11
06.4300 Wood Stairs And Railings	$18,564	0.75%	2.71
06.6600 Decking	$5,391	0.22%	0.79
07 Thermal and Moisture Protection			
07.2000 Insulation	$69,363	2.81%	10.13
07.2400 Exterior Insulation & Finish Systems (EIFS)	$6,628	0.27%	0.97
07.3000 Roofing	$19,853	0.81%	2.90
07.6600 Gutters & Leaders	$6,397	0.26%	0.93
07.9510 Vinyl Siding	$54,904	2.23%	8.02
08 Openings			
08.1400 Wood Doors & HW	$31,620	1.28%	4.62
08.1600 Residential Entry Doors & HW	$3,300	0.13%	0.48
08.5000 Windows	$51,043	2.07%	7.45
08.8500 Shower Enclosures	$13,056	0.53%	1.91
09 Finishes			
09.2300 Drywall & Carpentry	$107,321	4.35%	15.67
09.3013 Tile & Stone	$19,825	0.80%	2.89
09.6000 Flooring	$41,091	1.67%	6.00
09.9100 Painting	$58,588	2.38%	8.55
10 Specialties			
10.2800 Bath Accessories	$4,896	0.20%	0.71
11 Equipment			
11.3100 Appliances	$42,432	1.72%	6.19
12 Furnishing			
12.3600 Countertops	$29,249	1.19%	4.27
14 Conveying System			
14.2000 Elevators	$147,900	6.00%	21.59

Description	Total	Percent of Cost	Cost/Unit
21 Fire Suppression			
21.0000 Sprinkler	$51,000	2.07%	7.45
22 Plumbing			
22.0000 Plumbing	$106,692	4.33%	15.58
22.4000 Plumbing Fixtures	$34,540	1.40%	5.04
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$93,840	3.81%	13.70
26 Electrical			
26.0000 Electric	$210,276	8.53%	30.70
26.5000 Lighting Fixtures	$14,416	0.58%	2.10
27 Communications			
27.5123 Intercom System (Not Included)	$0	0.00%	0.00
28 Safety And Security			
28.4600 Fire Alarm	$30,600	1.24%	4.47
31 Sitework			
31.0000 Earthwork	$35,251	1.43%	5.15
31.0050 Site Demolition	$10,881	0.44%	1.59
31.1150 Sanitary Sewer	$24,480	0.99%	3.57
31.1200 Water & Fire Service	$57,120	2.32%	8.34
31.2500 Erosion And Sedimentation Controls	$6,120	0.25%	0.89
32 Exterior Improvements			
32.1500 Fencing	$7,819	0.32%	1.14
32.1600 Site Concrete	$7,572	0.31%	1.11
32.9300 Landscaping Restoration	$5,100	0.21%	0.74
Sub-Total (Direct Cost)	**$2,118,402**	**85.92%**	**309.26**
Overhead & Profit	$275,392	11.17%	40.20
Insurance	$71,814	2.91%	10.48
Total Estimate	**$2,465,608**	**100%**	**359.94**

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: 32 South Franklin St. Nyack NY

Scope of Work

Description
01.0050 General Requirements
Assistant Project Management
Blueprints
General Labor & Clean Up
General Supervision
Misc. Materials
Project Management
Supervision
Temporary Toilet
02.1000 Demolition
Remove Appliance
Remove Bilco Doors
Remove Chimney
Remove Doors & Frames
Remove Exterior Wall
Remove Fence
Remove Floor Tile
Remove Flooring
Remove GWB Ceilings
Remove GWB Walls (Plan View)
Remove Interior Partitions
Remove Millwork
Remove Plumbing Fixtures
Remove Roof In Its Entirety
Remove Siding
Remove Stairs
Remove Window
02.1500 Containers/Waste Removal
30-Yard Container
03.1000 Concrete
Concrete Pumps
F/O Quikrete 80lb Bag
F/O Sonotube Forms
Form & Pour Concrete Footings

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
Form & Pour Concrete Foundation Wall(s)
Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.
Form & Pour Exterior Concrete Stairs (Per Risers). F/I All Applicable Rebar Per Plans & Specifications.
Form & Pour Pitched Concrete Slab
I/O Sonotube Deck Footings (Per Hour)
Reinforced Concrete Elevator Shaft Wall
05.0100 Handrails & Egress Ladders
F/I 1-1/2" Pipe Handrail
F/I 1-1/2" Pipe Handrail (Rise/Run)
F/I 1-1/2" Pipe Rail with Spindles (Painted)
F/I Egress Ladder
06.2000 Finish Carpentry
F/I Base Molding
F/I Door Casing
F/I Window Casing
I/O Exterior Door Hardware
I/O Interior Door Hardware
I/O Interior Wood Door & F/I Trim
I/O Window Hardware & Screen(s)
06.2200 Millwork
F/I Bathroom Cabinets (Full-Height)
F/I Full-Height Cabinets
F/I Lower Cabinets
F/I Upper Cabinets
F/I Upper Cabinets
F/I Vanities
06.2300 Closet Interiors
F/I Closet Interiors (Hat Shelf & Rod)
06.4001 Wood Framing Materials
F/O 11-7/8" Pro 560 TJI (Per LF)
F/O 2x10 DF
F/O 2x12 DF
F/O 2x4 DF
F/O 2x4 PT
F/O 2x4 Studs
F/O 2x6 DF

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/O 2x6 PT
F/O 2x6 Studs
F/O 4x8x1/2" CDX Fir Plywood
F/O 4x8x3/4" TG Advantech Plywood
F/O 4x8x5/8" CDX Fir Plywood
F/O 6"x6"x12' Decorative Post
F/O FormSealR 5-1/2" x 50' Sill Seal
F/O Simpson ABU66Z Post Base
F/O Termite shield (6" x 25' Aluminum Roll)
06.4002 Wood Framing Labor
I/O Deck Post
I/O Deck Post
I/O Exterior Wall Framing & Sheathing @ 1st Floor
I/O Exterior Wall Framing & Sheathing @ 2nd Floor
I/O Floor Framing (Joists & Subfloor)
I/O Interior Framed Wall
I/O Residential Exterior Door(s)
I/O Roof Framing & Sheathing
I/O Window(s) (Standard Sizes)
06.4300 Wood Stairs And Railings
F/I Interior Stairs
06.6600 Decking
F/I Deck Stairs Open Riser (Per LF of Stair Tread)
F/I Front Entry Railing (White)
F/I Wood Decking
F/O 1/2" X 6" Lag Bolt
F/O 2x12 PT Deck Girder
F/O 2x8 PT (Deck Joist)
F/O 2x8 PT (Deck Outer Joist)
F/O 9" Grace Vycor Plus Deck Flashing
F/O Simpson Strong Tie LU28 2x8 Deck Joist Hangers
I/O Deck Framing
07.2000 Insulation
F/I 6" Mineral Wool Insulation
F/I Insulation & Air Seal @ Window(s)/Exterior Door(s)
F/I R-21 Closed-Cell

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I R-21 Fiberglass Batt
F/I R-21 Fiberglass Batt
F/I R-30 Fiberglass Batt @ Floors
F/I R-49 Spray-Foam
F/I Sound Deadening Insulation
F/I Tub Trap Insulation (Thermal)
07.2400 Exterior Insulation & Finish Systems (EIFS)
F/I Scratch & Brown Coats (Base Layers - Portland Cement Plaster)
07.3000 Roofing
F/I 3-Tab Asphalt Roof Shingles + Ice & Water Shield/Drip Edge & Ridge Cap
07.6600 Gutters & Leaders
5" Gutters
5" Leaders
07.9510 Vinyl Siding
F/I 12" Vinyl Soffits
F/I 5/4"x4"x18' Versatex Trim
F/I 5/4"x8"x18' Versatex Trim
F/I Tyvek Housewrap
F/I Tyvek Tape
F/I Vinyl Exterior Outside Corner Trim
F/I Vinyl Siding
08.1400 Wood Doors & HW
F/O Door Hardware ($150 Allowance Each)
F/O Door Hardware ($50 Allowance Each)
F/O Hollow Core Sliding Wood Doors (Pair) ($500 Allowance)
F/O Solid-Core Entry Wood Doors ($800/Ea Allowance)
F/O Solid-Core Wood Door ($300/Ea Allowance)
F/O Solid-Core Wood Doors (Pair) ($1,000 Allowance)
08.1600 Residential Entry Doors & HW
F/O Residential Entry Door Deadlock/Door Knob Combo [$150/Each Allowance Placeholder]
F/O Residential Wood Entry Door (36"x80"x9-1/6") ($1,500 Allowance Placeholder]
08.5000 Windows
F/O Windows
08.8500 Shower Enclosures
F/I Shower Enclosure
09.2300 Drywall & Carpentry

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I 5/8" GWB Ceilings (Level 4 Finish)
F/I 5/8" GWB Ceilings (Level 4 Finish)
F/I 5/8" GWB Walls (Level 4 Finish)
F/I 5/8" GWB Walls (Level 4 Finish)
I/O Bath Accessories
09.3013 Tile & Stone
F/I Floor Tile ($4/SF Material Allowance)
F/I Wall Tile ($4/SF Material Allowance)
F/I Waterproofing for Floor Tile
F/I Waterproofing for Wall Tile
09.6000 Flooring
F/I LVT (Luxury Vinyl Tile) Flooring @ Corridors
F/I LVT (Luxury Vinyl Tile) Flooring @ Corridors
F/I Luxury Vinyl Plank @ Units
09.9100 Painting
Paint Base Molding
Paint GWB Ceilings
Paint GWB Walls
Paint Window Casing
Paint/Stain Wood Doors & Casing
Prime & Paint Residential Fiberglass Entry Door
10.2800 Bath Accessories
Bath Accessories Budget
Bath Accessories Budget
11.3100 Appliances
F/O Dishwasher
F/O Dryer
F/O Dryer
F/O Range
F/O Refrigerator
F/O Vent Hood Insert 30"
F/O Washer
F/O Washer
12.3600 Countertops
Template, Fabricate & Install Solid Surface Countertop ($50/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops ($50/SF Material Allowance)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
14.2000 Elevators
Elevator 4 Stops
21.0000 Sprinkler
F/I NFPA 13 Sprinkler System
22.0000 Plumbing
Disconnect Boiler
Disconnect Existing Plumbing Fixtures
Disconnect Gas Meter and Pipework
Disconnect Hot Water Heater
Disconnect Water Meter and Pipework
F/I Gas Piping & Connection for HWH
F/I Gas Piping & Connection for Range
F/I Hose Bib
F/I Residential Hot Water Heater (HWH)
I/O Appliance
I/O Bath Lav (Sink) & Faucet
I/O Dishwasher
I/O Gas Meter
I/O Residential Toilet
I/O Sink & Faucet
I/O Standard Bathtub
22.4000 Plumbing Fixtures
F/O Kitchen Faucet
F/O Kitchen Sink
F/O LAV Sink
F/O Lav Faucet
F/O Residential Toilet
F/O Standard Bathtub
F/O Standard Shower Kit
23.0000 HVAC
Ancillary Split Unit
Duct Exhaust Fan
Split Unit + Condenser (Including Hyper Heat) (Add $3k for Each Additional Unit Up to 5)
26.0000 Electric
Electrical Disconnects Prior to Demo
F/I 100Amp Panel

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I 400/600 Amp Service
F/I Ceiling-Mounted Occupancy Sensor (OC)
F/I Dedicated Equipment Duplex 20amp
F/I Duplex Receptacle
F/I Electric Distribution Panel
F/I Exhaust Fan
F/I GFI Receptacle
F/I Residential Exhaust Fan
F/I Single-Pole Switch
F/O 2" Conduit for Internet Provider
F/O Terminations and Connections for 400 Amp Service
Home Run + Arc-Fault Breaker
I/O Lighting Fixture
I/O Underground Conduit for Internet Service
Underground Electrical Service Inspection
Wire 60 Amp AC Condenser Unit
Wire Elevator Equipment
26.5000 Lighting Fixtures
Lighting Fixture Budget
Lighting Fixture Budget
27.5123 Intercom System (Not Included)
Intercom System (Not Included)
28.4600 Fire Alarm
Fire Alarm
31.0000 Earthwork
Backfill Frost Walls
Backfill Slab & Compact
Excavate & Remove Fill From Site
Excavate Foundation (8'-9' Foundation Walls)
Excavate Foundation (Slab on Grade)
F/I Crushed Stone
Mobilization & GPS Layout (Sitework)
Trenching, Sand and Backfill Utility Trench for Underground Electric (2' Deep w/1' Sand)
31.0050 Site Demolition
Remove Exterior Stairs
Remove Foundation Wall

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
31.1150 Sanitary Sewer
F/I 6" Sanitary Lateral w/Tap, Compaction & Testing
31.1200 Water & Fire Service
F/I 2" Domestic Water line with RPZ and Meter Ser
F/I 4" Fire Service w/DDCDA and FDC
31.2500 Erosion And Sedimentation Controls
Erosion & Sedimentation Controls
32.1500 Fencing
F/I 6' Chain-Link Fencing
F/I 6' Chain-Link Single Gate
32.1600 Site Concrete
F/I 4" Sidewalk w/6"Aggregate Base
F/I Concrete Curb (6” Wide @ Top & 8-1/4” @ Bottom) (Includes Excavation)
Street/Sidewalk Restoration
32.9300 Landscaping Restoration
Landscaping

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Notes and Clarifications:

1. Pricing is to be used for budgetary purposes only.
2. All work to be performed during normal working hours. Overtime is not included.
3. Pricing is based on using open shop labor.
4. Permits and fees are not included.
5. Surveying fees are not included. Montana will coordinate stakeouts.
6. Temporary heating is not included. If required, will be billed on time and material basis.
7. Pricing for foundation walls is based on heights indicated on plans. Variations in grade are not accounted for.
8. Winter additive, ground thawing and/or blankets for concrete is not included.
9. Temporary heat is not included.
10. Pricing for excavation is based on bottom of footing depths indicated on drawings. If additional excavation is required to reach virgin soil additional charges for machine time, labor, concrete, waterproofing and backfilling may be incurred.
11. Rock removal is not included.
12. Tree removal is not included.
13. Snow/ice removal is not included.
14. Dewatering is not included.
15. Removal of unsuitable/contaminated soils is not included.
16. Landscaping is not included.
17. Window treatments are not included.
18. A 100amp panel is included for each unit.
19. If a sprinkler system is required there will be additional cost as we have not included a sprinkler system.
20. The new foundation does not include footing drains as there is no way to run them to daylight.
21. Catch basins or drainage for the roof leaders are not included.