Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Date: 12/04/2025

Elliot Berkowitz
Riverside Builders
137 5th Ave, 11th Floor
New York, NY 10010

Re: 1-3 S Broadway - Nyack, NY

Proposal

Montana Contracting Corp. will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$1,436,536**

Attachments:
Schedule of Values
Scope of Work
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting Corp.

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 12/04/2025

Estimate: 25056 1-3 S Broadway - Nyack, NY

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$84,010	5.85%	16.97
02 Existing Conditions			
02.1000 Demolition	$25,301	1.76%	5.11
02.1500 Containers/Waste Removal	$7,400	0.52%	1.49
03 Concrete			
03.3370 Concrete Topping	$17,070	1.19%	3.45
04 Masonry			
04.4300 Stone Masonry	$7,850	0.55%	1.59
05 Metal			
05.0100 Roof Access Ladder	$2,500	0.17%	0.51
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry (Five Star Millwork)	$34,413	2.40%	6.95
06.2200 Millwork (Vanities Only)	$11,368	0.79%	2.30
06.2300 Closet Interiors	$7,885	0.55%	1.59
06.4001 Wood Framing Materials	$26,170	1.82%	5.29
06.4002 Wood Framing Labor	$44,631	3.11%	9.02
06.4300 Wood Stairs And Railings	$20,294	1.41%	4.10
07 Thermal and Moisture Protection			
07.2000 Insulation	$33,228	2.31%	6.71
07.3000 Roofing (Allowance)	$11,500	0.80%	2.32
08 Openings			
08.1100 Entry Doors, Frames & HW (Allowance)	$10,000	0.70%	2.02
08.1400 Wood Doors & HW	$25,000	1.74%	5.05
08.5000 Windows	$67,113	4.67%	13.56
08.6200 Skylights	$5,097	0.35%	1.03
08.8500 Tub Enclosures (NIC)	$0	0.00%	0.00
09 Finishes			
09.2300 Drywall & Carpentry	$128,318	8.93%	25.92
09.3013 Tile & Stone	$44,850	3.12%	9.06
09.6400 Wood Flooring	$72,332	5.04%	14.61
09.9100 Painting	$96,197	6.70%	19.43
10 Specialties			
10.2800 Bath Accessories	$6,930	0.48%	1.40
11 Equipment			
11.3100 Appliances (Electric Dryer & Range)	$48,050	3.34%	9.71
12 Furnishing			
12.3600 Countertops	$33,011	2.30%	6.67
21 Fire Suppression			
21.0000 Sprinkler	$61,500	4.28%	12.42
22 Plumbing			

Description	Total	Percent of Cost	Cost/Unit
22.0000 Plumbing	$105,150	7.32%	21.24
22.4000 Plumbing Fixtures	$33,990	2.37%	6.87
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$108,947	7.58%	22.01
26 Electrical			
26.0000 Electric	$58,948	4.10%	11.91
26.5000 Lighting Fixtures	$12,000	0.84%	2.42
27 Communications			
27.1000 Intercom	$10,350	0.72%	2.09
28 Safety And Security			
28.4600 Fire Alarm (Allowance)	$6,500	0.45%	1.31
97 Notes/Exclusions/RFIs/Etc.			
97.0000 Notes/RFIs/Exclusions/Allowances:	$0	0.00%	0.00
Sub-Total (Direct Cost)	**$1,267,905**	**88.26%**	**256.14**
Overhead & Profit	$126,791	8.83%	25.61
Insurance	$41,841	2.91%	8.45
Total Estimate	**$1,436,536**	**100%**	**290.21**

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: 1-3 S Broadway - Nyack, NY

Scope of Work

Description
01.0050 General Requirements
Blueprints (Per Page)
Dumpster Permit
Equipment Rental
General Labor (1x 25% Allocation)
General Supervision (10% Allocation)
Misc. Materials/Protection/Consumables
Parking
Project Management (20% Allocation)
Supervision (50% Allocation)
Temporary Toilet (1x)
02.1000 Demolition
Remove Any Framing That Was Started In Order To Pour Levelrock Continuously
Remove Doors & Frames
Remove Existing Exterior Trim
Remove Existing Fire Escape Ladder
Remove Existing Stairs From 1st To 2nd Floor
Remove Floor Tile
Remove Flooring
Remove GWB Walls
Remove Interior Partitions
Remove Millwork & Kitchen Appliances
Remove Plumbing Fixtures
Remove Stairs From 2nd To 3rd Floor
Remove Window
Remove Window
Remove Wood Cladding
02.1500 Containers/Waste Removal
30-Yard Containers
03.3370 Concrete Topping
F/I Gypcrete Underlayment
04.4300 Stone Masonry
F/I Precast Sill
Infill Brick @ Window Opening

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
05.0100 Roof Access Ladder
F/I Roof Access Ladder
06.2000 Finish Carpentry (Five Star Millwork)
F/I Base Molding
F/I Door Casing
I/O Interior Door Hardware
I/O Interior Wood Door & F/I Trim
06.2200 Millwork (Vanities Only)
F/I Vanities [Duravit DE4355 Natural Walnut]
F/I Vanities [Duravit DE4355 Natural Walnut]
06.2300 Closet Interiors
F/I Closet Interiors (Hat Shelf & Rod)
06.4001 Wood Framing Materials
F/O 2x4 DF
F/O 2x4 PT
F/O 2x4 Studs
F/O 2x4 Studs & RC Channel
F/O 2x6 DF
F/O 2x6 PT
F/O 2x6 Studs
F/O 2x6 Studs & RC Channel
06.4002 Wood Framing Labor
Cut In Roof Access Hatch & Frame Opening
I/O Exterior & Vestibule Entry Doors 1.1/1.2
I/O Interior Framed Wall
I/O Interior Framed Wall
06.4300 Wood Stairs And Railings
F/I Wood Guardrail @ 1st to 2nd Floor Stair
F/I Wood Hand Railings
F/I Wood Railings 2nd to 3rd Floor
F/I Wood Stairs
F/I Wood Stairs
07.2000 Insulation
F/I Batt Insulation To Fit 2x4 On The Flat
F/I Sound Deadening Insulation
F/I 5" Sound Batt Insulation

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I R-21 Fiberglass Batt
F/I R-38C (Cathedral) Batt Insulation @ Roof
F/I Tub Trap Insulation (Thermal)
07.3000 Roofing (Allowance)
Flash Roof Curb @ New Access Hatch
Flashing for Penetrations/Pipes
Repair Or Replace Roof As Required
08.1100 Entry Doors, Frames & HW (Allowance)
F/O Door 1.1/1.2 Entry Door [3'6"x7'6"x1-3/4" Self Closing Wood Door & Glass Vision Panel]
08.1400 Wood Doors & HW (Five Star Millwork)
F/O 1-Hour Rated Unit/Basement Solid-Core Wood Door
F/O Door Hardware
F/O Door Hardware Set 1/5
F/O Door Hardware Set 2
F/O Door Hardware Set 2
F/O Door Hardware Set 3
F/O Door Hardware Set 4
F/O Door Hardware Set 4
F/O Louver W/D & Mechanical Room Wood Door
F/O Solid-Core Apartment Bathroom/Bedroom Wood Door
F/O Solid-Core Bedroom Closet Wood Door
F/O Solid-Core Bedroom Closet Wood Doors (Pair)
F/O Solid-Core Bedroom Closet Wood Doors (Pair)
F/O Solid-Core Kitchen Wood Door With Glass Vision Panel
F/O Solid-Core Wood Doors (Pair)
08.5000 Windows
F/O Anderson A-Series Double-Hung Window
08.6200 Skylights
F/I New Skylight To Replace Existing
08.8500 Tub Enclosures (NIC)
Shower Enclosure
09.2300 Drywall & Carpentry
F/I 1/2" GWB Walls (Level 4 Finish)
F/I Hung GWB Ceilings
F/I Wood Blocking for Bath Accessories
I/O Bath Accessories

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
09.3013 Tile & Stone
F/I Floor Tile
F/I Saddle/Threshold(s)
F/I Tile Backsplash @ Kitchens 2E/3E
F/I Tile Backsplash @ Kitchens 2N/3N
F/I Tile Backsplash @ Units 2W/3W
F/I Wall Tile
F/I Waterproofing for Floor Tile
F/I Waterproofing for Wall Tile
09.6400 Wood Flooring
F/I 3-1/4" Red Oak Wood Flooring
F/I 3-1/4" Red Oak Wood Flooring @ 1st to 2nd Floor Stair Landing
F/I USG SAM-N25 Sound Mat
09.9100 Painting
Finish Stairs & Railings
Paint Base Molding
Paint GWB Ceilings
Paint GWB Walls
Paint Interior Of Windows
Paint/Stain Wood Doors & Casing
Prep & Paint Brick Facade
Prep & Paint Existing Brick Facade
Prep & Paint Existing Cornice
Prep & Paint Existing Cornices
10.2800 Bath Accessories
F/O Bath Accessories Budget
F/O Recessed Medicine Cabinet [Kohler K-56551]
11.3100 Appliances (Electric Dryer & Range)
F/O Dishwasher
F/O Dryer
F/O Electric Range
F/O Over Range Microwave
F/O Refrigerator @ Apartment 2E/3E
F/O Refrigerator @ Apartment 2N/2W/3N/3W
F/O Stacking Kit For Washer/Dryer
F/O Washer

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
12.3600 Countertops
Template, Fabricate & Install Solid Surface Countertop @ Apartment 2N [Ceasarstone, Silestone Or Sim] ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop [Ceasarstone, Silestone Or Sim] @ Apartment 3E ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop [Ceasarstone, Silestone Or Sim] ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop [Ceasarstone, Silestone Or Sim] @ Apartment 2W ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop [Ceasarstone, Silestone Or Sim] @ Apartment 3N ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop [Ceasarstone, Silestone Or Sim] @ Apartment 3W ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops
21.0000 Sprinkler
F/I Sprinkler System
Sprinkler Backflow Submission Drawings & Application
Sprinkler Service Budget
22.0000 Plumbing
Disconnect Existing Plumbing Fixtures
F/I Residential Hot Water Heater (HWH)
I/O Appliance
I/O Appliance
I/O Bath Lav (Sink) & Faucet
I/O Dishwasher
I/O Over Range Microwave
I/O Residential Toilet
I/O Sink & Faucet
I/O Standard Bathtub
22.4000 Plumbing Fixtures
F/O Garbage Disposal [Insinkerator]
F/O Kitchen Faucet [Grohe 32 665 DC3 Super Steel Faucet]
F/O Kitchen Sink [Elkay EFRU22115T]
F/O LAV Sink [Duravit 2367800000 Single Hole White Gloss]
F/O Lav Faucet [Grohe 32216E Essence Brushed Nickel]
F/O Residential Toilet [Toto MS854114E, ECO ULTRA-MAX 1-Piece 01 Cotton
F/O Standard Bathtub [Duravit 700653 Right Drain White]
F/O Standard Shower Kit [Grohe 10249EN00 Brushed Nickel]
23.0000 HVAC
F/I Exhaust Fan
HVAC Per Walkthrough
26.0000 Electric

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
Dedicated Equipment Duplex 20amp
Duplex Receptacle
Electrical Disconnects Prior to Demo (Medium)
F/I 3-Way Switch
F/I GFI Receptacle
F/I Single-Pole Switch
Home Run + Arc-Fault Breaker
I/O Exit Sign
I/O Lighting Fixture
I/O Lighting Fixture
26.5000 Lighting Fixtures
Exit Sign
F/O L3 Above Vanity Lighting Fixture Budget
F/O L5 48" Strip Lighting Fixture Budget
F/O L6 30" Strip Lighting Fixture Budget
F/O L7 Undercabinet 12" Strip Lighting Fixture Budget
F/O L7 Undercabinet 24" Strip Lighting Fixture Budget
F/O L7 Undercabinet 48" Strip Lighting Fixture Budget
F/O L8 Ceiling-Mounted Lighting Fixture Budget
F/O Type L1 Recessed Lighting Fixture Budget
F/O Type L2 Recessed Lighting Fixture Budget
F/O Type L4 Ceiling-Mounted Lighting Fixture Budget
27.1000 Intercom
F/I Intercom System (Sound Only)
28.4600 Fire Alarm (Allowance)
Carbon Monoxide Detector
F/I Strobe Lights For Fire Alarm/Sprinkler System/Carbon Monoxide @ Front Facade
Smoke Detector

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Notes and Clarifications

1. Pricing is valid for forty five (45) business days.
2. Pricing is based on using open shop labor on straight time only.
3. Permit fees are not included.
4. Asbestos testing/abatement are not included.
5. Temporary heating/cooling is not included.
6. Special inspections are not included.
7. Snow removal is not included.
8. We have included a broom-swept clean and debris removal from work areas; professional cleaning, including window washing, floor scrubbing, and final turnover cleaning, is excluded and to be provided by others.
9. Temporary lighting and power for construction is included.
10. Entry doors 1.1 & 1.2 are included as an allowance pending details.
11. Any Framing that has been started will need to be removed. The UL rated floor system requires the Levelrock to be continuous under walls in order to keep the rating.
12. If Levelrock is eliminated we will likely have to add a second layer of sheet rock to the ceilings.
13. All work in the basement including the metal cellar access doors is not included.
14. The restaurant work will be treated as a second phase and is not included.
15. Fire alarm drawings are not present. We have included the additional devices shown. No programming or proprietary equipment is included.
16. Modifications needed for new storefront of flooring or concrete and storefront replacement are not included.
17. Electrical panels and service are assumed existing. If new panels are needed there will be additional costs.
18. A new ladder where the exterior fire escape ladder is being removed is not included.
19. Plumbing is priced assuming all apartments being fed from 1 water meter.
20. We have included a 40 gallon electric hot water heater with a backup drain pan with automatic shut off for each apartment.
21. It is assumed the dryer and range will be electric.
22. For HVAC we have included the floor mounted split system as requested but it is not recommended by our contractor.
23. Kitchen millwork is not included. Millwork price is vanities only.