Montana Contracting
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 04/23/2025

Nelson Benavides
Nelson Benavides Architect P.C.

Re: 113 Grand St. - Farkas Residence

Proposal

Montana Contracting will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project based on plans dated for the sum of: **$491,915**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 04/23/2025

Estimate: 25011 113 Grand St. - Farkas Residence

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$70,665	14.37%	
02 Existing Conditions			
02.1000 Demolition	$25,025	5.09%	
02.1500 Containers/Waste Removal	$3,053	0.62%	
03 Concrete			
03.1000 Concrete	$392	0.08%	
03.1500 Concrete Cutting	$2,474	0.50%	
03.3370 Concrete Topping	$5,630	1.14%	
04 Masonry			
04.1000 Masonry	$1,485	0.30%	
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$4,318	0.88%	
06.2200 Millwork	$26,239	5.33%	
06.4300 Wood Stairs And Railings	$1,405	0.29%	
07 Thermal and Moisture Protection			
07.3000 Roofing	$3,410	0.69%	
08 Openings			
08.1400 Wood Doors & HW	$10,945	2.22%	
08.8200 Arch. Metal & Glass	$3,696	0.75%	
08.8500 Shower Enclosures	$2,640	0.54%	
09 Finishes			
09.2300 Drywall & Carpentry	$53,490	10.87%	
09.3013 Tile & Stone ($12/SF Material Allowance)	$35,489	7.21%	
09.6000 Flooring	$2,860	0.58%	
09.6700 Fluid-Applied Flooring	$1,013	0.21%	
09.9100 Painting	$11,440	2.33%	
10 Specialties			
10.2800 Bath Accessories (Budget)	$2,200	0.45%	
11 Equipment			
11.3100 Appliances	$1,650	0.34%	
12 Furnishing			
12.3600 Countertops	$5,514	1.12%	
13 Special Construction			
13.2416 Saunas	$17,269	3.51%	
22 Plumbing			
22.0000 Plumbing	$21,120	4.29%	
22.4000 Plumbing Fixtures (Budgetary)	$6,600	1.34%	
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$46,475	9.45%	
26 Electrical			

Description	Total	Percent of Cost	Cost/Unit
26.0000 Electric	$33,308	6.77%	
26.5000 Lighting Fixtures (Budgetary)	$9,649	1.96%	
27 Communications			
27.1000 Tel/Data (Included In Electric)	$0	0.00%	
27.1020 Audio Visual (Included In Electric)	$0	0.00%	
28 Safety And Security			
28.4600 Fire Alarm (Local Devices Included In Electric)	$0	0.00%	
Sub-Total (Direct Cost)	**$409,454**	**83.24%**	
Overhead	$32,756	6.66%	
Profit	$35,377	7.19%	
Insurance	$14,328	2.91%	
Total Estimate	**$491,915**	**100%**	

Montana Contracting
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Notes and Clarifications:

1. Price is good for 30 days after proposal date and is subject to change prior to the date due to tariffs.
2. All work to be performed during standard working hours. Overtime is excluded.
3. Pricing is based on open shop labor.
4. Permits, municipal fees, and utility connection fees are excluded.
5. Temporary heating is excluded. If required, will be billed time and material (T&M).
6. Low voltage systems (audio/visual, security, networking) wiring and equipment is excluded. We have included backboxes and conduit with drag lines between points.
7. Window treatments (blinds, shades, curtains) are excluded.
8. Electric panel is based on installation of one (1) standard 100 AMP panel being fed by an existing panel.
9. Professional post-construction cleaning is included.
10. There is a refrigerator mentioned on the electrical panel schedule but it is not called out in the drawings. It is excluded pending clarification.
11. Gyp. Crete level topping is based on 3000 P.S.I. material.
12. The inset matt is not included.
13. AV equipment is not included but conduit and back boxes with pull strings is included.
14. The rock climbing wall is install only.
15. Bathroom exhaust duct is priced assuming the roof is directly over the 1st floor bathroom.
16. Breaker for main panel to feed sub panel is not included. The existing panel spec is needed to price this breaker.
17. Location of existing panel is unknown. We have included a maximum of 50 feet of feeders. If the panel is beyond this distance there will be additional costs.
18. One dual port tel/data location complete with cat6 cabling is included.
19. Three AV locations complete with RG-6 cabling are included.
20. On the drawing it says cover deck. Nothing is included except temporary protection for HVAC unit replacement.
21. Tile trim @ stairs is not included pending verification of spec.