Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Date: 09/19/2025

Chris & Deirdre Hoerenz

Re: 257 River Road

Budget Proposal

Montana Home Builders hereby proposes all materials, labor and supervision in accordance with drawings dated for the sum of **$2,164,293**

Attachments:
Schedule of Values

Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto

Montana Home Builders

Accepted By: _____

Date of Acceptance: _____

MONTANA
HOME BUILDERS

Status: Active Estimates
Contact:
Date: 09/19/2025

Estimate: 25041 257 River Road

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$200,590	9.27%	61.34
02 Existing Conditions			
02.1000 Demolition	$29,787	1.38%	9.11
02.1500 Containers/Waste Removal	$5,550	0.26%	1.70
03 Concrete			
03.1000 Concrete	$134,097	6.20%	41.01
04 Masonry			
04.1000 Masonry	$1,622	0.07%	0.50
04.4300 Stone Masonry	$25,907	1.20%	7.92
05 Metal			
05.0050 Structural Steel	$28,758	1.33%	8.79
05.0100 Pipe/Cable Railing	$20,951	0.97%	6.41
05.7610 Lintels	$775	0.04%	0.24
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$34,959	1.62%	10.69
06.2200 Millwork	$90,625	4.19%	27.71
06.2300 Closet Interiors	$13,874	0.64%	4.24
06.4001 Wood Framing Materials	$98,781	4.56%	30.21
06.4002 Wood Framing Labor	$85,450	3.95%	26.13
06.4300 Wood Stairs And Railings	$10,500	0.49%	3.21
06.6600 Decking	$51,134	2.36%	15.64
07 Thermal and Moisture Protection			
07.1000 Waterproofing	$2,833	0.13%	0.87
07.2000 Insulation	$41,715	1.93%	12.76
07.2400 Exterior Insulation & Finish Systems (EIFS)	$11,884	0.55%	3.63
07.3000 Roofing	$79,686	3.68%	24.37
07.6600 Gutters & Leaders	$4,909	0.23%	1.50
07.9510 Siding	$86,881	4.01%	26.57
08 Openings			
08.1400 Wood Doors & HW	$32,595	1.51%	9.97
08.1600 Residential Entry Doors & HW	$11,050	0.51%	3.38
08.3700 Garage Doors	$8,616	0.40%	2.63
08.5000 Windows	$82,890	3.83%	25.35
08.8500 Shower Enclosures	$4,500	0.21%	1.38
09 Finishes			
09.2300 Drywall & Carpentry	$32,600	1.51%	9.97
09.3013 Tile & Stone	$31,250	1.44%	9.56
09.6400 Wood Flooring	$40,343	1.86%	12.34
09.9100 Painting	$55,722	2.57%	17.04
10 Specialties			

Description	Total	Percent of Cost	Cost/Unit
10.2800 Bath Accessories	$3,700	0.17%	1.13
10.3100 Fireplaces	$39,800	1.84%	12.17
11 Equipment			
11.3100 Appliances	$13,900	0.64%	4.25
12 Furnishing			
12.3600 Countertops	$18,455	0.85%	5.64
22 Plumbing			
22.0000 Plumbing	$37,500	1.73%	11.47
22.4000 Plumbing Fixtures (Allowance)	$14,520	0.67%	4.44
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$117,218	5.42%	35.85
26 Electrical			
26.0000 Electric	$60,000	2.77%	18.35
26.5000 Lighting Fixtures (Allowance Except For 58 Recessed Lights Included In Electric)	$5,280	0.24%	1.61
28 Safety And Security			
28.4600 Fire Alarm	$1,500	0.07%	0.46
31 Sitework			
31.0000 Earthwork	$35,916	1.66%	10.98
31.1100 Drainage & Stormwater	$37,809	1.75%	11.56
31.1150 Sanitary Sewer	$5,700	0.26%	1.74
31.1200 Water & Fire Service	$3,200	0.15%	0.98
31.2100 Off-Gassing Mitigation	$5,000	0.23%	1.53
31.2200 Grading	$808	0.04%	0.25
31.2500 Erosion And Sedimentation Controls	$4,750	0.22%	1.45
32 Exterior Improvements			
32.1100 Asphalt Driveway	$14,048	0.65%	4.30
32.1400 Hardscaping	$17,438	0.81%	5.33
32.1500 Fencing	$1,810	0.08%	0.55
32.3200 Retaining Wall	$34,000	1.57%	10.40
32.9300 Landscaping	$2,908	0.13%	0.89
Sub-Total (Direct Cost)	**$1,836,092**	**84.84%**	**561.50**
Overhead & Profit	$275,414	12.73%	84.22
Insurance	$52,788	2.44%	16.14
Total Estimate	**$2,164,293**	**100%**	**661.86**

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Estimate Description: 257 River Road

Scope of Work

Description
01.0050 General Requirements
Assistant Project Management
Blueprints
General Labor & Clean Up
General Supervision
Misc. Materials
Project Management
Supervision
Temporary Toilet
02.1000 Demolition
Demo Shed
Demo Two Story House & Foundation
Disconnect Sewer & Water Service
Remove Asphalt Driveway
Remove Concrete Driveway
Remove Slate Patio
Remove Stone & Masonry Wall
02.1500 Containers/Waste Removal
30-Yard Container
03.1000 Concrete
Concrete Pumps
F/I Parge Cove @ Footings
F/O Quikrete 80lb Bag
F/O Sonotube Forms
Form & Pour Concrete Footings
Form & Pour Concrete Foundation Wall(s)
Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.
Form & Pour Spread Footings
I/O Sonotube Deck Footings (Per Hour)
04.1000 Masonry
F/I CMU Block [8"x8"x16"]
04.4300 Stone Masonry
F/I 2" Thick Bluestone Sills
F/I 5"-6" Stone Veneer

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Stone Hearth @ Screened In Porch
05.0050 Structural Steel
F/I Flitch Plate
F/I Steel Beams
F/I Steel Beams Vertical
05.0100 Pipe/Cable Railing
F/I 1-1/2" Pipe Handrail (Rise/Run)
F/I Stainless Steel Cable Railing [View Rail Black Metal Posts & Handrail)
05.7610 Lintels
F/I Steel Angle Above Windows To Support Stone Veneer
06.2000 Finish Carpentry
F/I Base Molding
F/I Door Casing
F/I Window Casing
F/I Wood Wainscoting @ Powder Room Walls
I/O Exterior Door Hardware
I/O Interior Door Hardware
I/O Interior Wood Door & F/I Trim
I/O Pocket Door
I/O Window Hardware & Screen(s)
06.2200 Millwork
F/I Bath 1 Vanities
F/I Bathroom Cabinets @ Master Bath
F/I Bench @ Basement Mudroom
F/I Built-In Millwork @ Entry Hall
F/I Cubbies @ Basement Mudroom
F/I Full-Height Linen Cabinet @ Laundry Room
F/I Lower Cabinets @ Plant Room
F/I Master Bath Vanities
F/I Powder Room Vanities
F/O Kitchen Cabinet Hardware ($1,200.00 Allowance)
F/O Kitchen Island
F/O Lower Cabinets @ Kitchen
F/O Upper Cabinets @ Kitchen
F/O Upper Cabinets Over Refrigerator
F/O Wood Hood Above Range With Insert

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
I/O Kitchen Cabinets
06.2300 Closet Interiors
F/I Closet Interiors (Hat Shelf & Rod)
F/I Closet Interiors (Master WIC)
F/I Closet Interiors (Pantry)
F/I Closet Interiors (Storage WIC)
06.4001 Wood Framing Materials
F/O 1-3/4" X 18" LVL 19.E
F/O 1-3/4" x 11-7/8" LVL
F/O 1-3/4" x 16" 2.0E LVL
F/O 1-3/4" x 7-1/4" LVL 19.E
F/O 1-3/4" x 9-1/2" LVL
F/O 11-7/8" Pro 560 TJI (Per LF)
F/O 11-7/8" TJI 360 I-Joist (Per LF)
F/O 2x10 DF
F/O 2x12 DF
F/O 2x12 DF
F/O 2x4 DF
F/O 2x4 PT
F/O 2x4 Studs
F/O 2x6 DF
F/O 2x6 PT
F/O 2x6 Studs
F/O 2x8 DF
F/O 2x8 DF
F/O 2x8 PT
F/O 2x8 PT (Rafter Tails)
F/O 2x8 Studs
F/O 3-1/2" x 5-1/4" x 10' PSL Parallam 1.8E
F/O 4x8x1/2" CDX Fir Plywood X 2
F/O 4x8x3/4" TG Advantech Plywood
F/O 4x8x5/8" R3.6 Zip Sheathing
F/O 5-1/2"x11-1/4" LVL
F/O 5-1/4" x 11-7/8" PSL (Parallam)
F/O 6"x6"x12' PT Post
F/O FormSealR 5-1/2" x 50' Sill Seal

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/O Pergola Framing
F/O Simpson ABU66Z Post Base
F/O Termite shield (6" x 25' Aluminum Roll)
06.4002 Wood Framing Labor
I/O Deck Post
I/O Exterior Wall Framing & Sheathing @ 1st Floor
I/O Exterior Wall Framing & Sheathing @ 2nd Floor
I/O Floor Framing (Joists & Subfloor)
I/O Interior Framed Wall
I/O Pergola Framing
I/O Residential Exterior Door(s)
I/O Roof Framing & Sheathing
I/O Window(s) (Standard Sizes)
06.4300 Wood Stairs And Railings
F/I White Oak Railings
F/I White Oak Stairs w/Poplar Strings & Risers (Per Riser)
06.6600 Decking
F/I IPE Deck Stairs
F/I IPE Decking [5/4" X 6"]
F/O 1/2" X 6" Lag Bolt
F/O 2x10 PT (Deck Joist)
F/O 2x10 PT (Deck Outer Joist)
F/O 2x12 PT Deck Girder
F/O 9" Grace Vycor Plus Deck Flashing
F/O Simpson Strong Tie LU28 2x8 Deck Joist Hangers
I/O Deck Framing
07.1000 Waterproofing
F/I Foundation Waterproofing [Bituminous 60 Mil Liquid Applied Damproofing With Drainage Board]
07.2000 Insulation
F/I Sound Deadening Insulation
F/I Insulation & Air Seal @ Window(s)/Exterior Door(s)
F/I R-21 Closed-Cell
F/I R-21 Closed-Cell
F/I R-21 Fiberglass Batt
F/I R-30 Fiberglass Batt
F/I R-49 Spray-Foam

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Tub Trap Insulation (Thermal)
07.2400 Exterior Insulation & Finish Systems (EIFS)
F/I Control Joints, Trim & Expansion Joints
F/I Finish Coat (Acrylic or Cement-Based Stucco Finish)
F/I Metal Lath & Fasteners
F/I Scaffolding & Access Equipment
F/I Scratch & Brown Coats (Base Layers - Portland Cement Plaster)
F/I Weather-Resistant Barrier (WRB), Flashing & Sealants
07.3000 Roofing
F/I Cricket @ Backside of Chimney
F/I EPDM Roof
F/I EPDM Roof at Parapet Walls
F/I Flashing @ Chimney
F/I Scupper @ Flat Roof
F/I Snow Guards [Continuous Double Pipe Rocky Mountain Snow Guards Inc. Drift 2 Or Equal
F/I Standing Seam Sheet Metal Roofing
07.6600 Gutters & Leaders
5" Leaders
6" Half Round Aluminum Gutters
07.9510 Siding
F/I 1"x Azek Trim @ Garage Door
F/I 1"x14"x12' Azek Trim
F/I 1"x18"x12' Azek Trim
F/I 1"x3"x12' Azek Trim
F/I 1"x8"x12' Azek Trim
F/I 12x12 Box Arouns Columns
F/I 12x12 Plywood & Azek Box @ Column
F/I 1x6 Boral [Truexterior, Painted]
F/I 2"x2"x12' Azek Trim
F/I 4'x8'x1/2" Azek Panel
F/I 5/4"x10"x12' Azek Trim
F/I 5/4"x12"x12' Azek Trim
F/I 5/4"x4"x12' Azek Trim
F/I 5/4"x6"x12' Azek Trim
F/I 5/4x3 Boral [Truexterior, Painted]
F/I Azek 1x6 V Groove Soffit [Azek, Color TBD]

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Custom Rafters 2"x8" Actual Douglas Fir W Decorative End [To Be Painted]
F/I Decorative Rafter
F/I Insect Screen Walls @ Screened In Porch
F/I James Hardie Board & Batten (16" O.C.)
F/I Outrigger Beam [5-1/2"x9" Douglas Fir With Decorative End, Painted]
F/I Siding #4 1x10 Shiplap Siding [TruExterior, Painted]
F/I Tyvek Housewrap
F/I Tyvek Tape
08.1400 Wood Doors & HW
F/O "Shutter" Hardware ($150 Allowance Each)
F/O "Shutters" @ Loft (Pair)
F/O Door Hardware ($150 Allowance Each)
F/O Solid-Core Wood Door
F/O Solid-Core Wood Door
F/O Solid-Core Wood Doors (Pair)
Pocket Door with Kit (Builder Grade)
08.1600 Residential Entry Doors & HW
F/O Front Residential Wood Entry Door (36"x80"x9-1/6") ($3,500 Allowance Placeholder]
F/O Residential Entry Door Deadlock/Door Knob Combo [$150/Each Allowance Placeholder]
F/O Residential Entry Door Deadlock/Door Knob Combo [$50/Each Allowance Placeholder]
F/O Residential Wood Entry Door (36"x80"x9-1/6") ($2,500 Allowance Placeholder]
F/O Screen Door
F/O Screen Door Hardware
08.3700 Garage Doors
Garage Door Budget
08.5000 Windows
F/O Exterior French Door Pair
F/O Marvin Ultimate Series Windows
08.8500 Shower Enclosures
F/I Shower Enclosure
09.2300 Drywall & Carpentry
F/I 5/8" GWB Ceilings (Level 4 Finish)
F/I 5/8" GWB Walls (Level 4 Finish)
F/I 5/8" Type X GWB Ceilings (Level 4 Finish)
I/O Bath Accessories
09.3013 Tile & Stone

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Floor Tile ($27.50/SF Material Allowance)
F/I Floor Tile ($7.50/SF Material Allowance)
F/I Floor Tile ($7/SF Material Allowance)
F/I Hearth @ Living Room
F/I Mud Job at Shower
F/I Plant Room Floor Tile [Vinales Salmon, Freight From Mexico Is Half The Cost]
F/I Saddle/Threshold(s)
F/I Wall Tile ($11/SF Material Allowance)
F/I Wall Tile ($7.50/SF Material Allowance)
F/I Wall Tile ($7/SF Material Allowance)
F/I Wall Tile ($7/SF Material Allowance)
F/I Wall Tile ($9.50/SF Material Allowance)
F/I Waterproofing for Floor Tile
F/I Waterproofing for Wall Tile
09.6400 Wood Flooring
F/I Engineered Wood Flooring ($13/SF Material Allowance)
09.9100 Painting
Paint Base Molding
Paint Door Casing (Per LF)
Paint GWB Ceilings
Paint GWB Walls
Paint Risers & Stringers
Paint Siding & Trim
Paint Window Casing
Paint/Stain Treads & Risers To Match Wood Flooring
Paint/Stain Wood Doors & Casing
Prime & Paint Residential Fiberglass Entry Door
10.2800 Bath Accessories
F/O Bath Accessories Budget
F/O Bath Accessories Budget
F/O Bath Accessories Budget
10.3100 Fireplaces
F/I Chimney Cap
F/I Chimney Pipe Ventilation
F/I Wood Burning Masonry Fireplace
F/I Wood Burning Stove

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
11.3100 Appliances
F/O Dishwasher
F/O Dryer
F/O Range
F/O Refrigerator
F/O Vent Hood Insert 30"
F/O Washer
12.3600 Countertops
Template, Fabricate & Install Shower Curb ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Backsplash ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops @ Bath 1 ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops @ Master Bath ($65/SF Material Allowance)
22.0000 Plumbing
F/I Floor Drain 3"
F/I Gas Piping & Connection for Range
F/I Hose Bib
F/I Refrigerator Waterline
F/I Sump Pump With Pit And Cover
I/O Appliance
I/O Bath Lav (Sink) & Faucet
I/O Dishwasher
I/O Residential Toilet
I/O Sink & Faucet
I/O Standard Bathtub
I/O Standard Shower
22.4000 Plumbing Fixtures (Allowance)
F/O Kitchen Faucet
F/O Kitchen Sink
F/O LAV Sink
F/O Lav Faucet
F/O Plant Room Farm Sink
F/O Plant Room Faucet
F/O Residential Toilet
F/O Standard Bathtub

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/O Standard Shower Kit
23.0000 HVAC
Duct Exhaust Fan
Duct Kitchen Exhaust Fan
HVAC Budget
26.0000 Electric
3-Way Switch
3-Way Switch
Dedicated Equipment Duplex 20amp
Duplex Receptacle
F/I 200Amp Panel
F/I EV Charging Station
F/I Junction Box for Ceiling Fan
F/I Single-Pole Switch
GFI Receptacle
Home Run + Arc-Fault Breaker
I/O Ceiling Fan
I/O Lighting Fixture
I/O Lighting Fixture
I/O Lighting Fixture (Residential)
Residential Exhaust Fan
Weatherproof GFI Receptacle
Wire 60 Amp AC Condenser Unit
Wire Sump Pump
26.5000 Lighting Fixtures (Allowance Except For 58 Recessed Lights Included In Electric)
Basic Recessed Lighting Fixture (Included In Electric)
Exterior Wall Sconce Lighting Fixture Budget
Kitchen Wall Sconce Lighting Fixture Budget [According To Renderings]
Pendants Over Island Lighting Fixture Budget
28.4600 Fire Alarm
Smoke Detector
31.0000 Earthwork
2" Rigid Insulation Below Grade
Backfill Frost Walls
Backfill Slab & Compact
Excavate Foundation (Frost Walls)

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
Excavate Foundation (Slab on Grade)
F/I Crushed Stone
Strip Topsoil and Stockpile on Site for Later Use
31.1100 Drainage & Stormwater
F/I 12" HDPE Piping
F/I 4" Footing Drain
F/I 4" HDPE Pipe
F/I Catch Basin @ Patio Stairs
F/I Cleanouts
F/I Cultec Field [R-150XLHD, 8 Chambers]
F/I Double Footing Drains @ Garage
F/I New Rip Rap
F/I Sedimentation Chamber For Pretreatment
31.1150 Sanitary Sewer
Connect to Existing Sewer Main
31.1200 Water & Fire Service
Connect To Existing Water Main
31.2100 Off-Gassing Mitigation
Radon Mitigation
31.2200 Grading
Rough Grading with Stockpiled Soil
31.2500 Erosion And Sedimentation Controls
F/I Construction Entrance
F/I Silt Fence
32.1100 Asphalt Driveway
Asphalt Driveway & Prep
Driveway Prep
32.1400 Hardscaping
2" Bluestone Treads (Perimeter Application)
Bluestone Pavers (Including Excavation & Gravel)
32.1500 Fencing
Re-Install Salvaged Fence
Remove Existing Fence And Slavage For Reinstall
32.3200 Retaining Wall
Excavation, Geo-Grid & Backfill
F/I Retaining Wall @ Patio [Diamond Straight Face Or Approved Equal]

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
32.9300 Landscaping
Seeding & Haying

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Notes and Clarifications:

1. Pricing is valid for thirty (30) calendar days.
2. All work to be performed during normal working hours. Overtime is not included.
3. Pricing is based on using open shop labor.
4. Permits and fees are not included.
5. Surveying fees are not included. Montana will coordinate stakeouts.
6. Temporary heating is not included. If required, will be billed on time and material basis.
7. Pricing for foundation walls is based on heights indicated on plans. Variations in grade are not accounted for.
8. Winter additive, ground thawing and/or blankets for concrete is not included.
9. Temporary heat is not included.
10. Pricing for excavation is based on bottom of footing depths indicated on drawings. If additional excavation is required to reach virgin soil additional charges for machine time, labor, concrete, waterproofing and backfilling may be incurred.
11. Rock removal is not included.
12. Snow/ice removal is not included.
13. Dewatering is not included.
14. Removal of unsuitable soils is not included.
15. Landscaping is not included..
16. Window treatments are not included.
17. It is assumed that the existing water , gas, and sewer service will be utilized for the new house.
18. Any materials or equipment including plumbing fixtures, lighting fixtures, millwork, tile, countertops, bath accessories, fireplaces, appliances, wood flooring, etc. are included as allowances.
19. The fish tank and associated equipment is not included.
20. Wainscot wall tile is included in the master bath and full height tile is included on the sink wall in the powder room from the counter to the ceiling.
21. Wood Wainscoting is included on the remaining walls of the powder room.
22. Assumed electric service is over head.
23. Footings & retaining walls at the patio are not included. We have included the block walls as shown on the civil drawings.
24. Block retaining wall install assumes that the existing material is suitable for compacted back fill. No import of import of fill is included.
25. Asbestos abatement is not included.
26. 5"-6" stone veneer allowance is $25/SF