Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 01/14/2026

Dr James & Dr Peter Sayegh

301 N Main St
New City, NY 10956

Re: 301 N Main St - Addition

Budget Proposal

Montana Contracting Corp. hereby proposes all materials, labor and supervision in accordance with drawings dated for the sum of **$1,679,447**

Attachments:
Schedule of Values

Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto

Montana Contracting Corp.

Accepted By: _____

Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 01/14/2026

Estimate: 25069 301 N Main St - Addition

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$171,219	10.19%	67.94
02 Existing Conditions			
02.1000 Demolition	$19,285	1.15%	7.65
02.1500 Containers/Waste Removal	$7,400	0.44%	2.94
03 Concrete			
03.1000 Concrete	$95,921	5.71%	38.06
04 Masonry			
04.5710 Brick	$24,589	1.46%	9.76
05 Metal			
05.0050 Structural Steel	$282,688	16.83%	112.18
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$5,348	0.32%	2.12
06.2200 Millwork	$31,050	1.85%	12.32
07 Thermal and Moisture Protection			
07.2400 Exterior Insulation & Finish Systems (EIFS)	$64,137	3.82%	25.45
07.3000 Roofing	$76,617	4.56%	30.40
07.6600 Downspouts	$960	0.06%	0.38
07.8000 Fireproofing	$7,620	0.45%	3.02
07.9510 Soffits	$5,776	0.34%	2.29
08 Openings			
08.1100 Wood Doors, HM Frames & HW	$23,650	1.41%	9.38
08.8200 Arch. Metal & Glass	$66,169	3.94%	26.26
09 Finishes			
09.2300 Drywall & Carpentry	$109,408	6.51%	43.42
09.2500 Acoustical Ceilings	$12,573	0.75%	4.99
09.6000 Flooring	$12,700	0.76%	5.04
09.9100 Painting	$14,440	0.86%	5.73
10 Specialties			
10.4400 Fire Protection Specialties	$1,050	0.06%	0.42
21 Fire Suppression			
21.0000 Sprinkler	$48,894	2.91%	19.40
22 Plumbing			
22.0000 Plumbing	$76,500	4.56%	30.36
22.4000 Plumbing Fixtures	$9,900	0.59%	3.93
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$93,938	5.59%	37.28
26 Electrical			
26.0000 Electric	$67,875	4.04%	26.93
26.5000 Lighting Fixtures	$13,250	0.79%	5.26
27 Communications			

Description	Total	Percent of Cost	Cost/Unit
27.1000 Tel/Data (Back Boxes & Conduit Into Ceiling Only)	$2,250	0.13%	0.89
28 Safety And Security			
28.4600 Fire Alarm	$26,000	1.55%	10.32
31 Sitework			
31.0000 Earthwork	$33,130	1.97%	13.15
31.1100 Storm Water Management	$22,971	1.37%	9.12
31.2500 Erosion And Sedimentation Controls	$3,000	0.18%	1.19
32 Exterior Improvements			
32.1200 Paving	$4,767	0.28%	1.89
32.1400 Hardscaping	$2,604	0.16%	1.03
32.1600 Site Concrete	$2,631	0.16%	1.04
32.1723 Pavement Markings	$1,523	0.09%	0.60
32.9300 Seeding	$1,116	0.07%	0.44
Sub-Total (Direct Cost)	**$1,442,948**	**85.92%**	**572.60**
Overhead & Profit	$187,583	11.17%	74.44
Insurance	$48,916	2.91%	19.41
Total Estimate	**$1,679,447**	**100%**	**666.45**

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: 301 N Main St - Addition

Scope of Work

Description
01.0050 General Requirements
Assistant Project Management
Blueprints
General Labor
General Supervision
Misc. Materials
Project Management
Supervision
Temporary Toilet
02.1000 Demolition
Demo Existing Treatment Room And Create Opening To New Corridor On 2 Floors
Remove Block Wall
Remove Existing Parapet
02.1500 Containers/Waste Removal
30-Yard Container
03.1000 Concrete
Concrete Pumps
F/I 3-1/2" Lightweight Concrete Fill Over Steel Decking
F/I Concrete Fill Over Steel Decking (Installed by Steel Sub)
Form & Pour 2'x1' Concrete Footings @ Stairs
Form & Pour 2'x2'x9' Concrete Columns
Form & Pour 3'x 1'4" Concrete Footings
Form & Pour 4'x4'x18" Spread Footings
Form & Pour 6" Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.
Form & Pour Concrete 12" Foundation Wall(s)
Form & Pour Concrete 8" Foundation Wall(s) @ Stairs
Form & Pour Exterior Concrete Stairs (Per Risers). F/I All Applicable Rebar Per Plans & Specifications.
04.5710 Brick
F/I Full-Brick Veneer To Match Existing
05.0050 Structural Steel
F/I Metal Decking
F/I Open Web Bar Joists (K-Series)
Structural Steel Beams, Plates, Engineering, etc.
06.2000 Finish Carpentry

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Base Molding
06.2200 Millwork
F/I Lower Exam Cabinets w/Integrated Countertops (Plastic Laminate)
F/I Upper Exam Cabinets (Plastic Laminate)
07.2400 Exterior Insulation & Finish Systems (EIFS)
F/I 2" Rigid Insulation [R-10 Continuous EPS]
F/I Base Coat (Polymer-Modified Cement Adhesive, Fiberglass Reinforcement Mesh)
F/I Control Joints, Trim & Expansion Joints
F/I Finish Coat (Acrylic or Synthetic Textured Finish)
F/I Scaffolding & Access Equipment
F/I Weather-Resistant Barrier (WRB), Flashing & Sealants
07.3000 Roofing
F/I .050 Aluminum Coping
F/I EPDM Roof With Insulation & Coverboard
F/I EPDM Roof at Parapet Walls
F/I Standing Seam Sheet Metal Roofing To Match Existing
Tie-In to Existing Roof
07.6600 Downspouts
F/I 5" Downspouts
07.8000 Fireproofing
F/I Spray-Applied Fireproofing (SFRM) @ Underside of Bar Joists/Metal Decking
07.9510 Soffits
F/I 24" Aluminum Soffits
08.1100 Wood Doors, HM Frames & HW
F/O Door Hardware
F/O HM Frame (Single)
F/O Solid-Core Wood Door
08.8200 Arch. Metal & Glass
Exterior Glass Storefront System To Match Existing
Remove Storefront Windows & Salvage For Re-use
09.2300 Drywall & Carpentry
Close Up Windows @ Basement Level
F/I 3-5/8" Metal Stud Framing
F/I 5/8" Densglass Sheathing
F/I 5/8" Densglass Sheathing Both Sides
F/I 5/8" GWB Walls (Level 4 Finish)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I 6" Metal Stud Framing
F/I 6" Metal Stud Framing
F/I 6" Mineral Wool Insulation
F/I Acoustical Sealant
F/I Blanket Insulation
F/I Weather-Resistive Barrier (WRB)
F/I Wood Blocking
I/O Fire Extinguisher Cabinet
I/O Interior HM Door, Frame & HW (Single)
Patch Existing GWB Walls
09.2500 Acoustical Ceilings
F/I ACT Ceilings ($2.50/SF Material Budget)
F/I ACT Standard Grid ($1.50/SF Material Allowance)
09.6000 Flooring
F/I LVT (Luxury Vinyl Tile) Flooring & Vinyl Base
09.9100 Painting
Paint Base Molding
Paint GWB Walls
Paint GWB Walls (Plan View)
Paint/Stain Wood Door + HM Frame (Single)
10.4400 Fire Protection Specialties
Fire Extinguisher Cabinet + FE
21.0000 Sprinkler
Dry Sprinkler Budget For Parking Area
Sprinkler Budget
22.0000 Plumbing
F/I Heat Trace For Waste Piping @ Parking Level
F/I Insta-Hot Water Heaters
I/O Exam Room Sink & Faucet
Relocate 10 Gas Meters
22.4000 Plumbing Fixtures
F/O Exam Room Sink & Faucet
23.0000 HVAC
HVAC Budget
Relocate Condenser Unit
26.0000 Electric

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
Electrical Rough Ins
F/I 200Amp Panel
F/I Duplex Receptacle
F/I GFI Receptacle
F/I Single-Pole Switch
F/I Temporary Lighting @ 2nd Floor
F/I Weatherproof GFI Receptacle
I/O Lighting Fixture
I/O Lighting Fixture
Wire HVAC Equipment
Wire HWHs
26.5000 Lighting Fixtures
F/O Lighting Fixtures ($250/Ea Budget)
27.1000 Tel/Data (Back Boxes & Conduit Into Ceiling Only)
F/I Tel/Data Outlet
28.4600 Fire Alarm
Fire Alarm
31.0000 Earthwork
Backfill Frost Walls
Backfill Slab & Compact
Concrete Washout
Excavate Foundation (Frost Walls)
Excavate Foundation (Slab on Grade)
Export & Dispose of Excess Fill
F/I Crushed Stone
31.1100 Storm Water Management
Drainage & Stormwater Management
F/I 4" Footing Drain to Daylight
31.2500 Erosion And Sedimentation Controls
F/I Construction Entrance
F/I Silt Fence
32.1200 Paving
F/I Base Course
F/I Subbase
F/I Top Course
32.1400 Hardscaping

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Belgium Block Curb
32.1600 Site Concrete
F/I Monolithic Sidewalk (6-3/4” Crushed Stone + 4” Concrete)
32.1723 Pavement Markings
Basic Striping
32.9300 Seeding
Seeding & Haying

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Notes and Clarifications:

1. Pricing is to be used for budgetary purposes only.
2. All work to be performed during normal working hours. Overtime is not included.
3. Pricing is based on using open shop labor.
4. Permits and fees are not included.
5. Surveying fees are not included. Montana will coordinate stakeouts.
6. Temporary heating is not included. If required, will be billed on time and material basis.
7. Winter additive, ground thawing and/or blankets for concrete is not included.
8. Rock removal is not included.
9. Snow/ice removal is not included.
10. Dewatering is not included.
11. Removal of unsuitable soils is not included.
12. Landscaping is not included. Will will seed the disturbed grass areas when construction is complete.
13. Window treatments are not included.
14. Data wiring is not included.
15. The design we included has parking @ ground level and two floors above.
16. The second floor is just a white box with infrastructure for HVAC & electric included but no interior walls or finishes of any kind are included.
17. Pricing is based on existing utilities being sufficient to handle the additional load. We have included 2 additional panels but if a service upgrade is needed there will be additional costs associated with this scope.
18. We have included a dry sprinkler system at the ground floor parking level.
19. The exterior windows are priced as salvaging the existing windows on the north side of the building and new windows to match on the east and west sides.
20. The fire alarm budget is based off of utilizing the existing system assuming no upgrades are needed for the panel.