EXHIBIT B

Construction Management | General Contracting

Montana Contracting Corp is a full service General Contractor and Construction Management Firm. We take pride in our commitment to excellence and professionalism in the Metropolitan NY and NJ commercial construction marketplace.

MONTANA
CONTRACTING

About Us

Montana Contracting Corp. is a full–service general contractor, construction manager and residential developer. With over 35 years of experience providing quality high-end residential and commercial renovations, Montana Contracting is equipped to handle simple improvements to full scale renovations including ground up projects. We offer our clients a wide variety of construction and building related services anchored by decades of proven success and reliability.

Letter from the President

From Montana's inception in 1984 our firm has grown from a family-owned and operated home builder to a diverse construction management firm building ground-up developments, corporate interiors and hospitality projects. Through our growth and success we have not forgotten the core values and ethics that Montana was founded on. At Montana Contracting, we recognize the challenges in today's marketplace and the expectations of our clientele. We believe in honesty and integrity, doing the right things for the right reasons, and treating people fairly. Each project is pursued with the sense of urgency, excellence and professionalism that our clients expect and deserve.

MONTANA
CONTRACTING

Core Values

Family First
“The homemaker has the ultimate career. All other careers exist for one purpose only – and that is to support the ultimate career.” - C.S. Lewis

Mutual Respect
"True greatness will be achieved through the abundant mind that works selflessly - with mutual respect, for mutual benefit.: - Steven Covey

Collaboration
"Individual commitment to a group effort — that is what makes a team work, a company work, a society work, a civilization work." - Vince Lombardi

Absolute Ownership
"Responsibility equals accountability equals ownership. And a sense of ownership is the most powerful weapon a team or organization can have." - Pat Summitt

Attitude
"Your living is determined not so much by what life brings to you as by the attitude you bring to life; not so much by what happens to you as by the way your mind looks at what happens." - Khalil Gibran

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 01/14/2026

Ability Beyond

4 Berkshire Boulevard
Bethel, Connecticut 06801

Re: Ability Beyond

Proposal

Montana Contracting Corp. will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project based on plans dated for the sum of: **$2,507,608**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting Corp.

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 01/14/2026

Estimate: 26001 Ability Beyond

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
01 General Requirements			
01.0050 General Requirements	$30,246	1.21%	7.30
02 Existing Conditions			
02.1500 Containers/Waste Removal	$11,400	0.45%	2.75
04 Masonry			
04.5710 Brick	$6,821	0.27%	1.65
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$36,111	1.44%	8.72
06.2200 Millwork	$34,823	1.39%	8.41
06.4001 Wood Framing Materials	$71,947	2.87%	17.37
06.4002 Wood Framing Labor	$46,202	1.84%	11.15
07 Thermal and Moisture Protection			
07.2000 Insulation	$52,457	2.09%	12.66
07.3000 Roofing	$71,631	2.86%	17.29
07.6600 Gutters & Leaders	$4,388	0.18%	1.06
07.9510 Siding	$36,760	1.47%	8.87
08 Openings			
08.1400 Doors, Frames & HW	$62,837	2.51%	15.17
08.1600 Entry Doors & HW	$12,590	0.50%	3.04
08.5000 Windows	$30,848	1.23%	7.45
08.8500 Shower Rods & Curtains	$1,113	0.04%	0.27
09 Finishes			
09.3013 Tile & Stone	$3,707	0.15%	0.89
09.6000 Flooring	$1,980	0.08%	0.48
09.9100 Painting	$40,187	1.60%	9.70
10 Specialties			
10.0000 SQ4D	$636,000	25.36%	153.51
10.2600 Wallcoverings	$31,741	1.27%	7.66
10.2800 Bath Accessories (Allowance)	$15,900	0.63%	3.84
10.3100 Fireplaces (Allowance)	$25,440	1.01%	6.14
11 Equipment			
11.3100 Appliances (Allowance)	$17,596	0.70%	4.25
12 Furnishing			
12.2000 Window Treatments (Not Included)	$0	0.00%	0.00
12.3600 Countertops	$15,469	0.62%	3.73
21 Fire Suppression			
21.0000 Sprinkler	$41,446	1.65%	10.00
22 Plumbing			
22.0000 Plumbing	$126,034	5.03%	30.42
22.4000 Plumbing Fixtures	$14,465	0.58%	3.49
23 Heating, Ventilating and Air-Conditioning			

Description	Total	Percent of Cost	Cost/SF
23.0000 HVAC	$207,336	8.27%	50.04
26 Electrical			
26.0000 Electric (To Code)	$112,472	4.49%	27.15
26.3600 Generators & Transfer Switches	$70,172	2.80%	16.94
26.5000 Lighting Fixtures	$24,380	0.97%	5.88
28 Safety And Security			
28.4600 Fire Alarm	$44,520	1.78%	10.75
31 Sitework			
31.0000 Earthwork	$15,280	0.61%	3.69
31.1100 Drainage & Stormwater	$75,995	3.03%	18.34
32 Exterior Improvements			
32.1200 Asphalt Driveway	$50,501	2.01%	12.19
32.1400 Paver Patio (By SQ4D)	$0	0.00%	0.00
33 Utilities			
33.3100 Septic Systems	$41,340	1.65%	9.98
Sub-Total (Direct Cost)	**$2,122,133**	**84.63%**	**512.22**
General Conditions	$212,213	8.46%	51.22
Fee	$151,733	6.05%	36.62
Insurance	$74,582	2.97%	18.00
Sub-Total ()	**$2,560,661**	**102.12%**	**618.07**
Discount If Project Starts Q3 or Earlier	-$53,053	-2.12%	-12.81
Total Estimate	**$2,507,608**	**100%**	**605.26**

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: Ability Beyond

Scope of Work

Description
01.0050 General Requirements
Blueprints
Jobsite Trailer
Professional Cleaning
Temporary Fencing
Temporary Toilet(s)
02.1500 Containers/Waste Removal
Containers/Waste Removal
04.5710 Brick
F/I 1" Rigid Insulation Behind Brick
F/I Brick Veneer
06.2000 Finish Carpentry
F/I Base Molding [5 ¼” Wood Neck]
F/I Base Molding [5 ¼” Wood Neck]
F/I Door Casing
F/I Window/Exterior Door Casing
I/O Barn Style Door
I/O Exterior Door Hardware
I/O Interior Door Hardware
I/O Interior Wood Door & F/I Trim
I/O Window Hardware & Screen(s)
06.2200 Millwork
F/I Island Cabinets @ Kitchen
F/I Lower Cabinets @ Kitchen
F/I Lower Cabinets @ Laundry
F/I Upper Cabinets (Not Included - Not Shown)
06.4001 Wood Framing Materials
F/O Wood Roof Trusses (Scissor)
06.4002 Wood Framing Labor
Crane Rental (Per Week)
I/O Residential Exterior Door(s)
I/O Roof Framing & Sheathing
I/O Roof Framing, Sheathing & Furring Strips @ Porch
I/O Window(s) (Standard Sizes)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
07.2000 Insulation
F/I Insulation & Air Seal @ Window(s)/Exterior Door(s)
F/I R-49 Spray-Foam
07.3000 Roofing
F/I 30 Year Asphalt Shingles
F/I Standing Seam Sheet Metal Roofing
07.6600 Gutters & Leaders
F/I 5" Gutters
F/I 5" Leaders
07.9510 Siding
F/I 2" Rigid Insulation (Under Siding)
F/I Aluminum Trim Coil Trim
F/I Exterior Post Covers
F/I Vinyl Board & Batten [Certainteed Traditional Accent 8" Single Board & Batten]
F/I Vinyl Shingles [Certainteed Cedar Impressions Perfection, Single 7" Straight Edge]
F/I Vinyl Vented Soffits [Certainteed InvisiVent Triple 3-13” High Performance]
08.1400 Doors, Frames & HW
Barn Style Door
F/O Door Hardware ($150/Ea Allowance)
F/O Solid-Core Wood Door + HM Frame
F/O Solid-Core Wood Doors (Pair)
08.1600 Entry Doors & HW
F/O Residential Entry Door Deadlock/Door Knob Combo [$50/Each Allowance Placeholder]
F/O Residential Fiberglass Entry Door (36"x80"x6-9/16") ($1000/Each Allowance Placeholder]
F/O Residential Wood Entry Door (36"x80"x9-1/6") ($1,500 Allowance Placeholder]
08.5000 Windows
F/O Windows
08.8500 Shower Rods & Curtains
F/I Shower Rods & Curtains
09.3013 Tile & Stone
F/I Tile Backsplash (4' High) ($7/SF Material Allowance)
09.6000 Flooring
F/I Sheet-Vinyl Flooring [Altro Aquarius w/Welded Seams]
Stamped Flooring (By SQ4D)
09.9100 Painting
Paint Base Molding

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
Paint Door Casing
Paint GWB Ceilings
Paint GWB Walls
Paint Window Casing
Paint/Stain Wood Doors & Casing
Prime & Paint Residential Fiberglass Entry Door
10.0000 SQ4D
Misc. (Shipping, Travel, Lodging, etc.)
SQ4D Package
10.2600 Wallcoverings
F/I Altro Whiterock @ Bathroom Walls
F/I FRP Panels @ Laundry [Marlite Symmetrix Smartseam]
10.2800 Bath Accessories (Allowance)
F/O Bath Accessories (Allowance)
10.3100 Fireplaces (Allowance)
Fireplaces & Surround (Allowance)
11.3100 Appliances (Allowance)
Dishwasher
Dryer
F/O Vent Hood Insert 30"
Refrigerator
Washer
12.2000 Window Treatments (Not Included)
Window Treatments
12.3600 Countertops
Template, Fabricate & Install Solid Surface Countertop ($65/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertop @ Laundry ($65/SF Material Allowance)
21.0000 Sprinkler
Sprinkler Budget
22.0000 Plumbing
F/I Floor Drain
F/I Hot Water Heaters
F/I Refrigerator Waterline
I/O Appliance
I/O Bath Lav (Sink) & Faucet
I/O Custom Shower

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
I/O Dishwasher
I/O Residential Toilet
Plumbing Rough-Ins
Plumbing Undergrounds
22.4000 Plumbing Fixtures
F/O Basic Round Push Plate - Dual Button [Toto YT930]
F/O Commercial Wall-Hung Lav Sink [Toto LT307(A)]
F/O Hand Shower w/Adjustable Mount
F/O In-Wall Tank Unit [Toto 1.8 & 0.9 GFP (WT172M)]
F/O Lav Faucet [Grohe Single-Handle S-Size (3427000A)]
F/O Shower Valve Body [Delta Universal R10000]
F/O Softclose Seat [Toto SS114/SS113]
F/O Wall-Hung Toilet [Toto EP 1.28 & 0.9 GPF (CWT428CMFG)]
23.0000 HVAC
F/I Central Exhaust System
F/I Ducted Heating & Cooling System
F/I PTAC Units w/Fresh Air Intake @ Bedrooms
26.0000 Electric (To Code)
F/I 200Amp Panels + CT Cabinet
F/I Devices & Switching
F/I Mechanical Equipment Wiring
F/I Whole-House Rough-In Wiring
F/O (3) 500 kcmil Aluminum Conductors + (1) #2 Ground
F/O 2" Conduit for Internet Provider
F/O 2" Conduit for Underground Electrical Service (Schedule 40 PVC)
F/O Terminations and Connections for 400 Amp Service
I/O 2" Conduit for Underground Electrical Service
I/O Lighting Fixtures
I/O Underground Conduit for Internet Service (By Others)
I/O Wire for 400 Amp Underground Electrical Service
Primary Service Up Pole
Provide Temporary Electrical Service
Underground Electrical Service Inspection
26.3600 Generators & Transfer Switches
F/I Generator + ATS
26.5000 Lighting Fixtures

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/O Lighting Fixtures (Budget)
28.4600 Fire Alarm
Fire Alarm Budget
31.0000 Earthwork
F/I Crushed Stone
Trenching, Sand and Backfill Utility Trench for Underground Electric (2' Deep w/1' Sand)
31.1100 Drainage & Stormwater
F/I 15" CMP Piping (Including Trenching, Bedding & BAckfill)
F/I 4" Footing Drain
F/I 8" HDPE Overflow Piping
F/I Cultec Units [330XLHD]
F/I DW#2
F/I Pre-Treatment Tank w/Riser Inlet to Grade
32.1200 Asphalt Driveway
F/I Asphalt Driveway (In Lieu of Pavers)
32.1400 Paver Patio (By SQ4D)
Paver Patio (By SQ4D)
33.3100 Septic Systems
F/I Sanitary Piping from House to Septic
F/I Septic System

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Notes and Clarifications:

1. Pricing is valid for sixty (60) calendar days.
2. Permit fees are not included.
3. Surveying fees are not included.
4. Utility company fees, including tap fees, connection fees, impact fees, and capacity charges.
5. Department of Health review fees related to septic or care facilities.
6. Geotechnical investigations, soil testing, test pits, rock excavation, ledge removal, blasting, or unsuitable soil remediation are excluded.
7. Hazardous materials of any kind, including asbestos, lead, mold, or contaminated soils, are excluded.
8. Rock hammering/removal is not included.
9. Fire sprinkler, electrical and fire alarm systems are included at code minimum only; upgrades or enhanced systems are excluded.
10. Electrical scope excludes data, telecom, Wi-Fi infrastructure, security systems, access control, cameras, and AV systems.
11. Fire alarm monitoring startup fees and recurring service charges.
12. All pricing is based on documents issued for budget only and is subject to change at permit or construction document phase.
13. Engineering services, including structural, MEP, fire protection design, redesigns, or re-approvals, are excluded.
14. Window treatments, furniture, furnishings, appliances beyond basic allowances, and owner-supplied items are excluded.
15. Special inspections and third-party testing fees, including concrete, masonry, steel, fireproofing, and soils are not included.
16. Snow removal, winter maintenance, and freeze protection beyond normal operations are not included.