Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Date: 07/11/2025

Eli Josephs

Re: Army Recruitment Center

Proposal

Montana Contracting Corp. will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$725,149**

Attachments:
Scope of Work
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting Corp.

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 07/11/2025

Estimate: 25035 Army Recruitment Center

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0040 Architecture & Engineering	$17,500	2.41%	
01.0050 General Requirements	$56,175	7.75%	
02 Existing Conditions			
02.1000 Demolition	$18,181	2.51%	
02.1500 Containers/Waste Removal	$3,700	0.51%	
03 Concrete			
03.1000 Concrete	$3,820	0.53%	
03.1500 Concrete Cutting	$3,146	0.43%	
06 Wood , Plastic and Composites			
06.2200 Millwork	$3,994	0.55%	
08 Openings			
08.1100 HM Doors, Frames & HW	$43,920	6.06%	
09 Finishes			
09.2300 Drywall & Carpentry	$107,761	14.86%	
09.2500 Acoustical Ceilings	$22,835	3.15%	
09.3013 Tile & Stone	$55,937	7.71%	
09.6000 Flooring	$12,645	1.74%	
09.9100 Painting	$21,562	2.97%	
10 Specialties			
10.2600 Wall And Door Protection	$1,729	0.24%	
10.2800 Bath Accessories	$5,796	0.80%	
10.4400 Fire Protection Specialties	$2,310	0.32%	
10.5600 Storage Shelving	$6,000	0.83%	
12 Furnishing			
12.2000 Window Treatments	$4,900	0.68%	
21 Fire Suppression			
21.0000 Sprinkler	$9,624	1.33%	
22 Plumbing			
22.0000 Plumbing	$21,300	2.94%	
22.4000 Plumbing Fixtures	$7,700	1.06%	
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$55,329	7.63%	
26 Electrical			
26.0000 Electric	$36,380	5.02%	
26.5000 Lighting Fixtures	$17,600	2.43%	
27 Communications			
27.1000 Tel/Data	$7,200	0.99%	
27.2100 Network Equipment	$2,940	0.41%	
28 Safety And Security			
28.4600 Fire Alarm	$1,200	0.17%	

Description	Total	Percent of Cost	Cost/Unit
28.4610 Security	$63,500	8.76%	
Sub-Total (Direct Cost)	**$614,685**	**84.77%**	
Permit & Pickup Fee	$500	0.07%	
Overhead & Profit	$92,278	12.73%	
Insurance	$17,687	2.44%	
Total Estimate	**$725,149**	**100%**	

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: Army Recruitment Center

Scope of Work

Description
01.0040 Architecture & Engineering
Architectural & Engineering
01.0050 General Requirements
Assistant Project Manager
Blueprints
General Labor
General Supervision
Misc. Materials
Project Manager I
Supervision
Temporary Toilet(s)
02.1000 Demolition
Remove ACT Ceilings, Lights & Diffusers
Remove Doors & Frames
Remove Flooring
Remove Interior Partitions
Remove Interior Partitions
Remove Plumbing Fixtures
Remove Plywood From Walls
02.1500 Containers/Waste Removal
30-Yard Container
03.1000 Concrete
F/I Gravel Subbase in Trench
Hand-Dig Fill from Trench & Remove from Jobsite
Patch Concrete Slab
03.1500 Concrete Cutting
Sawcut Existing Slab (2' Wide) For Underground Utilities. Flip & Haul Concrete Off Site.
06.2200 Millwork
F/I 3 Shelves @ Janitors Closet
F/I Plastic Laminate Countertops
08.1100 HM Doors, Frames & HW
F/O Door Hardware (Grade 2 Interior)
F/O HM Frame (Single)
F/O Solid-Core Wood Door w/Glass Panels

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
09.2300 Drywall & Carpentry
Assemble, Install & Anchor Storage Shelving Units
F/I 3-5/8" Metal Stud Framing
F/I 5/8" GWB Walls
F/I Acoustical Sealant
F/I Blanket Insulation
F/I Chair Rail [Alexandria Molding AMH 300 1-1/16" x 3"]
F/I Fire Department Access Lockbox
F/I Firestop Sealant
F/I Hung GWB Ceilings
F/I Level 5 Finish 5/8" GWB Walls
F/I Level 5 Finish 5/8" GWB Walls
F/I Plywood Panel on Wall for Electrical/Low-Voltage Equipment
F/I Wood Blocking
F/I Wood Blocking for Bath Accessories (Per Bath)
I/O Bath Accessories
I/O Fire Extinguisher Cabinet
I/O Interior HM Door, Frame & HW (Single)
Patch Existing GWB Walls To Level 5 Finish
09.2500 Acoustical Ceilings
F/I ACT Ceilings [2x4 With 2x2 Tegular-Revealed Panels, White, NRC Of .65]
09.3013 Tile & Stone
F/I Floor Tile [Shaw Contract - US Recruiting Standard, CT30J Sand 00200, 12x24]
F/I Floor Tile [Shaw Contract - US Recruiting Standard, CT30J Sand 00200, 12x24]
F/I PT-1/PT-2 Wall Tile [Shaw Contract US Recruiting Porcelain Standard, CT30J Sand 00200/CT30J Dark Grey 005500, 12x24]
F/I PT-2 Tile Base Cut 12x24 To 6x24
F/I Schluter Dilex Cove Brushed Chrome/Nickel
F/I Schluter Jolly Strip Brushed Chrome/Nickel
F/I Schluter Reno Ramp-TK Brushed Chrome/Nickel
F/I Waterproofing for Floor Tile
F/I Waterproofing for Wall Tile
09.6000 Flooring
Concrete Sealer (2 Coats)
F/I 4" Rubber Cove Base
F/I Carpet Tile
F/I VCT

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/O Carpet Tile Attic Stock
09.9100 Painting
Paint Chair Rail Molding
Paint GWB Ceilings
Paint GWB Walls
Paint GWB Walls
Paint GWB Walls
Paint/Stain Wood Door + HM Frame (Single)
10.2600 Wall And Door Protection
F/I FRP Panels @ Janitors Closet
10.2800 Bath Accessories
F/O ADA Bath Mirror 1/4" w/Polished Edges
F/O ADA Restroom Sign w/Braille
F/O CCTV Signage
F/O Coat Hook
F/O Electric Hand Dryers [Xlerator Model XB-SB]
F/O Grab Bar 18"
F/O Grab Bar 36"
F/O Grab Bar 42"
F/O Room Blade Signs
F/O Sanitary Napkin Disposal
F/O Soap Dispenser
F/O Toilet Tissue (Paper) Dispenser [Surface Mounted]
F/O Trash Receptacle Stand Alone Stainless Steel
10.4400 Fire Protection Specialties
F/O Fire Extinguisher Cabinet + FE
10.5600 Storage Shelving
F/O Storage Room Shelving
12.2000 Window Treatments
F/I Fixed Panel Shade @ Exterior Glass Doors
F/I Motorized Shades With Controls
21.0000 Sprinkler
Sprinkler Budget
Sprinkler Permit, Shop Drawings & Inspection
22.0000 Plumbing
Disconnect Existing Plumbing Fixtures

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Hot Water Heater (HWH)
I/O Bath Lav (Sink) & Faucet
I/O Commercial Toilet
I/O Mop Sink Connection
I/O Wall-Mounted Urinal (Including Rough-In)
I/O Water Fountain/Cooler
22.4000 Plumbing Fixtures
F/O Commercial Floor-Mounted Toilet + Flushometer
F/O LAV Sink
F/O Lav Faucet
F/O Mop Sink
F/O Wall-Mounted Urinal
F/O Water Fountain/Cooler [Elkay EZS8WSSK]
23.0000 HVAC
Duct Exhaust Fans Up Through Roof With Gooseneck
F/I Economizer
HVAC Budget Per SF
26.0000 Electric
Dedicated Equipment Duplex 20amp
Duplex Receptacle
Electrical Disconnects Prior to Demo (Medium)
Exhaust Fan
F/I Conduit From Demarcation Point To Military Services Commo Board
GFI Receptacle
I/O Exit Sign
I/O Lighting Fixture
I/O Lighting Fixture (Commercial)
Quad Receptacle
Wire Bath Accessories And Fixtures
Wire HVAC Equipment
Wire Hand Dryers
Wire Hot Water Heater [HWH] (120V)
Wire Motorized Shades
26.5000 Lighting Fixtures
Exit Sign
Lighting Fixture Budget

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
Lighting Fixture Budget
Lighting Fixture [Lucifer DL2YP-LEDX]
27.1000 Tel/Data
Tel/Data Outlet
27.2100 Network Equipment
F/I Wireless Access Point (+Wire & Accessories)
28.4600 Fire Alarm
Smoke Detector
28.4610 Security
Certified Integrator
F/I Aiphone Desk Station IXG2C7
F/I Aiphone Desk Station Stand MCW-S/B
F/I Aiphone Guard Station IXG-MK
F/I Aiphone IXG System IXG-DM7-HIDA
F/I Aiphone Network Door Release Relay Adaptor IXG-MAA
F/I Aiphone Surface Mounted Box SBX-IXGDM7
F/I Camera Hanwah XNF-9013RV
F/I Camera Hanwha XND-C8083RV
F/I Displays2Go SLC3770LBK Monitor Mounting Pole
F/I Hanwha LED Color Monitor SMT-2431
F/I Hanwha PoE Network Video Decoder SPD-152
F/I Hanwha Wave VMS (NVR) CCTV System WRT-P-3104W-16TB
F/I LSP Power Supply FPO250-C8D8E2
F/I Netgear 48 Port PoE+ Switch
F/I Samsung 55" 4K CCTV Monitor DU8000
F/I Trip Light Model # SRW12UDP For EC & CCTV Systems
F/I Tripp Lite 12U SRW12UDP Locking Security Cabinet
F/I Vertical Plastic Wire Duct ICCMSCMA81
F/I Videosecu BJZ ML411B-B1 Swivel Mounting Bracket
Provide Wave Pro-1 Recording Licensing
Provide Wave Pro-4 Recording Licensing
Provide Wave Pro-8 Recording Licensing
Security Wiring

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Notes and Clarifications

1. Pricing is valid for thirty (30) business days.
2. Pricing is based on using open shop labor on straight time only.
3. Permit fees are not included.
4. Asbestos testing/abatement are not included.
5. Phasing is not included.
6. Tax is not included. It is assumed that a capital improvement certificate will be provided prior to the start of construction.
7. Moving/relocating of equipment and/or furniture is not included.
8. Building and/or elevator service charges are not included.
9. Special inspections are not included.
10. Professional cleaning is not included.
11. Removal of adhesives or other contaminants on the existing slab is not included.
12. Existing exterior doors and hardware are existing to remain.
13. Wall coverings and graphics are excluded pending final locations and approval of graphics.
14. Security & data equipment & cabling is budgetary pending final requirements.
15. If floor boxes are required there will be additional costs.
16. We have included laminate counter tops in test rooms.
17. All finish items are allowances until final approval of products.
18. HVAC pricing is assuming the existing roof top unit is being re-used.
19. The HVAC pricing is budgetary pending approved design.
20. Fire alarm is priced as local hard wired smoke detectors. If a building system is required there will be additional costs.