Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 01/14/2026

Pat Quackenbush
Cushman & Wakefield

Re: Brewster Breakroom

Proposal

Montana Contracting Corp. will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project based on plans dated for the sum of: **$72,284**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting Corp.

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 01/14/2026

Estimate: 26002 Brewster Breakroom

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$13,100	18.12%	
02 Existing Conditions			
02.1000 Demolition	$1,180	1.63%	
02.1500 Containers/Waste Removal	$795	1.10%	
06 Wood , Plastic and Composites			
06.2200 Millwork	$18,773	25.97%	
09 Finishes			
09.2300 Drywall & Carpentry	$4,996	6.91%	
09.2500 Acoustical Ceilings	$742	1.03%	
09.6000 Flooring	$4,293	5.94%	
09.9100 Painting	$1,819	2.52%	
22 Plumbing			
22.0000 Plumbing	$9,063	12.54%	
22.4000 Plumbing Fixtures	$1,300	1.80%	
26 Electrical			
26.0000 Electric	$9,222	12.76%	
Sub-Total (Direct Cost)	**$65,283**	**90.31%**	
Fee	$4,896	6.77%	
Insurance	$2,105	2.91%	
Total Estimate	**$72,284**	**100%**	

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: Brewster Breakroom

Scope of Work

Description
01.0050 General Requirements
General Labor
Misc. Materials
Project Management
Supervision
02.1000 Demolition
Remove Flooring
02.1500 Containers/Waste Removal
20-Yard Container
06.2200 Millwork
F/I Lower Cabinets
F/I Plastic Laminate Countertops
F/I Upper Cabinets
09.2300 Drywall & Carpentry
F/I 3-5/8" Metal Stud Framing
F/I 5/8" GWB Walls (Level 4 Finish)
Patch Existing GWB Walls
09.2500 Acoustical Ceilings
Modify ACT Ceilings
09.6000 Flooring
F/I Base To Match Existing
F/I LVT (Luxury Vinyl Tile) Flooring
09.9100 Painting
Paint GWB Walls
Paint GWB Walls
22.0000 Plumbing
F/I 1/2" Copper Water Lines
F/I Ejector Pump + 125 Feet Of Piping
I/O Sink & Faucet
Instant Hot Under Sink
22.4000 Plumbing Fixtures
F/O Break Room Faucet
F/O Break Room Sink
26.0000 Electric

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I 100Amp Sub Panel Adjacent To Existing Panel
F/I Dedicated Equipment Duplex 20amp
F/I Duplex Receptacle

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Notes and Clarifications:

1. Pricing is valid for forty five (45) business days.
2. Pricing is based on using open shop labor on straight time only.
3. Permit fees are not included.
4. Asbestos testing/abatement are not included.
5. Tax is not included. It is assumed that a capital improvement certificate will be provided prior to the start of construction.
6. Special inspections are not included.
7. We have included a broom-swept clean and debris removal from work areas; professional cleaning, including window washing, floor scrubbing, and final turnover cleaning, is excluded and to be provided by others.
8. Sprinkler heads are existing to remain.
9. Light fixtures and switching are existing to remain.
10. HVAC is existing to remain.
11. We have included a 100Amp sub panel adjacent to the existing panel.
12. Fire alarm is existing to remain.
13. Six dedicated outlets are included.
14. An ejector pump and 125 feet of piping is included along with 135 feet of water lines with an instant hot water heater under the sink.

Alternates

1. Rework LED lighting in the warehouse. **$4,560**