MONTANA
HOME BUILDERS

A Custom Builder Creating Distinguished Homes

As you consider building a new home or renovating your current home, you are entering one of the most exciting times of your life. At Montana Home Builders we will be there to help with the many decisions you will be making. The best floor plan, the right style, careful choice of materials and finishes, all brought together to create a home as distinct and unique as you are.

MONTANA
HOME BUILDERS

About Us

Montana Home Builders is a full-service general contractor, construction manager and residential developer. With over 40 years of experience, Montana Home Builders is equipped to handle projects of all sizes and complexities. We offer our clients a wide variety of construction and building related services anchored by decades of proven success and reliability.

Letter from the President

From Montana's inception in 1984 our firm has grown from a family-owned and operated home builder to a diverse construction management firm building ground-up developments, corporate interiors and hospitality projects.

Through our growth and success we have not forgotten the core values and ethics that Montana was founded on. At Montana Home Builders, we recognize the challenges in today's marketplace and the expectations of our clientele. We believe in honesty and integrity, doing the right things for the right reasons, and treating people fairly. Each project is pursued with the sense of urgency, excellence and professionalism that our clients expect and deserve.

MONTANA
HOME BUILDERS

Core Values

Family First
“ The homemaker has the ultimate career. All other careers exist for one purpose only, and that is to support the ultimate career. ” - C.S. Lewis

Mutual Respect
"True greatness will be achieved through the abundant mind that works selflessly, with mutual respect, for mutual benefit." - Steven Covey

Collaboration
"Individual commitment to a group effort, that is what makes a team work, a company work, a society work, acivilization work." - Vince Lombardi

Absolute Ownership
"Responsibility equals accountability equals ownership. A sense of ownership is the most powerful weapon a team or organization can have." - Pat Summitt

Attitude
"Your living is determined not so much by what life brings to you as by the attitude you bring to life; not so much by what happens to you as by the way your mind looks at what happens." - Khalil Gibran

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Date: 01/23/2025

Adam Golinczak
Adam Golinczak Architecture P.C.
2 Tilson Ave
Highland, NY 12528

Re: Crest House

Proposal

Montana Home Builders will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project based on plans dated 11/11/2024 for the sum of: **$6,384,287**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Home Builders

Accepted By: _____
Date of Acceptance: _____

MONTANA
HOME BUILDERS

Status: Active Estimates
Contact:
Date: 01/23/2025

Estimate: 27095 Crest House

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
01 General Requirements			
01.0050 General Requirements	$542,000	8.49%	110.05
01.7000 Surveying	$13,500	0.21%	2.74
02 Existing Conditions			
02.1500 Containers/Waste Removal	$14,250	0.22%	2.89
03 Concrete			
03.1000 Concrete	$244,089	3.82%	49.56
03.3370 Concrete Topping	$56,616	0.89%	11.50
03.3500 Polished/Sealed Concrete	$11,714	0.18%	2.38
04 Masonry			
04.4300 Stone Masonry	$22,313	0.35%	4.53
05 Metal			
05.0050 Structural Steel	$650,324	10.19%	132.05
05.0100 Misc. Steel [Included in Structural Steel]	$0	0.00%	0.00
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$59,860	0.94%	12.15
06.2200 Millwork [Budgetary]	$109,948	1.72%	22.32
06.2300 Closet Interiors (Not Included)	$0	0.00%	0.00
06.6600 Decking	$86,922	1.36%	17.65
07 Thermal and Moisture Protection			
07.1000 Waterproofing	$15,606	0.24%	3.17
07.2000 Insulation	$105,303	1.65%	21.38
07.2400 Exterior Insulation & Finish Systems (EIFS)	$22,313	0.35%	4.53
07.3000 Roofing	$301,621	4.72%	61.24
07.6600 Gutters & Leaders	$4,847	0.08%	0.98
07.9510 Siding	$192,864	3.02%	39.16
08 Openings			
08.1100 Doors, Frames & HW	$24,000	0.38%	4.87
08.1400 Pre-Hung Wood Doors & HW	$64,100	1.00%	13.02
08.3700 Garage Doors	$10,500	0.16%	2.13
08.6200 Skylights	$21,420	0.34%	4.35
08.8200 Arch. Metal & Glass	$329,000	5.15%	66.80
08.8500 Shower Enclosures	$11,700	0.18%	2.38
09 Finishes			
09.2300 Drywall & Carpentry	$418,049	6.55%	84.88
09.2400 Decorative Plaster	$14,500	0.23%	2.94
09.2500 Acoustical Ceilings	$3,242	0.05%	0.66
09.3013 Tile & Stone	$68,947	1.08%	14.00
09.6400 Wood Flooring	$37,559	0.59%	7.63
09.7200 Wall Coverings	$7,500	0.12%	1.52
09.9100 Painting	$160,000	2.51%	32.49

Description	Total	Percent of Cost	Cost/SF
10 Specialties			
10.3100 Fireplaces	$27,767	0.43%	5.64
10.6000 Storage Containers	$7,560	0.12%	1.54
11 Equipment			
11.3100 Appliances	$72,210	1.13%	14.66
22 Plumbing			
22.0000 Plumbing	$60,947	0.95%	12.38
22.4000 Plumbing Fixtures	$12,540	0.20%	2.55
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$430,140	6.74%	87.34
26 Electrical			
26.0000 Electric	$337,816	5.29%	68.59
26.4100 Lightning Protection	$20,000	0.31%	4.06
26.5000 Lighting Fixtures	$55,000	0.86%	11.17
27 Communications			
27.1000 Wifi Systems	$6,375	0.10%	1.29
27.1020 Audio Visual	$22,926	0.36%	4.66
28 Safety And Security			
28.4600 Fire Alarm	$3,000	0.05%	0.61
28.4610 Security	$10,125	0.16%	2.06
31 Sitework			
31.0000 Sitework	$96,880	1.52%	19.67
31.1100 Drainage & Stormwater	$6,326	0.10%	1.28
31.2100 Off-Gassing Mitigation	$10,000	0.16%	2.03
31.2200 Grading	$10,100	0.16%	2.05
31.2300 Rock Hammering	$28,000	0.44%	5.69
31.2500 Erosion And Sedimentation Controls	$3,090	0.05%	0.63
32 Exterior Improvements			
32.0001 Driveway	$18,118	0.28%	3.68
32.1400 Hardscaping	$439,370	6.88%	89.21
32.1500 Fencing	$7,167	0.11%	1.46
32.3000 Site Improvements	$10,058	0.16%	2.04
32.3200 Retaining Walls At Driveway [Excluded]	$0	0.00%	0.00
33 Utilities			
33.2000 Well & Waterline (Allowance)	$38,844	0.61%	7.89
48 Electrical Power Generation			
48.1413 Solar	$85,000	1.33%	17.26
Sub-Total ()	**$5,443,966**	**85.27%**	**1,105.37**
Overhead	$435,517	6.82%	88.43
Fee	$440,961	6.91%	89.54
Insurance	$63,843	1.00%	12.96

Description	Total	Percent of Cost	Cost/SF
Total Estimate	**$6,384,287**	**100%**	**1,296.30**

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Notes and Clarifications:

General Exclusions:

1. Pricing is valid for thirty (30) calendar days.
2. All work to be performed during normal working hours. Overtime is not included.
3. Pricing is based on using open shop labor.
4. Permits and fees are not included.
5. 3rd party inspections are not included.
6. Surveying fees are not included. Montana will coordinate stakeouts.
7. Temporary heating is not included. If required, will be billed on time and material basis.
8. Pricing for foundation walls is based on heights indicated on plans. Variations in grade are not accounted for.
9. Winter additive, ground thawing and/or blankets for concrete is not included.
10. Temporary heat is not included.
11. Pricing for excavation is based on bottom of footing depths indicated on drawings. If additional excavation is required to reach virgin soil additional charges for machine time, labor, concrete, waterproofing and backfilling may be incurred.
12. Snow/ice removal is not included.
13. Dewatering is not included.
14. Removal of unsuitable soils is not included.
15. Landscaping is not included.
16. Pricing for installation of owner-supplied items is based on single mobilizations.
17. Window treatments are not included.
18. Pricing for well is based on a maximum depth of 400'. An additional cost of $20 will be billed for each additional foot thereafter.
19. Pricing for well casing is based on a maximum depth of 20' . An additional cost of $36 will be billed for each additional foot thereafter.
20. Major regrading or land balancing outside the immediate building area is not included.
21. Warranty coverage on owner-supplied materials or equipment is not included.
22. Professional cleaning is not included.
23. Pool and all assocated work is not included.

Project Specific Notes and Clarifications:

1. Pricing is based on an eighteen (18) month project.
2. Pricing for polished concrete is based on a high gloss, full exposure finish.
3. It is assumed that tile and stone accessories will be provided by owner (saddles, schluters, grout, etc.). We have labor and setting materials included.
4. We have included WD-3 decking at the Whiskey Deck.
5. Pricing for WD-2 decking is based on 5/4"x6" IPE.
6. Anti-split coating for Richlite decking is not included.
7. Steam shower included in specifications but not shown on plans is not currently included.
8. Exterior landscape lighting is not included.
9. Irrigation is not included.
10. Doorbell is not included.
11. The stucco finish on the foundation includes a scratch coat with wire base and topcoat and 3-1-1 mix being that it is on foam board and not directly on the concrete foundation.
12. Quietrock EZ-Snap is included where Quietrock is specified.
13. Retaining walls at the driveway are excluded.
14. Base molding is based on 1/2"x5" paint grade.
15. Closet interiors are excluded as per responsibility schedule.
16. We have included typical soft close hinges and soft close full extension under mount drawer sides. Other hardware where noted.
17. Pricing for millwork is budgetary pending final design.
18. Pricing for foundation waterproofing is based on a Tuff-N-Dri H8.
19. We have included sealing of finished side only of marble walls and floors.
20. Paving of driveway is not included as discussed at site walkthrough.
21. Bonding is not included.
22. Certification costs are not included.
23. We have included maintenance of driveway only for duration of project. No other work to driveway is included.

Owner Provided Items:

1. Septic tank(s), piping and leach field(s).
2. Furnishing and installation of TV's and brackets.
3. Exterior remote car charging station.
4. Fire extinguishers.

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

5. Wireless Access Points.
6. Security Devices.
7. Security Terminations.
8. Security Monitor/Computer.
9. Stone wall, floor and counter finishes.
10. Wallcoverings.
11. Plumbing fixtures per A9-122.00.
12. Bathroom accessories per A9-122.00.

Allowances:

1. $7,500.00 to install wallcoverings provided by owner.
2. $6,400.00 to furnish and install decorative plaster finish.
3. $25,000.00 to install WD-4 decking, including templating and fabrication as needed.
4. $30/sf to supply MT-AF Anodized Metal Panels.
5. $20,000.00 to supply and install lightning protection system.
6. $2,880.00 to supply cabinet hardware.
7. $2,500.00 to supply interior single wood doors (each).
8. $4,000.00 to supply interior pair wood doors (each).
9. $250.00 to supply door hardware (each).
10. $10,500.00 to furnish and install one (1) garage door with opener.
11. $50,000.00 to supply lighting fixture package (additional details required).
12. $28,000.00 for 80 hours of rock hammering.
13. $85,000.00 for solar.
14. $15/sf to supply paver material.
15. $10,000 to furnish and install gravel pathways.