Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Date: 01/09/2026

Don Petruncola
Tinkelman Architcture

Re: Dunagan Residence

Budget Proposal

Montana Home Builders hereby proposes all materials, labor and supervision in accordance with drawings dated for the sum of **$3,415,534**

Attachments:
Schedule of Values

Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto

Montana Home Builders

Accepted By: _____

Date of Acceptance: _____

MONTANA
HOME BUILDERS

Status: Active Estimates
Contact:
Date: 01/09/2026

Estimate: 25073 Dunagan Residence

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
01 General Requirements			
01.0050 General Requirements	$235,843	6.91%	43.67
02 Existing Conditions			
02.1000 Demolition	$42,000	1.23%	7.78
03 Concrete			
03.1000 Concrete	$152,317	4.46%	28.21
04 Masonry			
04.4300 Stone Masonry	$131,276	3.84%	24.31
05 Metal			
05.0050 Structural Steel	$55,282	1.62%	10.24
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$56,485	1.65%	10.46
06.2200 Millwork	$128,765	3.77%	23.85
06.2300 Closet Interiors	$28,952	0.85%	5.36
06.4001 Wood Framing Materials	$170,684	5.00%	31.61
06.4002 Wood Framing Labor	$155,883	4.56%	28.87
06.4300 Wood Stairs And Railings	$20,403	0.60%	3.78
06.6600 Decking	$73,573	2.15%	13.62
07 Thermal and Moisture Protection			
07.1000 Waterproofing	$20,740	0.61%	3.84
07.2000 Insulation	$76,834	2.25%	14.23
07.3000 Roofing	$193,841	5.68%	35.90
07.6600 Gutters & Leaders	$6,907	0.20%	1.28
07.9510 Siding	$78,442	2.30%	14.53
08 Openings			
08.1400 Wood Doors & HW	$42,210	1.24%	7.82
08.1600 Residential Entry Doors & HW	$77,660	2.27%	14.38
08.5000 Windows	$90,300	2.64%	16.72
08.8500 Shower Enclosures	$9,450	0.28%	1.75
09 Finishes			
09.2300 Drywall & Carpentry	$78,200	2.29%	14.48
09.3013 Tile & Stone	$56,840	1.66%	10.53
09.6400 Wood Flooring	$100,903	2.95%	18.69
09.9100 Painting	$55,868	1.64%	10.35
10 Specialties			
10.2800 Bath Accessories	$6,300	0.18%	1.17
10.3100 Fireplaces	$29,400	0.86%	5.44
11 Equipment			
11.3100 Appliances (NIC)	$0	0.00%	0.00
12 Furnishing			
12.3600 Countertops	$20,487	0.60%	3.79

Description	Total	Percent of Cost	Cost/Unit
14 Conveying System			
14.2000 Elevators	$68,250	2.00%	12.64
22 Plumbing			
22.0000 Plumbing	$82,845	2.43%	15.34
22.4000 Plumbing Fixtures	$28,160	0.82%	5.21
23 Heating, Ventilating and Air-Conditioning			
23.0000 HVAC	$218,295	6.39%	40.43
26 Electrical			
26.0000 Electric	$159,018	4.66%	29.45
26.5000 Lighting Fixtures	$35,475	1.04%	6.57
31 Sitework			
31.0000 Earthwork	$64,704	1.89%	11.98
31.1100 Drainage & Stormwater	$60,494	1.77%	11.20
31.2200 Grading	$7,875	0.23%	1.46
31.2500 Erosion And Sedimentation Controls	$1,297	0.04%	0.24
32 Exterior Improvements			
32.1400 Hardscaping	$3,028	0.09%	0.56
32.3200 Retaining Wall	$18,900	0.55%	3.50
Sub-Total (Direct Cost)	**$2,944,185**	**86.20%**	**545.22**
Overhead	$147,209	4.31%	27.26
Profit	$309,139	9.05%	57.25
Insurance	$15,000	0.44%	2.78
Total Estimate	**$3,415,534**	**100%**	**632.51**

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Estimate Description: Dunagan Residence

Scope of Work

Description
01.0050 General Requirements
Assistant Project Management
Blueprints
General Labor
General Supervision
Misc. Materials
Senior Project Management
Supervision
Temporary Toilet
02.1000 Demolition
Demolish Existing House
03.1000 Concrete
Concrete Pumps
Form & Pour Concrete Footings
Form & Pour Concrete Foundation Wall(s)
Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.
Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.
Form & Pour Spread Footings
04.4300 Stone Masonry
F/I Bluestone Sills
F/I Stone Chimney Cap
F/I Stone Veneer
F/I Stone Veneer (Plan View)
05.0050 Structural Steel
F/I Steel Beams
F/I Steel Beams Vertical
06.2000 Finish Carpentry
F/I 5/4" Window Stools [White Oak]
F/I Base Molding [White Oak]
F/I Door Casing [White Oak]
F/I Window Casing [White Oak]
I/O Exterior Door Hardware
I/O Interior Door Hardware
I/O Interior Wood Door & F/I Trim

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
I/O Pocket Door
I/O Window Hardware & Screen(s)
06.2200 Millwork
F/I Full-Height Cabinets @ Pantry
F/I Kitchen Island
F/I Lower Cabinets
F/I Lower Cabinets @ Mudroom
F/I Upper Cabinets
F/I Upper Cabinets @ Mudroom
F/I Vanities
F/I Window Seat
06.2300 Closet Interiors
F/I Closet Interiors (Hat Shelf & Rod)
F/I Closet Interiors (Linen Closet)
F/I Closet Interiors (Master WIC)
F/I Closet Interiors (WIC)
06.4001 Wood Framing Materials
F/O 1-3/4" x 11-1/4" LVL
F/O 1-3/4" x 11-7/8" LVL
F/O 1-3/4" x 16" 2.0E LVL
F/O 1-3/4" x 9-1/2" LVL
F/O 1-3/4"x14" LVL 1.9E
F/O 1-3/4"x18-0" LVL
F/O 1-3/4"x20-0" LVL
F/O 18" Pro 560 TJI (Per LF)
F/O 2x10 DF
F/O 2x12 DF
F/O 2x12 DF
F/O 2x12 DF
F/O 2x12 PT
F/O 2x4 DF
F/O 2x4 PT
F/O 2x4 Studs
F/O 2x6 DF
F/O 2x6 PT
F/O 2x6 Studs

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/O 2x8 DF
F/O 2x8 DF
F/O 3-1/2"x5"x10' PSL Post
F/O 3-1/2"x7"x10' PSL Post
F/O 4x8x1-1/2" Plywood
F/O 4x8x1/2" CDX Fir Plywood
F/O 4x8x3/4" TG Advantech Plywood
F/O 4x8x5/8" CDX Fir Plywood
F/O 4x8x5/8" R6.6 Zip Sheathing
F/O 6"x6"x12' PT Post
F/O FormSealR 5-1/2" x 50' Sill Seal
F/O Simpson ABU66Z Post Base
F/O Termite shield (6" x 25' Aluminum Roll)
06.4002 Wood Framing Labor
F/I 6X6 PT Post
F/I Timber Truss Designed By Others
I/O Deck Post
I/O Exterior Wall Framing & Sheathing @ 1st Floor
I/O Exterior Wall Framing & Sheathing @ 2nd Floor
I/O Floor Framing (Joists & Subfloor)
I/O Floor Framing (Joists & Subfloor)
I/O Interior Framed Wall
I/O Residential Exterior Door(s)
I/O Roof Framing & Sheathing
I/O Window(s) (Standard Sizes)
Wood Framing Labor For LVL'S & Posts
06.4300 Wood Stairs And Railings
F/I Paint-Grade Wood Railings (Poplar/Pine w/Square Balusters & Box Newels]
F/I White Oak Stairs w/Poplar Strings & Risers (Per Riser)
06.6600 Decking
F/I 42" Pine Treated Deck Railing
F/I Deck Stairs Open Riser (Per LF of Stair Tread)
F/I Decking
F/I Sonotube Deck Footings (Hand Dug)
F/O 1/2" X 6" Lag Bolt
F/O 2x12 PT Deck Girder

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/O 2x12 PT Deck Joists
F/O 2x8 PT (Deck Joist)
F/O 2x8 PT (Deck Outer Joist)
F/O 9" Grace Vycor Plus Deck Flashing
F/O Decking
F/O Simpson Strong Tie LU28 2x8 Deck Joist Hangers
I/O Deck Framing
07.1000 Waterproofing
F/I Foundation Waterproofing [Rub-R-Wall Membrane w/2" XPS (R-10) Foam Board Application] (Plan View)
07.2000 Insulation
F/I Sound Deadening Insulation
F/I Insulation & Air Seal @ Window(s)/Exterior Door(s)
F/I R-21 Mineral Wool
F/I R-21 Mineral Wool
F/I R-30 Mineral Wool
F/I R-49 Mineral Wool
07.3000 Roofing
F/I EPDM Roof @ 2nd Floor Covered Deck
F/I Metal Ridge Vent
F/I Standing Seam Sheet Metal Roofing
07.6600 Gutters & Leaders
F/I 5" Gutters
F/I 5" Leaders
07.9510 Siding
F/I Aluminum Fascia
F/I Band @ Siding
F/I Exterior Window Trim ($15/LF Budget)
F/I Prefinished Board N Batten Siding
F/I Prefinished James Hardie Plank Siding
F/I Prefinished James Hardie Plank Siding
F/I Tyvek Housewrap
F/I Tyvek Tape
08.1400 Wood Doors & HW
F/O Door Hardware ($150 Allowance Each)
F/O Pocket Door with Kit
F/O Solid-Core Wood Door ($1,250/Ea Allowance)

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/O Solid-Core Wood Doors (Pair) ($2,500 Allowance)
08.1600 Residential Entry Doors & HW
F/O Door 100 Residential Fiberglass Entry Door Assembly (42"x96")
F/O Door 101 Residential Fiberglass Entry Door Assembly (36"x96")
F/O Door 115 Residential Fiberglass Entry Door Assembly (36"x80"x9-1/6")
F/O Door 207 Pair Of Residential Fiberglass Entry Door Assembly (71-1/4"x82")
F/O Doors 111, 112, 113 & 114 Pair Of Residential Fiberglass Entry Door Assembly (71"x83-1/2")
F/O Doors 217 & 220 Residential Fiberglass & Glass Entry Door Assembly (36-3/8"x82")
F/O Doors 218 & 219 Residential Fiberglass Entry Door Assembly (30-3/8"x82")
F/O Fiberglass Sidelite 1'0"x8'0"
F/O Residential Entry Door Deadlock/Door Knob Combo [$250/Each Allowance Placeholder]
08.5000 Windows
F/O Type A ELDH3664 E Marvin Elevate Windows
F/O Type B ELDH3656 Marvin Elevate Windows
F/O Type C ELDHP6260 Marvin Elevate Windows
F/O Type D ELDH3636 Marvin Elevate Windows
F/O Type E ELDH5460 Marvin Elevate Windows
F/O Type F ELDH3652 Marvin Elevate Windows
F/O Type G ELDHP6272 Marvin Elevate Windows
F/O Type H ELDH3660 2W E Marvin Elevate Windows
F/O Type I ITDHP2224 Marvin Elevate Windows
F/O Type J ELDH4844 Windows
F/O Type K ELDH3660 E Marvin Elevate Windows
F/O Type L ELDH4268 2W E Marvin Elevate Windows
F/O Type M ELDHP6276 Marvin Elevate Windows
Windows
08.8500 Shower Enclosures
F/I Shower Enclosure
09.2300 Drywall & Carpentry
F/I 1/2" GWB Walls (Level 4 Finish)
F/I 5/8" GWB Ceilings (Level 4 Finish)
F/I 5/8" GWB Walls (Level 4 Finish)
I/O Bath Accessories
09.3013 Tile & Stone
F/I Floor Tile ($7/SF Material Allowance)
F/I Marble Saddle

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Mud Job at Shower
F/I Tile Backsplash ($7/SF Material Allowance) (Plan View)
F/I Wall Tile ($7/SF Material Allowance)
F/I Waterproofing for Floor Tile
F/I Waterproofing for Wall Tile
Seal Stone Tile @ Entry & Mudroom
09.6400 Wood Flooring
F/I Engineered Wood Flooring ($13/SF Material Allowance)
Stain & Seal Wood Railing
Stain & Seal Wood Stairs
09.9100 Painting
Paint Base Molding
Paint Door Casing (Per LF)
Paint Exterior PT Post
Paint GWB Ceilings
Paint GWB Walls
Paint Stringers & Risers
Paint Window Casing
Paint/Stain Wood Doors & Casing
Prime & Paint Residential Fiberglass Entry Door
10.2800 Bath Accessories
F/O Bath Accessories Budget
F/O Bath Accessories Budget
10.3100 Fireplaces
F/I Propane Fireplace
11.3100 Appliances (NIC)
F/O Dishwasher
F/O Dryer
F/O Freezer
F/O Grill
F/O Microwave Drawer
F/O Range
F/O Refrigerator
F/O Vent Hood Insert 30"
F/O Vent Hood Insert @ Outside Grill
F/O Washer

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
12.3600 Countertops
Template, Fabricate & Install Stone Countertops
Template, Fabricate & Install Stone Countertops
14.2000 Elevators
F/I Residential Elevators 950#RH Rail In-Line Opening, Millenium Gate, 12 Square Foot Elevator
22.0000 Plumbing
F/I Gas Piping & Connection for Range
F/I Hose Bib
F/I Instant Hot Water Heater (HWH)
I/O Appliance
I/O Bath Lav (Sink) & Faucet
I/O Dishwasher
I/O Freestanding Bathtub
I/O Gas Connection for Genrator
I/O Propane Gas Fireplace Connection
I/O Residential Toilet
I/O Sink & Faucet
I/O Standard Shower
22.4000 Plumbing Fixtures
F/O Free-Standing Bathtub
F/O Kitchen Faucet
F/O Kitchen Sink
F/O LAV Sink
F/O Lav Faucet
F/O Residential Toilet
F/O Standard Shower Kit
F/O Tub Filler/Faucet
23.0000 HVAC
Duct Exhaust Fan
F/I Dehumidification System @ Basement
HVAC budget
26.0000 Electric
F/I 200Amp Panel
F/I 3-Way Switch
F/I Controllers For Heat Matt
F/I Dedicated Equipment Duplex 20amp

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
F/I Duplex Receptacle
F/I Electric Heat Mat (Warmlyyours)
F/I GFI Receptacle
F/I Home Run + Arc-Fault Breaker
F/I Home Run + Standard Breaker
F/I LED Dimmer Switch
F/I LED Dimmer Switch
F/I Residential Exhaust Fan
F/I Weatherproof GFI Receptacle
F/I Weatherproof GFI Receptacle
F/I Whole House Propane Generator
I/O Lighting Fixture (Residential)
Wire Elevator Equipment
Wire Instant Hot Water Heaters
Wire Mechanical Equipment
26.5000 Lighting Fixtures
Lighting Fixture Budget
Lighting Fixture Budget
Lighting Fixture Budget
Lighting Fixture Budget
Lighting Fixture Budget
31.0000 Earthwork
2" Rigid Insulation Below Grade
Backfill & Compact
Backfill Frost Walls
Backfill Slab & Compact
Excavate Foundation (Frost Walls)
Excavate Foundation (Slab on Grade)
F/I Crushed Stone
Import of Structural Fill
Trenching, Sand and Backfill Utility Trench for Underground Utilities
31.1100 Drainage & Stormwater
Drainage & Stormwater Management
F/I 4" Footing Drain
31.2200 Grading
Rough Grading with Stockpiled Soil

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Description
31.2500 Erosion And Sedimentation Controls
F/I Silt Fence
32.1400 Hardscaping
F/I Bluestone Pavers @ Entrance Walkway
32.3200 Retaining Wall
F/I Retaining Wall

Montana Home Builders
173 North Rt. 9W
Congers, NY, 10920
(845) 398-1778

Notes and Clarifications:

1. Pricing is to be used for budgetary purposes only.
2. All work to be performed during normal working hours. Overtime is not included.
3. Pricing is based on using open shop labor.
4. Permits and fees are not included.
5. Surveying fees are not included. Montana will coordinate stakeouts.
6. Temporary heating is not included. If required, will be billed on time and material basis.
7. Pricing for foundation walls is based on heights indicated on plans. Variations in grade are not accounted for.
8. Winter additive, ground thawing and/or blankets for concrete is not included.
9. Temporary heat is not included.
10. Pricing for excavation is based on bottom of footing depths indicated on drawings. If additional excavation is required to reach virgin soil additional charges for machine time, labor, concrete, waterproofing and backfilling may be incurred.
11. Rock removal is not included.
12. Tree removal is not included.
13. Snow/ice removal is not included.
14. Dewatering is not included.
15. Removal of unsuitable soils is not included.
16. Landscaping is not included.
17. Window treatments are not included.
18. Audio/visual is not included.
19. Security is not included.
20. Gas/Propane service is not included.
21. It is assumed that we will be able tie into the existing well.
22. The existing electrical service will be utilized.
23. The exterior concrete and stone stairs are not included pending clarification.
24. We included Warmly Yours Electric Heat Matt For Tiled Areas.
25. Bookshelves are not included pending clarification. It mentions installing existing shelves in one area.
26. Demo price assumes no asbestos is present. Asbestos testing is not included.
27. Exposed timber framing is not included. Priced per the structural framing plan.

Allowances (Material Allowances Are Including Taxes and Delivery to Site)

1. Retaining walls. $18,000
2. Stormwater controls. $50,000
3. Generator supply and connections. $55,000
4. Tile per square foot. $7.00
5. Wood flooring per square foot. $13.00
6. Countertop material per square foot. $80.00
7. Decking material per square foot. $12.00