MONTANA
CONTRACTING

Construction Management | General Contracting

Montana Contracting Corp is a full service General Contractor and Construction Management Firm. We take pride in our commitment to excellence and professionalism in the Metropolitan NY and NJ commercial construction marketplace.

MONTANA
CONTRACTING

About Us

Montana Contracting Corp. is a full–service general contractor, construction manager and residential developer. With over 35 years of experience providing quality high-end residential and commercial renovations, Montana Contracting is equipped to handle simple improvements to full scale renovations including ground up projects. We offer our clients a wide variety of construction and building related services anchored by decades of proven success and reliability.

Letter from the President

From Montana's inception in 1984 our firm has grown from a family-owned and operated home builder to a diverse construction management firm building ground-up developments, corporate interiors and hospitality projects. Through our growth and success we have not forgotten the core values and ethics that Montana was founded on. At Montana Contracting, we recognize the challenges in today's marketplace and the expectations of our clientele. We believe in honesty and integrity, doing the right things for the right reasons, and treating people fairly. Each project is pursued with the sense of urgency, excellence and professionalism that our clients expect and deserve.

MONTANA
CONTRACTING

Core Values

Family First
“The homemaker has the ultimate career. All other careers exist for one purpose only – and that is to support the ultimate career.” - C.S. Lewis

Mutual Respect
"True greatness will be achieved through the abundant mind that works selflessly - with mutual respect, for mutual benefit.: - Steven Covey

Collaboration
"Individual commitment to a group effort — that is what makes a team work, a company work, a society work, a civilization work." - Vince Lombardi

Absolute Ownership
"Responsibility equals accountability equals ownership. And a sense of ownership is the most powerful weapon a team or organization can have." - Pat Summitt

Attitude
"Your living is determined not so much by what life brings to you as by the attitude you bring to life; not so much by what happens to you as by the way your mind looks at what happens." - Khalil Gibran

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Date: 05/23/2025

Brian Messana
Messana O'Rorke | Brian Messana Architect

Re: Mainbridge Commons Development

Proposal

Montana Contracting Corp. will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project for the sum of: **$29,774,289**

Attachments:
Scope of Work
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting Corp.

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 05/23/2025

Estimate: 25018 Mainbridge Commons Development

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
01 Medical Buidling	$13,330,110	44.77%	126.95
02 Sitework	$1,958,000	6.58%	18.65
03 Block 4 Three Story	$4,043,374	13.58%	38.51
04 Block 2 Three Story	$2,716,668	9.12%	25.87
05 Block 3 Two Story	$1,903,543	6.39%	18.13
06 Block 1 Two Story	$1,900,999	6.38%	18.10
Sub-Total (Direct Cost)	**$25,852,694**	**86.83%**	**246.22**
General Conditions	$1,551,162	5.21%	14.77
Fee	$1,644,231	5.52%	15.66
Insurance	$726,202	2.44%	6.92
Total Estimate	**$29,774,289**	**100%**	**283.56**

MONTANA CONTRACTING

Estimate: 25018 Mainbridge Commons Development **Date: 05/23/2025**

Estimated Costs

Description	Total Direct Cost
01 Medical Buidling	
03.1000 Concrete	1,049,168.45
04.1000 Masonry	270,185.17
05.0050 Structural Steel	3,449,985.94
05.0100 Misc. Steel	155,236.80
05.1000 Ornamental Metals	50,000.00
05.7630 Canopy Systems	76,780.00
06.2200 Millwork	74,994.25
07.1000 Foundation Waterproofing	73,946.34
07.2000 Insulation	290,632.25
07.3000 Roofing	742,335.33
07.7600 Roof Pavers	14,505.96
07.8000 Fireproofing Of Structural Steel	309,580.00
07.9510 Siding	682,602.80
08.1100 HM Doors, Frames & HW	82,080.00
08.5000 Windows	373,103.28
08.6200 Skylights	291,846.50
08.8200 Arch. Metal & Glass	732,725.30
08.8400 Glass Railings	38,490.00
09.2300 Drywall & Carpentry	1,256,703.02
09.2500 Acoustical Ceilings	40,388.53
09.3013 Tile & Stone	214,506.52
09.6000 Flooring	230,550.94
09.9100 Painting	103,908.05
10.2800 Bath Accessories	13,200.00
10.2900 Toilet Partitions	62,400.00
12.3600 Countertops	10,463.85
14.2000 Elevators	125,000.00
21.0000 Sprinkler	321,922.50

MONTANA
CONTRACTING

Description	Total Direct Cost
22.0000 Plumbing	120,800.00
22.4000 Plumbing Fixtures	38,610.00
23.0000 HVAC	655,200.00
26.0000 Electric	562,535.21
26.5000 Lighting Fixtures	179,183.40
27.1000 Tel/Data	137,801.90
28.4600 Fire Alarm	163,800.00
31.0000 Earthwork	238,137.05
31.1100 Drainage & Stormwater	33,316.65
32.1400 Hardscaping	51,050.25
32.1600 Site Concrete	0.00
32.1723 Pavement Markings	6,985.53
32.9300 Landscaping	5,448.00
01 - Medical Buidling Totals	**$13,330,109.76**
02 Sitework	
03.1000 Concrete	6,480.00
26.0000 Electric	130,832.14
26.5000 Lighting Fixtures	45,000.00
31.0000 Earthwork	80,015.95
31.1100 Drainage & Stormwater	383,719.70
32.1200 Paving	701,026.31
32.1500 Fencing	24,023.50
32.1600 Site Concrete	328,062.30
32.1723 Pavement Markings	18,693.57
32.1800 Athletic and Recreational Surfaces	64,150.90
32.3218 Athletic and Recreational Surfaces	40,579.89
32.9300 Landscaping	135,415.97
02 - Sitework Totals	**$1,958,000.24**
03 Block 4 Three Story	
03.1000 Concrete	120,550.35
06.2000 Finish Carpentry	159,392.79

MONTANA
CONTRACTING

Description	Total Direct Cost
06.4001 Wood Framing Materials	333,944.30
06.4002 Wood Framing Labor	282,335.15
07.2000 Insulation	184,137.35
07.3000 Roofing	31,744.46
07.6600 Gutters & Leaders	12,000.00
07.9510 Siding	338,533.18
08.1400 Wood Doors & HW	79,200.00
08.1600 Entry Doors & HW	23,100.00
08.5000 Windows	148,500.00
09.2300 Drywall & Carpentry	194,442.45
09.3013 Tile & Stone	93,600.00
09.6400 Wood Flooring	255,000.00
09.9100 Painting	113,922.61
10.2800 Bath Accessories	39,600.00
10.4400 Fire Protection Specialties	6,930.00
11.3100 Appliances	99,000.00
12.3600 Countertops	90,000.00
22.0000 Plumbing	360,000.00
22.4000 Plumbing Fixtures	132,660.00
23.0000 HVAC	364,500.00
26.0000 Electric	360,000.00
26.5000 Lighting Fixtures	128,700.00
28.4600 Fire Alarm	21,600.00
31.0000 Earthwork	58,710.83
31.1100 Drainage & Stormwater	11,270.60
03 - Block 4 Three Story Totals	**$4,043,374.06**
04 Block 2 Three Story	
03.1000 Concrete	82,226.40
06.2000 Finish Carpentry	106,469.34
06.4001 Wood Framing Materials	223,958.44
06.4002 Wood Framing Labor	189,519.36

MONTANA
CONTRACTING

Description	Total Direct Cost
07.2000 Insulation	123,237.48
07.3000 Roofing	21,225.05
07.6600 Gutters & Leaders	10,000.00
07.9510 Siding	238,347.43
08.1400 Wood Doors & HW	52,800.00
08.1600 Entry Doors & HW	15,400.00
08.5000 Windows	99,000.00
09.2300 Drywall & Carpentry	130,352.27
09.3013 Tile & Stone	62,400.00
09.6400 Wood Flooring	170,000.00
09.9100 Painting	76,355.76
10.2800 Bath Accessories	26,400.00
10.4400 Fire Protection Specialties	4,620.00
11.3100 Appliances	66,000.00
12.3600 Countertops	60,000.00
22.0000 Plumbing	240,000.00
22.4000 Plumbing Fixtures	88,440.00
23.0000 HVAC	243,000.00
26.0000 Electric	240,000.00
26.5000 Lighting Fixtures	85,800.00
28.4600 Fire Alarm	14,400.00
31.0000 Earthwork	38,744.80
31.1100 Drainage & Stormwater	7,971.92
04 - Block 2 Three Story Totals	**$2,716,668.24**
05 Block 3 Two Story	
03.1000 Concrete	83,410.45
06.2000 Finish Carpentry	71,682.04
06.4001 Wood Framing Materials	154,103.12
06.4002 Wood Framing Labor	132,664.89
07.2000 Insulation	93,097.28
07.3000 Roofing	20,964.52

MONTANA
CONTRACTING

Description	Total Direct Cost
07.6600 Gutters & Leaders	10,000.00
07.9510 Siding	166,345.64
08.1400 Wood Doors & HW	35,200.00
08.1600 Entry Doors & HW	15,400.00
08.5000 Windows	66,000.00
09.2300 Drywall & Carpentry	87,407.81
09.3013 Tile & Stone	41,600.00
09.6400 Wood Flooring	114,000.00
09.9100 Painting	51,549.07
10.2800 Bath Accessories	17,600.00
10.4400 Fire Protection Specialties	3,080.00
11.3100 Appliances	44,000.00
12.3600 Countertops	40,000.00
22.0000 Plumbing	160,000.00
22.4000 Plumbing Fixtures	58,960.00
23.0000 HVAC	162,000.00
26.0000 Electric	160,000.00
26.5000 Lighting Fixtures	57,200.00
28.4600 Fire Alarm	9,600.00
31.0000 Earthwork	39,352.00
31.1100 Drainage & Stormwater	8,325.68
05 - Block 3 Two Story Totals	**$1,903,542.50**
06 Block 1 Two Story	
03.1000 Concrete	83,172.45
06.2000 Finish Carpentry	71,594.11
06.4001 Wood Framing Materials	153,794.44
06.4002 Wood Framing Labor	132,403.29
07.2000 Insulation	93,022.56
07.3000 Roofing	20,991.14
07.6600 Gutters & Leaders	10,000.00
07.9510 Siding	165,367.15

MONTANA
CONTRACTING

Description	Total Direct Cost
08.1400 Wood Doors & HW	35,200.00
08.1600 Entry Doors & HW	15,400.00
08.5000 Windows	66,000.00
09.2300 Drywall & Carpentry	87,249.47
09.3013 Tile & Stone	41,600.00
09.6400 Wood Flooring	114,000.00
09.9100 Painting	51,442.39
10.2800 Bath Accessories	17,600.00
10.4400 Fire Protection Specialties	3,080.00
11.3100 Appliances	44,000.00
12.3600 Countertops	40,000.00
22.0000 Plumbing	160,000.00
22.4000 Plumbing Fixtures	58,960.00
23.0000 HVAC	162,000.00
26.0000 Electric	160,000.00
26.5000 Lighting Fixtures	57,200.00
28.4600 Fire Alarm	9,600.00
31.0000 Earthwork	39,269.85
31.1100 Drainage & Stormwater	8,052.00
06 - Block 1 Two Story Totals	**$1,900,998.85**
Totals	**$25,852,693.64**

Estimate Summary

Description	Percentage	Totals
Sub-Total (Direct Cost)		**$25,852,693.64**
General Conditions	6.00%	$1,551,161.62
Fee	6.00%	$1,644,231.32
Insurance	2.50%	$726,202.16
Sub-Total () Total		**$29,774,288.74**

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: Mainbridge Commons Development

Scope of Work

Description
03.1000 Concrete
Cast-In-Place Concrete
Concrete Pumps
F/I Concrete Fill Over Steel Decking (Installed by Steel Sub)
F/I Concrete Stair Pan Infill
Form & Pour Concrete Footings
Form & Pour Concrete Foundation Wall(s)
Form & Pour Concrete Slab. F/I All Applicable Rebar, Vapor Barrier & Mesh.
Form & Pour Pitched Concrete Slab
Form & Pour Spread Footings
Pump Truck
Reinforced Concrete Wall
04.1000 Masonry
F/I CMU Block [8"x8"x16"] @ Elevator Shaft & Stair Shafts
F/I CMU Block [8"x8"x16"] @ Garage Level Interior Walls
05.0050 Structural Steel
F/I Galvanized Steel Dunnage
F/I Metal Decking
F/I Primary Steel Beams
F/I Secondary Steel Beams
F/I Small Primary Steel Beams
F/I Steel Beams
F/I Steel Beams @ 2nd Floor
F/I Steel Beams Vertical
F/I Steel Beams Vertical @ 2nd Floor
F/I Steel Columns @ Garage Level
05.0100 Misc. Steel
F/I Elevator Pit Ladder
F/I Steel Pan Stairs & Railings
F/I Steel Stair Landings
05.1000 Ornamental Metals
F/I Steel Stair @ Reception Hall
05.7630 Canopy Systems
F/I Custom Canopy 3'6" Deep

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Custom Canopy 9'6" Deep
06.2000 Finish Carpentry
F/I Base Molding
Finish Carpentry @ 2 Story Block 1
Finish Carpentry @ 2 Story Block 3
Finish Carpentry @ 3 Story Block 2
Finish Carpentry @ 3 Story Block 4
06.2200 Millwork
F/I Full-Height Cabinets @ Brushing 204.10
F/I Full-Height Cabinets @ Dr. Elbialy's Office 203.3
F/I Full-Height Cabinets @ Hygene Lobby 202.5
F/I Full-Height Cabinets @ Staff Toilet 202.4
F/I Lower Cabinets @ Kitchenette 203.2
F/I Lower Cabinets @ Lab 203.7
F/I Plastic Laminate Counter @ Administration 203.11
F/I Plastic Laminate Open Shelf @ Administration 203.11
F/I Upper Cabinets @ Kitchenette 203.2
F/I Upper Cabinets @ Lab 203.7
F/I Vanities
06.4001 Wood Framing Materials
F/O 2x10 DF
F/O 2x6 DF
F/O 2x6 PT
F/O 2x6 Studs
F/O 2x8 DF
F/O 4x8x1/2" CDX Fir Plywood
F/O 4x8x3/4" TG Advantech Plywood
F/O 4x8x5/8" CDX Fir Plywood
F/O FormSealR 5-1/2" x 50' Sill Seal
F/O Termite shield (6" x 25' Aluminum Roll)
F/O Wood Framing Materials @ 2 Story Block 1
F/O Wood Framing Materials @ 2 Story Block 3
F/O Wood Framing Materials @ 3 Story Block 2
F/O Wood Framing Materials @ 3 Story Block 4
06.4002 Wood Framing Labor
I/O Exterior Wall Framing & Sheathing @ 1st Floor

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
I/O Exterior Wall Framing & Sheathing @ 2nd Floor
I/O Floor Framing (Joists & Subfloor)
I/O Roof Framing & Sheathing
Wood Framing Labor @ 2 Story Block 1
Wood Framing Labor @ 2 Story Block 3
Wood Framing Labor @ 3 Story Block 2
Wood Framing Labor @ 3 Story Block 4
07.1000 Foundation Waterproofing
F/I Foundation Waterproofing [Rub-R-Wall Membrane w/2" XPS (R-10) Foam Board Application]
07.2000 Insulation
F/I Insulation @ 2 Story Block 1
F/I Insulation @ 2 Story Block 3
F/I Insulation @ 3 Story Block 2
F/I Insulation @ 3 Story Block 4
F/I R-21 Fiberglass Batt
F/I R-49 Spray-Foam
07.3000 Roofing
F/I 3-Tab Asphalt Roof Shingles + Ice & Water Shield/Drip Edge & Ridge Cap
F/I Balcony Waterproofing Membrane Roofing
F/I EPDM Roof
F/I EPDM Roof at Parapet Walls
F/I Standing Seam Sheet Metal Roofing
F/I Waterproofing Membrane Roofing @ Court Yard Areas Above Parking Garage
07.6600 Gutters & Leaders
F/I Gutters & Leaders @ 2 Story Block 1
F/I Gutters & Leaders @ 2 Story Block 3
F/I Gutters & Leaders @ 3 Story Block 2
F/I Gutters & Leaders @ 3 Story Block 4
07.7600 Roof Pavers
F/I Roof Pavers
07.8000 Fireproofing Of Structural Steel
F/I Fireproof Underside Of Decks & Beams
07.9510 Siding
F/I Siding @ 2 Story Block 3
F/I Siding @ 3 Story Block 2
F/I Siding ($11/SF Budget)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Siding @ 2 Story Block 1
F/I Siding @ 3 Story Block 4
F/I Tyvek Housewrap
F/I Tyvek Tape
Tyvek Tape
08.1100 HM Doors, Frames & HW
F/O Door Hardware
F/O Door Hardware
F/O HM Door
F/O HM Frame (Single)
F/O Solid-Core Wood Door
08.1400 Wood Doors & HW
F/O Pre-Hung Wood Doors @ 2 Story Block 1
F/O Pre-Hung Wood Doors @ 2 Story Block 3
F/O Pre-Hung Wood Doors @ 3 Story Block 2
F/O Pre-Hung Wood Doors @ 3 Story Block 4
08.1600 Entry Doors & HW
F/O Entry Doors @ 2 Story Block 1
F/O Entry Doors @ 2 Story Block 3
F/O Entry Doors @ 3 Story Block 2
F/O Entry Doors @ 3 Story Block 4
08.5000 Windows
F/O Windows @ 2 Story Block 3
F/O Windows @ 3 Story Block 1
F/O Windows @ 3 Story Block 2
F/O Windows @ 3 Story Block 4
F/O Windows @ Medical Buidling
F/O Windows@ Medical Buidling
08.6200 Skylights
F/O Round Skylights @ Elevator & Stair Shafts
F/O Skylights @ Sloping Roofs
F/O Walkable Skylights @ Garage Ceiling/Courtyard
08.8200 Arch. Metal & Glass
F/I Exterior Glass Storefront System
F/I Exterior Glass Storefront System @ 2nd Floor
F/I Exterior Storefront Door & HW

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Exterior Storefront Door & HW
F/I Interior Storefront @ 1st Floor
F/I Interior Storefront @ 1st Floor
F/I Interior Storefront @ 2nd Floor
F/I Interior Storefront @ 2nd Floor
08.8400 Glass Railings
F/I Glass Railings (With Posts Every 4') @ Balcony & Terrace
09.2300 Drywall & Carpentry
Drywall & Carpentry @ 2 Story Block 1
Drywall & Carpentry @ 2 Story Block 3
Drywall & Carpentry @ 3 Story Block 2
Drywall & Carpentry @ 3 Story Block 4
F/I 3-5/8" Metal Stud Framing
F/I 3-5/8" Metal Stud Soffit Framing
F/I 5/8" Densglass Sheathing
F/I 5/8" GWB Ceilings
F/I 5/8" GWB Soffit Fascia
F/I 5/8" GWB Walls
F/I 5/8" Lead-Lined GWB @ 2nd Floor
F/I 6" Metal Stud Framing
F/I 6" Mineral Wool Insulation
F/I Blanket Insulation
F/I Firestop Sealant
F/I Hung GWB Ceilings
F/I Hung GWB Ceilings 2 Layers GWB
F/I Weather-Resistive Barrier (WRB)
I/O Bath Accessories
I/O Exterior HM Door, Frame & HW (Single)
I/O Interior HM Door, Frame & HW (Single)
I/O Round Skylights
I/O Windows
09.2500 Acoustical Ceilings
F/I ACT Ceilings @ 2nd Floor
09.3013 Tile & Stone
F/I Floor Tile ($7/SF Material Allowance)
F/I Tile Wall Base ($7/LF Material Allowance)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Wall Tile ($7/SF Material Allowance) @ 2nd Floor
F/I Wall Tile ($7/SF Material Allowance)
F/I Waterproofing for Floor Tile
F/I Waterproofing for Wall Tile
Tile & Stone @ 2 Story Block 1
Tile & Stone @ 2 Story Block 3
Tile & Stone @ 3 Story Block 2
Tile & Stone @ 3 Story Block 4
09.6000 Flooring
F/I 4" Vinyl Base
F/I Carpet Tile @ 2nd Floor
F/I LVT (Luxury Vinyl Tile) Flooring @ 1st Floor
F/I LVT (Luxury Vinyl Tile) Flooring @ 2nd Floor
09.6400 Wood Flooring
F/I Engineered Wood Flooring ($13/SF Material Allowance) @ 2 Story Block 1
F/I Engineered Wood Flooring ($13/SF Material Allowance) @ 2 Story Block 3
F/I Engineered Wood Flooring ($13/SF Material Allowance) @ 3 Story Block 2
F/I Engineered Wood Flooring ($13/SF Material Allowance) @ 3 Story Block 4
09.9100 Painting
Paint Base Molding
Paint GWB Ceilings
Paint GWB Soffit Fascia
Paint GWB Walls
Paint HM Door & Frame (Single)
Paint/Stain Wood Door + HM Frame (Single)
Painting @ 2 Story Block 1
Painting @ 2 Story Block 3
Painting @ 3 Story Block 2
Painting @ 3 Story Block 4
10.2800 Bath Accessories
F/O Bath Accessories
F/O Bath Accessories @ 2 Story Block 1
F/O Bath Accessories @ 2 Story Block 3
F/O Bath Accessories @ 3 Story Block 2
F/O Bath Accessories @ 3 Story Block 4
10.2900 Toilet Partitions

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
F/I Toilet Partitions @ 1st Floor
F/I Toilet Partitions @ 2nd Floor
10.4400 Fire Protection Specialties
F/O Fire Extinguisher Cabinet + FE @ 2 Story Block 1
F/O Fire Extinguisher Cabinet + FE @ 2 Story Block 3
F/O Fire Extinguisher Cabinet + FE @ 3 Story Block 2
F/O Fire Extinguisher Cabinet + FE @ 3 Story Block 4
11.3100 Appliances
F/I Appliances @ 2 Story Block 1
F/I Appliances @ 2 Story Block 3
F/I Appliances @ 3 Story Block 2
F/I Appliances @ 3 Story Block 4
12.3600 Countertops
Template, Fabricate & Install Solid Surface Countertops ($50/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops ($50/SF Material Allowance) @ 2 Story Block 3
Template, Fabricate & Install Solid Surface Countertops ($50/SF Material Allowance) @ 3 Story Block 1
Template, Fabricate & Install Solid Surface Countertops ($50/SF Material Allowance) @ 3 Story Block 2
Template, Fabricate & Install Solid Surface Countertops ($50/SF Material Allowance) @ 3 Story Block 4
Template, Fabricate & Install Solid Surface Countertops @ Bathrooms 1st Floor ($50/SF Material Allowance)
Template, Fabricate & Install Solid Surface Countertops @ Brushing Room 204.10 ($50/SF Material Allowance)
14.2000 Elevators
F/I 3-Stop Elevator
21.0000 Sprinkler
F/I Dry Sprinkler Equipment
F/I New Sprinkler Heads
Sprinkler Permits, Filing, Inspections, Signoff & Hydrostatic Testing
Sprinkler Pumps And Risers
Sprinkler Shop Drawings
22.0000 Plumbing
F/I Elevator Pit Sump Pump
F/I Plumbing Mains And Risers @ Medical Building
I/O Bath Lav (Sink) & Faucet
I/O Commercial Toilet
I/O Exam Room Sink & Faucet
I/O Wall-Mounted Urinal (Including Rough-In)
Plumbing @ 2 Story Block 1

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
Plumbing @ 2 Story Block 3
Plumbing @ 3 Story Block 2
Plumbing @ 3 Story Block 4
22.4000 Plumbing Fixtures
F/O Commercial Floor-Mounted Toilet + Flushometer
F/O Exam Room Sink & Faucet
F/O LAV Sink
F/O Lav Faucet
F/O Plumbing Fixtures @ 2 Story Block 1
F/O Plumbing Fixtures @ 2 Story Block 3
F/O Plumbing Fixtures @ 3 Story Block 2
F/O Plumbing Fixtures @ 3 Story Block 4
F/O Wall-Mounted Urinal
23.0000 HVAC
HVAC Budget 1st & 2nd Floor
HVAC Budget @ 2 Story Block 3
HVAC Budget @ 3 Story Block 1
HVAC Budget @ 3 Story Block 2
HVAC Budget @ 3 Story Block 4
26.0000 Electric
Electric @ 2 Story Block 1
Electric @ 2 Story Block 3
Electric @ 3 Story Block 2
Electric @ 3 Story Block 4
Electric Power Budget @ 1st Floor
Electric Power Budget @ 2nd Floor
Electric Power Budget @ Parking Garage
F/O (3) 500 kcmil Aluminum Conductors + (1) #2 Ground
F/O 2" Conduit for Internet Provider
F/O 2" Conduit for Underground Electrical Service (Schedule 40 PVC)
F/O Terminations and Connections for 400 Amp Service
I/O 2" Conduit for Underground Electrical Service
I/O Emergency & Exit Lighint Fixture Budget
I/O Lighting Fixture
I/O Linear Lighting Fixture
I/O Underground Conduit for Internet Service (By Others)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
I/O Wire for 400 Amp Underground Electrical Service
Primary Service Up Pole
Site Electric
Underground Electrical Service Inspection
26.5000 Lighting Fixtures
F/O Emergency & Exit Lighting Fixture Budget
F/O Exterior Lighting Fixtures (Parking Lot)
F/O LED Linear Lights
F/O Lighting Fixtures
F/O Lighting Fixtures @ 2 Story Block 1
F/O Lighting Fixtures @ 2 Story Block 3
F/O Lighting Fixtures @ 3 Story Block 2
F/O Lighting Fixtures @ 3 Story Block 4
F/O Undercabinet Lighting LED Tape @ 2nd Floor
27.1000 Tel/Data
Low-Voltage Budget @ 1st Floor
Low-Voltage Budget @ 2nd Floor
28.4600 Fire Alarm
Fire Alarm Budget @ 2 Story Block 1
Fire Alarm Budget @ 2 Story Block 3
Fire Alarm Budget @ 3 Story Block 2
Fire Alarm Budget @ 3 Story Block 4
Fire Alarm Budget @ Medical Building
31.0000 Earthwork
2" Rigid Insulation Below Grade
Backfill Frost Walls
Backfill Slab & Compact
Backfill Slab & Compact
Excavate Foundation (Frost Walls)
Excavate Foundation (Slab on Grade)
Excavate Foundation (Slab on Grade)
F/I Crushed Stone
Remove Soil From Site
Respread Topsoil
Strip Topsoil and Stockpile on Site for Later Use
Trenching, Sand and Backfill Utility Trench for Underground Electric (2' Deep w/1' Sand)

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
31.1100 Drainage & Stormwater
F/I 4" Footing Drain
F/I Drainage & Stormwater @ Parking Lot
F/I Trench Drains Set in Concrete (Per LF)
Water Catchment Basin
32.1200 Paving
F/I 2" Top Course (Mix I-4/I-5)
F/I 6" Base Course (Two 3" Lifts)
F/I 8" Subbase
32.1400 Hardscaping
F/I Exterior Pavers
32.1500 Fencing
F/I Chain-Link Fencing
F/I Chain-Link Fencing @ Trash Enclosure
32.1600 Site Concrete
Excavate & Backfill for Dumpster Enclosure
F/I 4" Sidewalk w/6"Aggregate Base
F/I Concrete Curb (6” Wide @ Top & 8-1/4” @ Bottom) (Includes Excavation)
F/I Concrete Curb @ Courtyard (6” Wide @ Top & 8-1/4” @ Bottom) (Includes Excavation)
32.1723 Pavement Markings
Basic Striping (4” standard yellow/white lines, water-based paint)
Basic Striping @ Parking Garage
32.1800 Athletic and Recreational Surfaces
Basketball Court Budget
Paint Lines On Junior Basketball Court
Playground Budget
32.3218 Athletic and Recreational Surfaces
F/I Playground Surface
32.9300 Landscaping
F/I 2'-3' Tree
F/I 6'-7' Tree
F/I Large Trees
F/I Planting Soil @ Courtyard
Seeding

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

Scope of Work

Assumptions:

- **General**
  1. The residential buildings are to be wood framed.
  2. Blocks 1 and 3 are estimated as 8 separate residences each.
  3. Block 2 is estimated as 12 separate residences.
  4. Block 4 is estimated as 18 separate residences.
  5. Each residence will have 2 bathrooms.
- **Concrete**
  1. The main medical building foundation is concrete as well as concrete infill on metal decking at each floor.
  2. The residential units have concrete frost walls, footings, and slab on grade. No Basements.
- **Masonry**
  1. Parking garage walls, elevator shaft, and round stair shafts are included as CMU.
- **Structural Steel**
  1. The main medical building is figured as a steel structure with metal decking.
  2. Galvanized steel dunnage for HVAC equipment on the roof of the medical building.
- **Misc. Steel**
  1. Steel stairs and landings are figured for the medical building stair shafts.
- **Ornamental Metals**
  1. The open stairs at the reception hall.
- **Canopy Systems**
  1. Custom canopies @ medical building entrances.
- **Insulation**
  1. R-49 spray foam will be applied to all roof structures.
  2. The medical building will have 6" mineral wool insulation at all exterior walls.
  3. The residential structures will have R-21 fiberglass batt insulation.
- **Roofing**
  1. The medical building will have a combination of EPDM and standing seam metal roofing.
  2. The residential unit roofing will be 3-tab asphalt roof shingles.
- **Roof Pavers**
  1. The second floor balcony of the medical building will have pavers on pedestals over a waterproofing membrane.
- **Siding**
  1. Prefinished fiber cement siding is included for all structures.
- **HM Doors, Frames, & HW**
  1. The doors and frames in the medical building will be hollow metal.
- **Wood Doors & Hardware**
  1. All interior doors in the residential building will be pre-hung wood doors.
- **Entry Doors & Hardware**
  1. Wood and glass entry doors will be installed for each residential building.
- **Glass Railings**
  1. The second floor balcony of the medical building will have glass railings.
- **Drywall & Carpentry**
  1. All GWB walls will receive level 4 finish.
  2. All walls in the medical building will be metal framed.
  3. 5/8" GWB is included throughout.
  4. Lead lined GWB where indicated.
  5. Exterior sheathing on the medical building will be 5/8" Densglass
- **Flooring**
  1. The floors in the medical spaces are LVT and Carpet Tile

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778

- **Wood Flooring**
    1. The residential buildings will have wood flooring throughout.
- **HVAC**
    1. Forced air heating and cooling is budgeted in all buildings.
- **Fire Alarm**
    1. A fully functioning central fire alarm system is included for the medical building.
    2. Local hardwired smoke and carbon detectors throughout the residential buildings.