Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Date: 10/07/2025

Jake Kramer
Kramer Construction & Management Inc.
1615 Barclay Boulvard
Buffalo Grove, IL 60089

Re: Urban Air Lake Grove

Proposal

Montana Contracting Corp. will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project based on plans dated for the sum of: **$166,814**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Steve Catalanotto
Montana Contracting Corp.

Accepted By: _____
Date of Acceptance: _____

MONTANA CONTRACTING

Status: Active Estimates
Contact:
Date: 10/07/2025

Estimate: 52051 Urban Air Lake Grove

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/Unit
03 Concrete			
03.3500 Polished/Sealed Concrete	$16,883	10.12%	
06 Wood , Plastic and Composites			
06.2000 Finish Carpentry	$4,788	2.87%	
06.2200 Millwork	$3,785	2.27%	
08 Openings			
08.1400 Wood Doors & HW	$5,040	3.02%	
09 Finishes			
09.2300 Drywall & Carpentry	$32,900	19.72%	
09.2500 Acoustical Ceilings	$4,459	2.67%	
09.6000 Flooring	$7,396	4.43%	
09.6700 Fluid-Applied Flooring	$6,952	4.17%	
09.9100 Painting	$14,399	8.63%	
26 Electrical			
26.0000 Electric	$14,070	8.43%	
26.5000 Lighting Fixtures	$19,085	11.44%	
27 Communications			
27.1000 Tel/Data	$4,253	2.55%	
27.1020 Audio Visual	$504	0.30%	
Sub-Total (Direct Cost)	**$134,515**	**80.64%**	
General Conditions	$16,142	9.68%	
Overhead & Profit	$11,299	6.77%	
Insurance	$4,859	2.91%	
Total Estimate	**$166,814**	**100%**	

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Estimate Description: Urban Air Lake Grove

Scope of Work

Description
03.3500 Polished/Sealed Concrete
Polished Concrete
06.2000 Finish Carpentry
F/I Door Casing
I/O Interior Door Hardware
I/O Interior Wood Door & F/I Trim
06.2200 Millwork
F/I Control Room Desk (Basic - Laminate Panels/Countertop)
08.1400 Wood Doors & HW
F/O 36"X48" Solid-Core Wood Door ($800/Ea Allowance)
F/O 36"X84" Solid-Core Wood Door ($1800/Ea Allowance)
F/O Door Hardware ($150 Allowance Each)
09.2300 Drywall & Carpentry
F/I 1/2" Plywood Walls
F/I 3-5/8" Metal Stud Framing
F/I 3-5/8" Metal Stud Soffit Framing
F/I 5/8" GWB Soffit Fascia
F/I 5/8" GWB Walls (Level 4 Finish)
F/I Acoustical Sealant
F/I Blanket Insulation
I/O Briefing TV
I/O Rules Board
I/O Scoreboard TV Ceiling Mounted
I/O Vesting Room Laser Tag Equipment Storage Mounts
Skim Coat (Level 5) Finish at GWB Walls
09.2500 Acoustical Ceilings
F/I ACT Ceilings ($2.50/SF Material Budget)
F/I ACT Standard Grid ($1.50/SF Material Allowance)
09.6000 Flooring
F/I Broadloom Carpet With Padding
F/I Vinyl Cove Base
Standard Floor Prep
09.6700 Fluid-Applied Flooring
Seal Concrete Non Skid Epoxy Sealant [Light Gray]

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Description
09.9100 Painting
Paint Exposed Ceiling Black Including All Conduit & Exposed MEPS
Paint GWB Soffit Fascia
Paint GWB Walls
Paint GWB Walls
Paint/Stain Wood Doors & Casing
26.0000 Electric
F/I Ceiling Mounted Quad Receptacle
F/I Duplex Receptacle
F/I LED Dimmer Switch
F/I Quad Receptacle
F/I Single-Pole Switch
I/O Lighting Fixture
I/O Lighting Fixture Suspended From Slab Above
26.5000 Lighting Fixtures
F/O 1x4 White Lighting Fixture With 2 Lamps [Wildfire Ultrablade 48" Dual Lamp]
F/O LED Black Light Lighting Fixture [Wildfire Sablelux BLB Lamps 48"]
F/O Recessed Lighting Fixture ($125/Each Budget)
27.1000 Tel/Data
F/I Tel/Data Outlet
27.1020 Audio Visual
F/I Backbox & Conduit From Control Room To Speakers

Montana Contracting Corp.
173 North Route 9W
Congers, NY, 10920
(845) 398-1778
Company License: H-011193

Notes and Clarifications:

1. Pricing is valid for thirty (30) business days.
2. Pricing is based on using open shop labor on straight time only.
3. Permit fees are not included.
4. Asbestos testing/abatement are not included.
5. Tax is not included. It is assumed that a capital improvement certificate will be provided prior to the start of construction.
6. Temporary heating/cooling is not included.
7. Special inspections are not included.
8. Snow removal is not included.
9. We have included a broom-swept clean and debris removal from work areas; professional cleaning, including window washing, floor scrubbing, and final turnover cleaning, is excluded and to be provided by others.
10. Computers & sound equipment are not included.
11. Fire alarm & sprinkler work is not shown and is not included.
12. No HVAC work is included.
13. We have included up to 160 square feet of level 5 finish for mural walls. All other GWB walls to be level 4.
14. Center prop, bases, and energy gates are not included.
15. We have included a budget for ACT ceilings in the control and staging area. The laser tag area will be exposed ceiling painted black.
16. Slab to slab height is assumed 14'9".