Bluewater Builders LLC
485 Van Cortlandt Park
Yonkers, NY, 10705
(917) 902-5847

Date: 09/08/2024

Client Name
Client Company
Client Address Line 1
New York, NY 10010

Re: Sample Estimate - NYC Amenity & Corridors

Proposal

Bluewater Builders LLC will furnish all necessary supervision, labor, materials and equipment to build the above-referenced project based on plans dated 06/24/2024 for the sum of: **$459,208**

Attachments:
Schedule of Values
Notes and Clarifications

All work will be done in a professional and workman-like manner, licensed as required by law. All work to be fully covered with compensation and liability insurances.

Thank you for the opportunity.

Very truly yours,

Matt Nicosia
Bluewater Builders LLC

Accepted By: _____
Date of Acceptance: _____

Blue Water Construction Advisors

Status: Active Estimates
Contact:
Date: 09/08/2024

Estimate: 98765 Sample Estimate - NYC Amenity & Corridors

Estimate Cost Totals

Description	Total	Percent of Cost	Cost/SF
02 Existing Conditions			
02.0500 Protection	$20,932	4.56%	11.30
02.1000 Demolition	$21,216	4.62%	11.46
05 Metal			
05.0050 Structural Steel (Budget)	$5,000	1.09%	2.70
06 Wood , Plastic and Composites			
06.2200 Millwork	$136,150	29.65%	73.51
08 Openings			
08.8300 Mirrors	$1,046	0.23%	0.56
09 Finishes			
09.2300 Drywall & Carpentry	$1,000	0.22%	0.54
09.3013 Tile & Stone	$80,863	17.61%	43.66
09.6000 Flooring	$3,319	0.72%	1.79
09.7200 Wall Coverings	$9,705	2.11%	5.24
09.9100 Painting	$38,076	8.29%	20.56
10 Specialties			
10.1400 Signage	$5,200	1.13%	2.81
12 Furnishing			
12.5800 Bench	$1,109	0.24%	0.60
26 Electrical			
26.0000 Electric	$12,400	2.70%	6.70
26.5000 Lighting Fixtures	$7,463	1.63%	4.03
Sub-Total ()	**$343,477**	**74.80%**	**185.46**
General Conditions	$61,826	13.46%	33.38
Fee	$40,530	8.83%	21.88
Insurance	$13,375	2.91%	7.22
Total Estimate	**$459,208**	**100%**	**247.95**

Status: Active Estimates
Contact:
Date: 09/08/2024

Estimate: 98765 Sample Estimate - NYC Amenity & Corridors

Estimate Totals

Description	Total Estimate	Job %	Cost/SF
01 Lobby	$314,287	68.44%	169.70
02 Corridor	$40,554	8.83%	21.90
03 Cellar Hallway	$104,367	22.73%	56.35
Total Estimate	**$459,208**	**100%**	**247.95**

Bluewater Builders LLC
485 Van Cortlandt Park
Yonkers, NY, 10705
(917) 902-5847

Notes and Clarifications:

1. Pricing is to be used for budgetary purposes only.
2. All work to be performed on straight time using open shop labor.
3. Permits and fees are not included.
4. Owner to provide builder's risk (all risk) insurance and be responsible for paying all deductibles.
5. Asbestos Testing & Abatement are not included.
6. We have included skim coating at all wall-covering locations.
7. Work in stairwells is not included.
8. We have included a $20,000.00 allowance for tenant protection in the Lobby.
9. Pricing for electric is based on the following:
    1. Lobby
        1. Disconnect and Safe-Off Existing Electric Prior to Demolition.
        2. F/I One (1) New Pendant (3 Separate Lights). Channel ceilings and patch as needed to wire.
        3. F/I One (1) H-1 Wall-Mounted Lighting Fixture.
        4. Existing Switching to Remain.
    2. Corridor:
        1. Disconnect and Safe-Off Existing Electric Prior to Demolition.
        2. F/I Two (2) H-1 Wall-Mounted Lighting Fixtures
        3. Existing Switching to Remain.
    3. Cellar Hallway
        1. Disconnect and Safe-Off Existing Electric Prior to Demolition.
        2. F/I Eleven (11) H-1 Lighting Fixtures