Estimate: 24004801 Emblem Health Rev. 1

Estimate Unit Costs

Line	Description	Quantity	Unit Cost	Total
1	**01 General Requirements**			
2	**01.0050 General Requirements**			
3	Clean And Polish Window Frames	9.00 EA	150.00	1,350.00
4			**General Requirements Total**	**$1,350.00**
5			**General Requirements Total**	**$1,350.00**
6	**03 Concrete**			
7	**03.3370 Concrete Topping**			
8	F/I Self-Leveling at Existing Slab	12,088.65 SF	4.00	48,354.60
9			**Concrete Topping Total**	**$48,354.60**
10			**Concrete Total**	**$48,354.60**
11	**06 Wood , Plastic and Composites**			
12	**06.2200 Millwork**			
13	F/I Millwork Behind Registration Desk	24.07 LF	350.00	8,424.50
14	F/I Registration Desk	32.11 LF	700.00	22,477.00
15	F/I Reception Desk Front Section	19.15 LF	650.00	12,447.50
16	F/I Reception Desk Back Section	13.48 LF	500.00	6,740.00
17	F/I 12"x60" Plastic Laminate Shelf On Standards And Brackets	1.00 EA	400.00	400.00
18	F/I Angled Panel At Exam Room Sinks [ML-1]	8.00 EA	800.00	6,400.00
19	F/I 12" Plastic Laminate Shelf On H.D. Standards & H.D. Brackets	2.00 EA	400.00	800.00
20	F/I Millwork Panel Above Upper Cabinets [ML-1]	122.66 SF	100.00	12,266.00
21	F/I Millwork Panel Above Upper Cabinets [PL-3]	45.25 SF	100.00	4,525.00
22	F/I Wood Fascia Above Upper Cabinets [ML-1]	97.28 SF	100.00	9,728.00
23	F/I Upper Cabinets [ML-1]	98.74 LF	600.00	59,244.00
24	F/I Upper Cabinets [PL-3]	36.60 LF	600.00	21,960.00
25	F/I Upper Cabinets [ML-1]	77.57 LF	500.00	38,785.00
26	F/I Lower Cabinets [PL-3]	39.80 LF	750.00	29,850.00
27	F/I Lower Cabinets [ML-1]	160.10 LF	750.00	120,075.00
28			**Millwork Total**	**$354,122.00**
29			**Wood , Plastic and Composites Total**	**$354,122.00**
30	**07 Thermal and Moisture Protection**			
31	**07.8400 Firestopping**			
32	Firestopping @ All New And Existing Fire Rated Assemblies	181.19 LF	25.00	4,529.75
33			**Firestopping Total**	**$4,529.75**
34			**Thermal and Moisture Protection Total**	**$4,529.75**
35	**08 Openings**			
36	**08.1100 Doors, Frames & HW**			
37	HM Frame (Single)	31.00 EA	325.00	10,075.00
38	HM Frame (Pair)	3.00 EA	375.00	1,125.00
39	HM Door	5.00 EA	350.00	1,750.00
40	Solid-Core Wood Door	38.00 EA	550.00	20,900.00
41	Door Hardware Set K-1	3.00 EA	1,075.00	3,225.00

Line	Description	Quantity	Unit Cost	Total
42	Door Hardware Set 0-2	7.00 EA	1,075.00	7,525.00
43	Door Hardware Set C-3	4.00 EA	1,075.00	4,300.00
44	Door Hardware Set O-1	2.00 EA	1,075.00	2,150.00
45	Door Hardware [Not Specified]	2.00 EA	1,500.00	3,000.00
46	Door Hardware Set H-1	13.00 EA	1,075.00	13,975.00
47	Door Hardware Set K-20	6.00 EA	1,075.00	6,450.00
48	Door Hardware Set O-2	1.00 EA	1,075.00	1,075.00
49	Door Hardware Set H-1	2.00 EA	1,075.00	2,150.00
50	Door Hardware Set G-1	2.00 EA	1,075.00	2,150.00
51	F/O Door Hardware (Commercial Exterior)	1.00 EA	1,075.00	1,075.00
52			**Doors, Frames & HW Total**	**$80,925.00**
53	**08.8200 Arch. Metal & Glass**			
54	Private Office Metal And Glass Wall And Door System By Dirtt	164.48 SF	105.00	17,270.40
55	Passage Door Metal And Glass Wall System By Dirtt [With Wood Doors Included In Doors Frames & Hardware]	211.20 SF	105.00	22,176.00
56			**Arch. Metal & Glass Total**	**$39,446.40**
57			**Openings Total**	**$120,371.40**
58	**09 Finishes**			
59	**09.2300 Drywall & Carpentry**			
60	Trimmed Opening	2.00 EA	200.00	400.00
61	F/I GWB Window Openings With GWB	15.00 EA	200.00	3,000.00
62	Finish Window Returns With GWB	12.00 EA	200.00	2,400.00
63	Finish Underside Of Return Air Shaft-Way Above	1.00 EA	500.00	500.00
64	F/I End-Cap At The Wall End With Compressible Filler Where Partitions Meet Windows	6.00 EA	250.00	1,500.00
65	Install New Door Hardware At Existing Door	1.00 EA	150.00	150.00
66	F/I 5/8" GWB Walls	36,740.53 SF	3.00	110,221.59
67	F/I 5/8" GWB Ceilings	175.83 SF	3.00	527.49
68	Wood Blocking	1,049.90 LF	15.00	15,748.50
69	Wood Blocking And Soffit To Support Mecho Shades	195.56 LF	50.00	9,778.00
70	Blanket Insulation	11,533.89 SF	1.50	17,300.83
71	F/I Blanket Insulation	7,072.49 SF	2.00	14,144.98
72	3" SAFB Insulation 2' Along Walls Of Exam Rooms And Talking Rooms	1,561.96 SF	1.26	1,968.07
73	Plywood Panel on Wall for Electrical/Low-Voltage Equipment	3.00 EA	250.00	750.00
74	Install Bath Accessories	4.00 BATH	600.00	2,400.00
75	Install Fire Extinguisher Cabinet	5.00 EA	200.00	1,000.00
76	Install Interior Door, Frame & HW	40.00 EA	250.00	10,000.00
77	I/O Interior Door, Frame & HW	3.00 EA	250.00	750.00
78	F/I 3-5/8" Metal Stud Framing	26,921.47 SF	5.25	141,337.73
79			**Drywall & Carpentry Total**	**$333,877.19**
80	**09.2500 Acoustical Ceilings**			

Line	Description	Quantity	Unit Cost	Total
81	ACT-4 Ceilings [Armstrong Lyra Concealed 8434, 30"x30"x7/8", Grid Concealed 15/16" Quick Kerf Edge, White, Wall Trim & Sprinkler Cap To Be White]	1,940.80 SF	18.00	34,934.40
82	ACT 2 Ceilings [Armstrong Ultima Health Tegular 3/4" Thick 24x24 and 12x24, Grid 9/16" Suprafine XL, Wall Trim Lay-In Shadow]	895.36 SF	18.00	16,116.48
83	ACT -1 Ceilings [Armstrong Ultima Tegular 1" Thick 24x24 and 12x24, Grid 9/16" Suprafine XL, Wall Trim Lay-In Shadow]	7,955.19 SF	18.00	143,193.42
84			**Acoustical Ceilings Total**	**$194,244.30**
85	**09.3013 Tile & Stone**			
86	PT-1B [Mosa Collection:Terra, 6" x12", Color: 215 Grey Green, Grout: Laticrete Unsanded 45 Raven]	85.60 LF	25.50	2,182.80
87	PT-1 Floor Tile [Mosa Terra Tones - 215 X Y ZV 24"x24"x1/2" Color: 215 Grey Green, Grout: Laticrete Unsanded 45 Raven]	725.96 SF	31.50	22,867.80
88	PT-2 Wall Tile [Nemo, Volcanic Porcelain Collection 316 SP015030 Color: Bianco Naturale, 12"x24", Matte, Grout: Laticrete Unsanded 78 Sterling Silver]	1,662.67 SF	31.50	52,374.15
89	RS-2 Schluter Schiene [Brushed Stainless]	11.91 LF	9.00	107.19
90	Waterproofing for Tile	377.88 SF	5.25	1,983.87
91			**Tile & Stone Total**	**$79,515.81**
92	**09.6000 Flooring**			
93	F/I RB-1 4" Vinyl Cove Base[Tarkett Johnsonite Finishing Boarders 178 Ironstone CG	2,609.61 LF	3.50	9,133.64
94	RB-2 Tarkett Johnsonite 4" Rubber Cove Base [Traditional Straight, Color 178 Ironstone CG]	749.41 LF	7.00	5,245.87
95	F/I RF-1 Forbo [Marmoleum Real 3146 Serene Grey] Sheet-Vinyl Flooring (Add $4/LF for Welded Seams)	7,815.03 SF	13.75	107,456.66
96	C-1 Carpet Tile [JJ Invision Kinetex Strata 1826 18"x36"]	73.83 SY	60.00	4,429.80
97	C-2 Carpet Tile [JJ Invision Kinetex Strata 1826, 18"X36", 1853 Volcanic]	291.22 SY	60.00	17,473.20
98	RS-1 Tarkett Slim Line Transitions [1/4" Tappering To 1/8" STC-178-C, 178 Ironstone CG]	31.24 LF	9.00	281.16
99	RS-4 Tarkett Vinyl Transition Strip [CRS-178-A Or CRS-178-B, 178 Ironstone CG]	37.09 LF	9.00	333.81
100	RS-X Transition Strip [Unspecified]	6.29 LF	9.00	56.61
101			**Flooring Total**	**$144,410.75**
102	**09.7200 Wall Coverings**			
103	WC-2 Wallcovering [Carnegie, Xorel Meteor 6427, 52" Wide, Color 727 Red]	7.80 SY	98.00	764.40
104	WC-1 Wallcovering [Carnegie, Xorel Nexus 64251, 52" Wide, Color W901]	35.61 SY	98.00	3,489.70
105			**Wall Coverings Total**	**$4,254.10**
106	**09.9100 Painting**			
107	Paint GWB Walls	28,425.78 SF	1.30	36,953.52
108	Paint Existing GWB Walls	2,784.98 SF	1.30	3,620.47
109	Paint/Stain New Doors & Frames	43.00 EA	175.00	7,525.00
110	Paint Existing HM Door & Frame	2.00 EA	150.00	300.00
111			**Painting Total**	**$48,398.99**
112			**Finishes Total**	**$804,701.14**

Line	Description	Quantity	Unit Cost	Total
113	**10 Specialties**			
114	**10.2600 Wall And Door Protection (Not Included)**			
115	CG-1 Corner Guards Frey Reglet [DMCT-1250, 1-1/4" Aluminum]	99.00 EA	0.00	0.00
116	WP-1 Construction Specialties Wall Protection [Acrovyn .060N, Texture: Suede, Color: 949 White]	1,385.31 SF	0.00	0.00
117	WP-1 Divider	487.02 LF	0.00	0.00
118	WP-1 Inside Corner	60.00 EA	0.00	0.00
119	WP-1 End Cap	92.00 EA	0.00	0.00
120	WP-1 Adhesive	1,385.31 SF	0.00	0.00
121	Install WP-1 Panels	1,385.31 SF	0.00	0.00
122			**Wall And Door Protection (Not Included) Total**	**$0.00**
123	**10.2800 Bath Accessories**			
124	F/O T-1 Soap Dispenser [Owner Supplied]	4.00 EA	0.00	0.00
125	F/O T-2 Mirror [Bobrick B-293-2436]	4.00 EA	450.00	1,800.00
126	F/O T-3 36" Grab Bar [Bobrick B-5806X36]	4.00 EA	60.00	240.00
127	F/O T-4 42" Grab Bar [Bobrick B-5806X42]	4.00 EA	75.00	300.00
128	F/O T-4 18" Grab Bar [Bobrick B-5806X18]	4.00 EA	50.00	200.00
129	F/O T-6 Toilet Tissue Dispenser [Owner Supplied]	4.00 EA	0.00	0.00
130	F/O T-7 Robe Hook [Kohler K-13433-BN]	8.00 EA	35.00	280.00
131	F/O T-8 Paper Towel Dispenser [Owner Supplied]	4.00 EA	0.00	0.00
132	F/O T-9 Toilet Seat Cover Dispenser [Bobrick B-4221]	4.00 EA	150.00	600.00
133	F/O T-10 Baby Changing Station [Koala Kare KB111-SSWM]	3.00 EA	1,200.00	3,600.00
134	Electric Hand Dryers [Xlerator, Model XL-SB]	9.00 EA	1,100.00	9,900.00
135			**Bath Accessories Total**	**$16,920.00**
136	**10.4400 Fire Protection Specialties**			
137	Fire Extinguisher Cabinet + FE	5.00 EA	350.00	1,750.00
138			**Fire Protection Specialties Total**	**$1,750.00**
139			**Specialties Total**	**$18,670.00**
140	**12 Furnishing**			
141	**12.2000 Window Treatments**			
142	SH-1 Mechoshade [Ecoveil Screens, 0963 1% Open, Color: Grey]	25.00 EA	650.00	16,250.00
143			**Window Treatments Total**	**$16,250.00**
144	**12.3600 Countertops**			
145	Solid Surface Countertops [SS-3]	447.74 SF	120.00	53,728.80
146	Solid Surface Backsplash[SS-3]	67.88 SF	120.00	8,145.60
147	Solid Surface Backsplash [SS-3]	40.38 SF	120.00	4,845.60
148	Corian Window Sills On MDF	60.50 LF	60.00	3,630.00
149			**Countertops Total**	**$70,350.00**
150	**12.4416 Shower Curtains**			
151	F/I - Cubicle Curtains	2.00 EA	1,500.00	3,000.00
152			**Shower Curtains Total**	**$3,000.00**

Line	Description	Quantity	Unit Cost	Total
153			**Furnishing Total**	**$89,600.00**
154	**21 Fire Suppression**			
155	**21.0000 Sprinkler**			
156	Sprinkler	15,076.00 SF	10.00	150,760.00
157			**Sprinkler Total**	**$150,760.00**
158			**Fire Suppression Total**	**$150,760.00**
159	**22 Plumbing**			
160	**22.0000 Plumbing**			
161	F/I Recessed Hose Bib For Mop Bucket	2.00 EA	650.00	1,300.00
162	I/O PF-2 Commercial Floor-Mounted Toilet + Flushometer [American Standard 3043.001, White Seat 5901.100, Flushometer Sloan 8111-1.28]	4.00 EA	2,800.00	11,200.00
163	I/O Bath Lav (Sink) & Faucet	4.00 EA	2,400.00	9,600.00
164	I/O PF-4 Lounge Sink & Faucet [Elkay Blr150C-Gourmet Sink Package]	2.00 EA	1,200.00	2,400.00
165	I/O PF-9 Exam Room Sink & Faucet [Elkay LRAD151750, Chicago Faucet 895-317ABCP]	25.00 EA	2,400.00	60,000.00
166	I/O Hand Wash Med Room Sink & Faucet [Not Specified]	1.00 EA	2,400.00	2,400.00
167	I/O PF-5 Soiled/Clean Room Sink & Faucet [Elkay LRAD252265C, Faucet LKE4121]	1.00 EA	2,400.00	2,400.00
168	I/O PF-6 POC/Lab Sink & Faucet [Elkay LRAD252265C, Bradley Eyewash S19-270C]	3.00 EA	2,400.00	7,200.00
169	I/O Water Fountain/Cooler [Elkay LZWS-LRPBM28K]	2.00 EA	2,000.00	4,000.00
170	Refrigerator Waterline	2.00 EA	900.00	1,800.00
171	F/I Floor Drain	11.00 EA	1,400.00	15,400.00
172	I/O Mop Sink & Faucet Connection	2.00 EA	2,300.00	4,600.00
173			**Plumbing Total**	**$122,300.00**
174	**22.4000 Plumbing Fixtures**			
175	F/O PF-4 Lounge Sink & Faucet [Elkay Blr150C-Gourmet Sink Package]	2.00 EA	2,400.00	4,800.00
176	F/O PF-1 Toilet Sink [American Standard 0955.001EC, Acrylic Shroud 0062.000EC, Carrier Wade 520]	4.00 EA	750.00	3,000.00
177	F/O PF-1 Toilet Faucet [American Standard Faucet 6053.104]	4.00 EA	750.00	3,000.00
178	F/O PF-2 Commercial Floor-Mounted Toilet + Flushometer [American Standard 3043.001, White Seat 5901.100, Flushometer Sloan 8111-1.28]	4.00 EA	1,000.00	4,000.00
179	F/O Mop Sink & Faucet [Kohler Whitby K-6710, Faucet T&S Brass And Bronze Works B-0665-BTSP]	2.00 EA	2,100.00	4,200.00
180	F/O PF-9 Exam Room Sink & Faucet [Elkay LRAD151750]	17.00 EA	1,300.00	22,100.00
181	F/O Hand Wash Med Room Sink & Faucet[Not Specified]	1.00 EA	1,100.00	1,100.00
182	F/O PF-9 Exam Room Sink & Faucet [Elkay LRAD151750, Chicago Faucet 895-317ABCP]	8.00 EA	1,300.00	10,400.00
183	F/O PF-5 Soiled/Clean Room Sink & Faucet [Elkay LRAD252265C, Faucet LKE4121]	1.00 EA	1,300.00	1,300.00
184	F/O PF-6 POC/Lab Sink & Faucet [Elkay LRAD252265C, Bradley Eyewash S19-270C]	3.00 EA	1,600.00	4,800.00
185	F/O Water Fountain/Cooler [Elkay LZWS-LRPBM28K]	2.00 EA	6,000.00	12,000.00
186			**Plumbing Fixtures Total**	**$70,700.00**
187			**Plumbing Total**	**$193,000.00**

Line	Description	Quantity	Unit Cost	Total
188	**23 Heating, Ventilating and Air-Conditioning**			
189	**23.0000 HVAC**			
190	HVAC	15,076.00 SF	27.00	407,052.00
191			**HVAC Total**	**$407,052.00**
192			**Heating, Ventilating and Air-Conditioning Total**	**$407,052.00**
193	**26 Electrical**			
194	**26.0000 Electric**			
195	Allowance for M/P Wiring, Electrical Work Not Shown on Arch. Plans, Etc.	15,076.00 SF	3.00	45,228.00
196	Duplex Receptacle (Commercial)	220.00 EA	175.00	38,500.00
197	Quad Receptacle (Commercial)	68.00 EA	235.00	15,980.00
198	GFI Receptacle (Commercial)	57.00 EA	250.00	14,250.00
199	GFI Quad Receptacle (Commercial)	4.00 EA	250.00	1,000.00
200	Quad Receptacle, USB Charger	14.00 EA	400.00	5,600.00
201	Duplex Receptacle, USB Charger	6.00 EA	350.00	2,100.00
202	Dedicated Equipment Duplex 20amp	3.00 EA	275.00	825.00
203	Wire Hand Dryers	9.00 EA	330.00	2,970.00
204	Wire Water Cooler	4.00 EA	330.00	1,320.00
205	I/O Fixture Type B 24x24 [NEO-RAY S282R-A-2-L35-ESTG-UNV-DD-1D-95N]	96.00 EA	175.00	16,800.00
206	I/O Light Fixture Type A [NEO-RAY S184R-A-2-L35-ESTG-UNV-DD-1D-95N]	79.00 EA	175.00	13,825.00
207	I/O Type C [Philips Lightolier 4RN-C4L-10-8-35-M-Z10-U-C4-R-DL-WH]	9.00 EA	175.00	1,575.00
208	I/O Light Fixture Type D [Saylite X1LED CFR232XL18W40-INV5]	4.00 EA	175.00	700.00
209	I/O Type F [Deco Lighting RND-2-M-35-U-W-SX-M]	34.00 EA	175.00	5,950.00
210	I/O Exit Sign [Exittronix 90XE-R-WB-RW-WH]	29.00 EA	175.00	5,075.00
211	Single-Pole Switch (Commercial)	65.00 EA	140.00	9,100.00
212	Temporary Lighting & Power (LS)	1.00 LS	6,000.00	6,000.00
213			**Electric Total**	**$186,798.00**
214	**26.5000 Lighting Fixtures**			
215	F/O Fixture Type B 24x24 [NEO-RAY S282R-A-2-L35-ESTG-UNV-DD-1D-95N]	96.00 EA	500.00	48,000.00
216	F/O Light Fixture Type A [NEO-RAY S184R-A-2-L35-ESTG-UNV-DD-1D-95N]	79.00 EA	500.00	39,500.00
217	F/O Type C [Philips Lightolier 4RN-C4L-10-8-35-M-Z10-U-C4-R-DL-WH]	9.00 EA	500.00	4,500.00
218	F/O Light Fixture Type D [Saylite X1LED CFR232XL18W40-INV5]	4.00 EA	500.00	2,000.00
219	F/O Type F [Deco Lighting RND-2-M-35-U-W-SX-M]	34.00 EA	500.00	17,000.00
220	F/O Exit Sign [Exittronix 90XE-R-WB-RW-WH]	29.00 EA	500.00	14,500.00
221			**Lighting Fixtures Total**	**$125,500.00**
222			**Electrical Total**	**$312,298.00**
223	**27 Communications**			
224	**27.1000 Tel/Data**			
225	Data Outlet	154.00 EA	325.00	50,050.00
226	Telephone Outlet	31.00 EA	325.00	10,075.00

Line	Description	Quantity	Unit Cost	Total
227	Furniture Mounted Tel/Data Outlet	1.00 EA	350.00	350.00
228	Provide/Install/Coordinate Final Location Of PAC Boxes For TV's	1.00 EA	600.00	600.00
229			**Tel/Data Total**	**$61,075.00**
230	**27.1010 Access Control**			
231	Electric Door Strike	10.00 EA	450.00	4,500.00
232	Maglock for Pair Doors (1200 lb)	3.00 EA	1,050.00	3,150.00
233	Door Release Button	2.00 EA	275.00	550.00
234	Card Readers	11.00 EA	1,050.00	11,550.00
235			**Access Control Total**	**$19,750.00**
236	**27.1020 Audio Visual**			
237	Public Announcement Speaker Panel	16.00 EA	280.00	4,480.00
238	Conference Room Speaker Panel	0.00 EA	600.00	0.00
239	Conference Room Microphone Panel	0.00 EA	600.00	0.00
240			**Audio Visual Total**	**$4,480.00**
241	**27.5223 Nurse Call**			
242	F/I Nurse Call Pull Chord And Light [Alpha Communications EK117B (With Buzzer/Horn)]	8.00 EA	650.00	5,200.00
243			**Nurse Call Total**	**$5,200.00**
244			**Communications Total**	**$90,505.00**
245	**28 Safety And Security**			
246	**28.4600 Fire Alarm**			
247	Fire Alarm	15,076.00 SF	8.00	120,608.00
248			**Fire Alarm Total**	**$120,608.00**
249			**Safety And Security Total**	**$120,608.00**
250	**Sub-Total (Base Cost)**			**$2,715,921.89**

Estimate Summary



Material [$324,447]
Labor [$0]
SubContractor [$2,390,575]
Equipment [$0]
Other [$900]

Description		Total
Sub-Total (Base Cost)		$2,715,921.89
Total Estimate		$2,715,921.89