PANDOLPHO INDUSTRIES
16 Whittier Avenue
Cortlandt Manor, NY 10567

Estimate

Date	Estimate #
6/26/2025	178

Name / Address
Montana Contracting 173 N Route 9W Congers, NY 10920

Project
Paramount Theater

Description	Qty	Rate	Total
Demolition of existing courtyard Remove and dispose of concrete - 1105 sqft Remove and dispose of dirt - 1105 sqft 16" total of soil and concrete to be removed		20,900.00	20,900.00T
Supply and Install Permeable Pavers in existing courtyard - 1105 sqft Edward Martin Dawson 24"x48" Ash No Grout 12" of 3/4" Gravel Base 2" of 3/8" Gravel Base		105,225.00	105,225.00T
Option of Concrete Base Supply and Install Permeable Pavers - 1105 sqft Edward Martin Dawson 24"x48" Ash No Grout 4" of Concrete base 11" of 3/4 Gravel $121,020		0.00	0.00
All work shall be performed in a professional manner in accordance with standard practices. Quotes are valid for 30 Days			

Thank you for your business.

MBE Certification
MWCERT2023-385

Westchester Home Improvement License
WC-35829-H22

www.pandolphoindustries.com

Subtotal	$126,125.00
Sales Tax (8.375%)	$10,562.97
Total	$136,687.97

Balances not paid within 30 days or as set forth will incur finance charges of 1.5% per month together with costs, disbursements and reasonable attorney fees in the amount of 33.5%, if the account is turned over for collection