Estimate

1-3 South Broadway 2025-11-26

Job #25-139

Ashland Industries, Inc.
719 West Nyack Road
Suite 33
West Nyack, New York 10994
carminen@ashlandindustries.com
845.267.0059

Montana Contracting
173 Route 9W
Congers, NY

	Unit Price	Quantity	Total
Formulated Gypcrete	$3.15	5000 SF	$15,750.00 (+ Tax)

Furnish and install a Formulated Gypcrete to an average height of 1 inch.

- Furnish and install all Formulated materials.
- Furnish and install primer and pins.
- Nominal depth of pour will be 1 inch. Entire job will
- be installed in no more than 1 mobilizations.

Notes;

- We will require 100 feet of continuous parking space. Parking space will be secured by others.
- Any permits will be provided by others.
- All penetrations to be sealed by others. Special care
- should be taken over occupied or furnished spaces.
- Leaks happen. • Installed height for each floor to receive underlayment will be given by others.

- We are not responsible for garbage and pallet removal, we will leave in designated area onsite.
- Areas to receive underlayment will be broom swept and free of obstructions.
- No surface prep of substrate is included in this estimate.

The client shall pay as set forth above. Price is subject to change, with the customer's approval.

Invoicing & Payment – Invoice will be issued to Client upon completion of the Work. Client shall pay invoice within 7 days of receipt of invoice. Client shall also pay a late charge of 1-1/2% per month on all balances unpaid 30 days after the invoice date.

Deposit Payment

50% to be paid upfront for materials for each phase/mobilization; all materials will be delivered to and stored at the job site or our warehouse.

The exact deposit amount for each phase/mobilization is yet to be determined and will be agreed upon before any material orders are released for delivery.

Balance Payment

The remaining balance - after the deposit - for phase/mobilization is due when work is complete.

All checks should be made payable to Ashland Industries, Inc 719 W Nyack Rd W Nyack NY 10994

Final Pricing

Final pricing will be based on actual measured installations, as agreed with client.

Please note that square footage price will increase if the size of the job is reduced.

Sales Tax

Pricing does not include Sales Tax. Sales Tax will be added to the invoice unless we are provided with a Tax Exempt or Capital Improvement Certificate.

YOUR RESPONSIBILITIES, EXCEPTIONS, AND NOTES.

1. The client will provide a dumpster to deposit empty coatings containers, demoed material, and other job waste.
2. The client shall move equipment or objects from the work area and provide a broom-swept surface.
3. The client will coordinate the work of other trades, so we have unobstructed access to the work area.
4. The client is to provide access to electrical power from a breaker of at least 100 amps of three phase 208-volt 3-phase power.
5. ~~Access to a working elevator or construction hoist with at least 3,000 lbs lifting capacity.~~
6. Adequate Water Supply of at least 50 # pressure on all floors used for a pour.
7. The estimate assumes all work will be completed within one mobilization(s) and that all materials can be stored on-site or in our warehouse.
8. Ashland will need exclusive uninterrupted access to each work floor area when applying materials.
9. Additional mobilizations could incur an additional cost to the client.

10. Others must remove all construction materials, ladders, tools, etc. before our work can begin.

11. Others will provide any permits required.

12. We need an adequate location for staging our pump, miscellaneous equipment, and materials on the ground level and on each floor where we pump from.

13. Space temperature should be at least 45 degrees before any materials can be applied.

14. Ashland will survey all areas to confirm the work scope area and finished floor heights to be installed, both to be approved by the client.

15. This price is valid for 30 days from the date noted on the letterhead on page 1.

16. This price does not include any permits or testing - testing can be provided by a 3rd party and coordinated by Ashland.

17. The price does not include additional material removal, substrate cleaning, moisture mitigation, or repairs.

18. ~~Installed materials are underlayment/water proofing and not a wear surface / finished floor product .~~

_____ _____

Approved By Print