Date: 1/23/2026
Quote number: 45102040-01-REV1
Client: Montana Constructing
Att: Alex Divernieri — 845-398-1778 — a.divernieri@montanacontracting.com
Steve Catalanotto — 845-398-1778 — s.catalanotto@montanacontracting.com
Agent: ProBuilt Lockers + Cabinets
Project: South Orangetown Ambulance Corp

LINCORA LOCKERS

PRODUCT

— CLARIFICATIONS —
NOTE: No specifications given about the lockers, thus quote with LINCORA "Series-52"
NOTE: Recess base and galvanneal steel quoted in option

— LOCKERS —
Series: 52 STD
Build type: All-welded
Top: 20ga
Bottom: 20ga
Sides: 22ga
Back: 22ga
Frame: 16ga
Ventilation Type : Standard louver door and solid sides
Door: 20/22ga
Shelf: 22ga
Latching mechanism: Single point
Hinges: 5-knuckle 14ga
Recess handle: Stainless steel
Paint finish: Powder-coated standard LINCORA colour
NOTE: Delivery and Installation included

CODE	DESCRIPTION	QTY	UNIT $USD	TOTAL $USD
	— LOCKERS —			
52 - 1 - 18 15 72 2 - 00	Serie 52 — 36" W x 15" D x 78" H — Packaging included Single tier bank of two unit, One fixed upper shelf + Three single prong hooks with a coat bar per compartment, 6"H integrated slopping top	9		
52 - 1 - 18 15 72 1 - 00	Serie 52 — 18" W x 15" D x 78" H — Packaging included Single tier bank of one unit, One fixed upper shelf + Three single prong hooks with a coat bar, 6"H integrated slopping top	2		
	— ACCESSORIES —			
920-073290	Plastic number plate ***sequence required***	20		
920-125001216502-72	Wood top bench 1" 1/4 thick with metal trapezoidal legs — 72" W x 16" D **NOTE: Maple or oak top can be offered*	2		
	— SHIPPING INFORMATION —			
Installation	Installation fees *Regular hours — Prevailling wage — Access to elevator if required*	1		
Pallet	Palletizing fee *48x52*	4		
Freight	Freight charge to 70 Independence Avenue, Tappan, New-York 10983, USA *LTL — Dock-to-Dock — Regular hours*	1		
	SUB TOTAL PRE-TARIFFS : up to Q3 2026		**SUBTOTAL**	**$12,364.00**
	Applicable tariffs			**$557.00**
	TOTAL : up to Q3 2026		**TOTAL**	**$12,921.00**
OPTION(S):				

DIV	Option for 4"H recessed base *NOTE: prevents contact between locker and floor detergents and water, while enhancing ventilation*	1	$716.00	$716.00
DIV	Option for "all-galvanneal" metal *NOTE: provides increased corrosion protection, especially in high humid areas*	1	$990.00	$990.00

Lead time (in weeks): TBD following reception of all approvals (Credit - Drawings - Colors)

Contact: Kenley Nozière
Email: estimation@LINCORA.com
Estimation by: Kenley Nozière

FOB: Lincora dock, Montreal, QC, H1N 2E9 — unless stated otherwise in "Freight"
Please write the above quote number on your purchase order
No warranty on lockers if placed in or close to a wet environment (such as pool area, water front, ect…)
Terms & conditions: see following pages

Terms and conditions

Price:

- Price valid for a period of 10 days following the date of the quote.
- Prices are subject to any unusual fluctuations in the price of steel, delivery, or other factors.
- Prices for delivery scheduled more than 8 months after the date of the quote will be indexed by 5%.

Delivery:

- Ecoterm: FOB Lincora Dock, Mtl QC H1N 2E9
- Price includes delivery in 1 phase, otherwise additional charges may apply.

Timeline:

- **Drawing Approval:** Within 10 working days of final order.
- **Delivery time:** 8 to 10 weeks following final approval of drawings.

Note:

- Any change in delivery date must be communicated 4 weeks before the initially confirmed delivery date, otherwise storage fees may be charged.
- Storage fees are $1 per square ft / week.

Payment terms:

- To be determined, subject to credit approval
- For any new customer:
  - 1/3 upon receipt of the order.
  - 1/3 at the start of production.
  - 1/3 upon delivery.
- Contract holdbacks will be a maximum of 5% of the installation value.
- No holdbacks apply if Lincora does not install the equipment.
- Said contract holdbacks will be payable within a maximum of 90 days after installation is completed.

Note: Any late payment that has not been the subject of an agreement with LINCORA will be charged a financial fee of 2% per month.

Cancellation Fees:

- In case of order cancellation, a minimum cancellation fee of 20% of the order amount will apply. Depending on the project's progress and payments made, cancellation fees will be adjusted accordingly.

Measurement changes:

Any modification to the dimensions of the lockers must be requested no later than 8 weeks before the scheduled delivery date.

Limitations:

- **Locker quantities:** The quantities and specifications of the products provided in our quote are LINCORA's interpretation according to the documents provided by the customer.

- **Specifications and quantities** for the furniture, provided in the quote, must be verified, and controlled by the buyer before ordering. The accuracy of all specifications is the responsibility **of the latter**.

- **Multiple colours:** Any additional request for alternating colors on lockers (including doors and frames), any extra color choices, or any specific requests unknown at the time of the quote may incur additional charges

- **Installation (if applicable):** The installation price assumes access to a clean site prepared to receive the lockers for installation. The contractor is responsible for providing all necessary handling equipment (pallet jack, freight elevator, lifts, etc.) and services (electricity, lighting, and others).

- The installation is planned to be carried out in one single phase. Any returns or additional work required to complete the installation of the lockers, the responsibility of which is not related to LINCORA's work, will be invoiced at the following rates:
    - Hourly rate of $125 / hour.
    - Travel rate of $90 / hour.
    - Mileage: $0.80 / km (subject to change without notice).

- Locker installation requires a level floor. Floor leveling is not the responsibility of **LINCORA**. No leveling of lockers beyond 0.5'' is included.

- The customer is responsible for taking the measurements – Lincora disclaims any responsibility relating to the taking of the measurements.

- No warranty on lockers will be applicable if they are installed in an area adjacent to a swimming pool.