PROPOSAL

Job: BIG GEYSER
Description: SITE WORK FOR RENOVATION OF EXISTING FACILITY
Location: BREWSTER, NY
Client: MONTANA
Bid Date: 2025-10-22 REVISED
PRICE VALID FOR 30 DAYS
Estimator: KST
Plans: INSITE, 10-10-25 (PAGES 1-15)

NO.	ITEM	QTY	U/M	UNIT PRICE	AMOUNT
****THIS IS A MEMO OF UNDERSTANDING THAT THE WORK TO BE PERFORMED IS LIMITED TO THE SCOPE BELOW. THE SCOPE IS BASED SOLEY ON THE CIVIL DESIGN DRAWINGS REFERENCED ABOVE. ****					
SITE DEMO					
1	MOBILIZATION	1	LS	$ 4,775.00	$ 4,775.00
2	REMOVAL AND DISPOSAL OF CHAIN LINK FENCING	1000	LF	$ 4.50	$ 4,500.00
3	REMOVAL AND DISPOSAL OF CURBS	1700	LF	$ 7.50	$ 12,750.00
4	REMOVAL AND DISPOSAL OF EXISTING UTILITIES AS NEEDED	1	LS	$ 4,250.00	$ 4,250.00
5	REMOVAL AND DISPOSAL OF CLAY TENNIS COURT SURFACE	24000	SF	$ 0.50	$ 12,000.00
6	REMOVAL AND DISPOSAL OF EXISTING TREES AND LANDSCAPING AS NEEDED	1	LS	$ 5,500.00	$ 5,500.00
7	REMOVAL AND DISPOSAL OF EXISTING CONCRETE SIDEWALKS/STEPS/PADS	4700	SF	$ 4.50	$ 21,150.00
8	REMOVAL AND DISPOSAL OF EXISTING CONCRETE PLANTERS	1	LS	$ 4,500.00	$ 4,500.00
9	REMOVAL AND DISPOSAL ADDITIONAL MISC. CONCRETE WALLS	1	LS	$ 7,250.00	$ 7,250.00
10	REMOVAL AND DISPOSAL OF EXISTING ASPHALT **(INCLUDING MAIN PARKING AREA)**	29000	SF	$ 0.95	$ 27,550.00
				SUB TOTAL	**$ 104,225.00**
SITE EROSION CONTROL					
11	FURNISH AND INSTALL CONSTRUCTION ENTRANCE	3	EA	$ 2,500.00	$ 7,500.00
12	FURNISH AND INSTALL SILT FENCE	1600	LF	$ 4.50	$ 7,200.00
13	FURNISH AND INSTALL ORANGE CONSTRUCTION FENCE	700	LF	$ 3.50	$ 2,450.00
14	FURNISH AND INSTALL INLET PROTECTION	19	EA	$ 300.00	$ 5,700.00
15	FURNISH AND INSTALL WATER BAR, CHECK DAMS AND DEWATERING DEVICE AS NEEDED	1	LS	$ 4,250.00	$ 4,250.00
16	TEMPORARY STABILIZATION AS NEEDED	1	LS	$ 8,250.00	$ 8,250.00
17	STREET SWEEPING FOR TOMPKINS EXCAVATING ONLY	1	LS	$ 3,500.00	$ 3,500.00
				SUB TOTAL	**$ 38,850.00**
SITE MASS EARTHWORK					
18	STRIP TOPSOIL AND STOCKPILE ON-SITE	2000	CY	$ 7.00	$ 14,000.00
19	MASS EARTH TO CUT	16500	CY	$ 6.00	$ 99,000.00
20	MASS EARTH TO FILL	2200	CY	$ 5.00	$ 11,000.00
21	ROUGH GRADE ENTIRE SITE	1	LS	$ 19,500.00	$ 19,500.00
22	RE-SPREAD TOPSOIL **(MACHINE PLACEMENT ONLY)**	1000	CY	$ 8.00	$ 8,000.00

23	EXPORT EXCESS FILL	14300	CY	$ 16.00	$ 228,800.00
24	EXPORT EXCESS TOPSOIL	1000	CY	$ 12.00	$ 12,000.00
				SUB TOTAL	**$ 392,300.00**
SITE DRAINAGE					
25	FURNISH AND INSTALL 6" WALL DRAIN AND ROOF DRAIN	600	LF	$ 29.00	$ 17,400.00
26	FURNISH AND INSTALL 6" HDPE	120	LF	$ 24.00	$ 2,880.00
27	FURNISH AND INSTALL 12" HDPE	140	LF	$ 44.00	$ 6,160.00
28	FURNISH AND INSTALL 15" HDPE	600	LF	$ 48.00	$ 28,800.00
29	FURNISH AND INSTALL 18" HDPE	40	LF	$ 59.00	$ 2,360.00
30	FURNISH AND INSTALL TRENCH DRAIN	60	LF	$ 375.00	$ 22,500.00
31	FURNISH AND INSTALL 30" X 48" CATCH BASIN	9	EA	$ 3,450.00	$ 31,050.00
32	FURNISH AND INSTALL 48" DIAM. DRAIN MANHOLE	1	EA	$ 3,250.00	$ 3,250.00
33	FURNISH AND INSTALL 24" X 24" YARD DRAIN	1	EA	$ 2,250.00	$ 2,250.00
34	CONNECT TO EXISTING DRAINAGE	6	EA	$ 2,000.00	$ 12,000.00
35	FURNISH AND INSTALL END SECTION WITH RIP-RAP	9	EA	$ 1,450.00	$ 13,050.00
36	RE-GRADE STORMWATER BASINS	2	EA	$ 4,500.00	$ 9,000.00
37	FURNISHN AND INSTALL GRASS SWALE	1	LS	$ 2,000.00	$ 2,000.00
38	CHANGE FRAME AND GRATE ON EXISTING STRUCTURE	3	EA	$ 1,150.00	$ 3,450.00
39	SAW CUT, DEMO AND RESTORE FULL DEPTH ASPHALT FOR DRAINAGE ACROSS ROAD	350	SF	$ 6.00	$ 2,100.00
				SUB TOTAL	**$ 156,150.00**
SITE UTILITIES					
40	FURNISH AND INSTALL NEW FORCE MAIN	350	LF	$ 25.00	$ 8,750.00
41	CONNECT NEW FORCE MAIN TO EXISTING FORCE MAIN	4	EA	$ 1,000.00	$ 4,000.00
42	TRENCHING AND BEDDING FOR NEW E/G/T	225	LF	$ 23.00	$ 5,175.00
43	TRENCHING AND BEDDING FOR SITE LIGHTING	700	LF	$ 18.00	$ 12,600.00
44	FURNISH AND INSTALL 18" X 72" LIGHT POLE BASES **(DOES NOT INCLUDE ANCHOR BOLTS OR CONDUIT)**	3	EA	$ 1,350.00	$ 4,050.00
				SUB TOTAL	**$ 34,575.00**
SITE CONCRETE					
45	FURNISH AND INSTALL CONCRETE CURBS	2100	LF	$ 27.00	$ 56,700.00
46	FURNISH AND INSTALL CONCRETE SIDEWALKS	1500	SF	$ 13.00	$ 19,500.00
47	FURNISH AND INSTALL CONCRETE LOADING DOCK PADS INCLUDING RAMP	5575	SF	$ 13.00	$ 72,475.00
				SUB TOTAL	**$ 148,675.00**
SITE PAVING					
48	FURNISH AND PLACE FABRIC BELOW ITEM 4 FOR ALL AREAS	68600	SF	$ 0.35	$ 24,010.00
49	FURNISH AND PLACE 8" ITEM 4 FOR LD AREAS	1150	CY	$ 52.00	$ 59,800.00
50	FURNISH AND PLACE 12" ITEM 4 FOR HD AREAS	1550	CY	$ 52.00	$ 80,600.00
51	FURNISH AND PLACE 2.5" ASPHALT BINDER FOR LD AREAS	36100	SF	$ 2.10	$ 75,810.00
52	FURNISH AND PLACE 4" ASPHALT BINDER FOR HD AREAS	32500	SF	$ 3.20	$ 104,000.00
53	FURNISH AND PLACE 1.5" ASPHALT TOP FOR LD AREAS	36100	SF	$ 1.35	$ 48,735.00
54	FURNISH AND PLACE 2" ASPHALT TOP FOR HD AREAS	32500	SF	$ 1.75	$ 56,875.00
55	STRIPE PARKING LOT	1	LS	$ 4,475.00	$ 4,475.00
				SUB TOTAL	**$ 454,305.00**

MISC ITEMS					
56	EXCAVATE, BACKFILL AND GRAVEL PREP FOR BUILDING ADDITION	1	LS	$ 5,000.00	$ 5,000.00
57	FURNISH AND INSTALL BOLLARDS	2	EA	$ 750.00	$ 1,500.00
58	FURNISH AND INSTALL TYP. TRAFFIC SIGNS	10	EA	$ 450.00	$ 4,500.00
59	EXCAVATE, BACKFILL AND PREP FOR CONCRETE RETAINING WALLS INCLUDING CRUSHED STONE BACKFILL	1	LS	$ 29,500.00	$ 29,500.00
				SUB TOTAL	**$ 40,500.00**
			GRAND TOTAL		**$ 1,369,580.00**

ROCK REMOVAL AND UNIT PRICING		
1	12,000 FT-LB HAMMER ON 80,000 LB EXCAVATOR **(8 HR MIN. PLUS $500 MOB.)**	$500/HR
2	7,500 FT-LB HAMMER ON 52,000 LB EXCAVATOR **(8 HR MIN. PLUS $500 MOB.)**	$400/HR
3	5,000 FT-LB HAMMER ON 52,000 LB EXCAVATOR **(8 HR MIN. PLUS $500 MOB.)**	$350/HR
4	CRUSHER/EXCAVATOR/LOADER/ROCK TRUCK TO HANDLE, PROCESS OR CRUSH HAMMERED/PROCESSED ROCK	$350/HR
5	EXPORT OF EXCESS ROCK (PROCESSED OR UNPROCESSED)	$30/CY
6	IMPORT RECYCLED ITEM #4 AS STRUCTURAL FILL (MATERIAL ONLY - 18 CY PER TRIAXLE LOAD)	$45/CY
7	LABORER	$125/HR
8	FIELD LEADER	$150/HR
9	EQUIPMENT AND OPERATOR	$300/HR

NOTES	
1	*THIS CONTRACT INCLUDES THE USE OF GPS 3-D MODELING OF THE SITE DESIGN AND THE USE OF GPS MACHINE CONTROL*
2	*THIS BID IS BASED SOLEY ON THE CIVIL DESIGN DRAWINGS, ANY DISCREPENCIES BETWEEN ARCHITECTURAL DRAWINGS, SPEC MANUALS, AND ANY OTHER DOCMENTATION ARE TO BE DISCUSSED AS CHANGE ORDERS*
3	*ALL QUANTITIES ARE ASSUMED TO BE LOOSE IN-TRUCK YARDS AND WILL BE TRACKED BY TRUCK LOADS @ 18 CY*
4	*ALL DIP, WATER VALVES, FITTINGS, FRAME AND GRATES/COVERS ARE PRICED AS EQUAL TO "DOMESTIC". NO "DOMESTIC" ITEMS ARE INCLUDED IN THIS PROPOSAL.*
5	*PRICING SUBJECT TO CHANGE AFTER CONTRACTS BASED ON VOLITILE MATERIAL MARKETS. THIS PRICING IS ONLY VALID FOR 30 DAYS FROM ABOVE DATE. PAST THAT MATERIAL PRICING IS SUBJECT TO REVIEW AND ADJUSTMENT*
6	*NOT RESPONSILBE FOR PUDDLING IN PAVED AREAS WITH LESS THAN 3% PITCH IN ANY DIRECTION*
7	*ALL EXISTING TOPO GRADES WILL BE VERIFIED PRIOR EXCAVATION BEGINS - ADDITIONAL COSTS WILL APPLY IF ACTAUL CONDITIONS DO NOT MATCH CONDITIONS SHOWN ON DRAWINGS*

NO.	EXCLUSIONS
1	CONSTRUCTION FENCING
2	ROCK REMOVAL INCLUDING HAMMERING, CRUSHING, AND ANY ASSOCIATED MACHINE TIME FOR HANDLING, EXCAVATING, CRUSHING OR LOADING OF ANY ROCK, INCLUDING HAMMERED OR PROCESSED ROCK. ROCK REMOVAL IS DEFINED AS LEDGE/BED ROCK AND/OR ANY BOULDER OVER 1 CUBIC YARD
3	DRILLING, BLASTING, SETTING OF BLASTING MATS AND ANY ASSOCIATED PERMINTS, SURVEYS, AND FEES
4	ENGINEER, SURVEYOR AND INSPECTION FEES
5	PERMITS, BONDS AND ANY ASSOCIATED FEES
6	AS-BUILTS
7	COMPACTION TESTING
8	SOIL TESTING
9	TREATMENT AND/OR REMOVAL OF UNSUITABLE SOIL DUE TO WATER CONDITION, EXCESS MOISTURE, NOT MEETING SPEC, ETC.
10	REMOVAL OF CONTAMINATED MATERIAL
11	PRIVATE MARKOUT
12	DEWATERING
13	DUST CONTROL FOR OTHERS
14	STREET CLEANING FOR OTHERS
15	MUD, SNOW AND FROST REMOVAL
16	BACKFILLING/GRADING/FILLING WITH ANY MATERIAL OTHER THAN ON-SITE EXCAVATED MATERIAL AND, EXPORT OF EXCESS FILL IF GENERATED, AND IMPORT OF SELECT STRUCTURAL FILL. ASSUMED TO **ONLY** USE ON-SITE MATERIAL FOR ALL CUTS/FILLS/GRADING/BACKFILLING/ETC.
17	MOVING AND HANDLING OF MATERIAL FROM OTHER TRADES TO ALLOW FOR SITE WORK TO CONTINUE
18	RAKING, SEEDING AND LANDSCAPING
19	SCREENING OR ROCK, ROOT, DEBRIS REMOVAL FROM MACHINE PLACED TOPSOIL
20	FENCING, GATES, GUIDE RAILS, RAILINGS, ETC.
21	NOT RESPONSIBLE FOR FROST HEAVING
22	NOT RESPONSIBLE FOR STANDING WATER IN PAVEMENT AREAS WITH LESS THAN 3% PITCH IN ANY DIRECTION
23	REPLACEMENT OF PLANTER BOXES IN FRONT OF BUILDING
24	CONCRETE RETAINING WALLS
25	CONCRETE STEPS
26	DEMO OF EXISTING BUILDING AND STRUCTURAL DEMO FOR "GARAGE UNDER" AT NORTH WEST CORNER OF BUILDING

SUBMITTED BY: KEVIN TOMPKINS	*Kevin Tompkins*		
		DATE:	10/22/2025

ACCEPTED BY:			
		DATE:	