CALCULATED FIRE PROTECTION CO., INC.
CFP

SYCAMORE SQUARE, SUITE 2
2510 ROUTE 44
SALT POINT, NY 12578

PHONE (845) 677-5201
www.calculatedfire.com

July 10th, 2025

Re: Shake Shack –
35 Winslow Gate Rd,
Poughkeepsie, NY
Estimate **#E25-0459**

Greetings,

We are pleased to offer our proposal covering all necessary labor and material(s) required to complete the following work**:** ***Relocate and add heads from existing branch lines to accommodate new ceiling and partition layout based off drawings FD100 & F101 dated 5/13/25. Existing mains and branch lines shall remain.***

- Heads shall be centered both ways in ceiling tiles nearest existing branch line outlets.
- Approximate total head count is 40. New concealed style & upright heads shall be used.
- System shall remain in service at the end of each workday.
- Tap into existing main or lines, add new branch lines and heads as indicated.
- It is assumed there are existing heads in all locations.
- It is assumed all work shall be performed on straight time.
- Professional Engineers review and seal.
- Drawings and calculations.
- 200 psi pressure test.
- Permits secured.
- Headbox with accessories.

Our price for this work shall be: *NINETEEN THOUSAND NINE HUNDRED DOLLARS ($19,900.00).*
Sales tax is included in our price based on a Capital Improvement Project.

Please add the appropriate amount if the following are required or requested:

- Additional cost for sprinkler head w/ 5ft of pipe…$250.00 per head

<u>Excluded work:</u>
(Qualifications/exceptions/clarifications)
Anything not outlined in included work listed above including but not limited to the following:

- Installation is based on N.F.P.A, New York State & local codes regarding material and design. Specifications and insurance underwriter requirements are specifically excluded if they exceed code requirements.
- Adding new lines or mains; upsizing or gridding to achieve required pressure and volume for added heads. It is assumed the existing mains and lines are adequate for the new modifications.
- Demolition, removing, relocating, raising or adjusting any existing sprinkler branch lines or mains.
- Heads shall be centered both ways in ceiling tiles nearest each existing branch line outlets.
- Installing, removing, replacing or cutting ceiling tiles. Ceiling tiles shall be cut and installed by "others", after our head installation.
- Opening, Cutting and patching walls or ceilings including soffits or "boxing in" of exposed piping.
- All ceiling grid and framing must be installed prior to our arrival.
- It is assumed that there is an accessible control valve and drain located on the same floor as our work and that this system drains properly without trapped piping.
- Repairing leaks on existing system piping which may occur due to movement and recharging.
- The purchaser is to provide light and power, without cost to us, during our hours of work.
- Special color sprinkler head escutcheons; our price is based on standard stock colors only.
- All work is to be completed during our normal working hours Monday through Friday.
- Furnishing, removing, replacing or reinstalling cover plates on existing heads.
- Fire watch and/or temporary fire systems.
- Painting and/or priming of our pipes/heads/components including prepping/cleaning or removing oils.
- Seismic or sway bracing and hangers.
- Fire extinguishers and cabinets.
- Phase work/mobilization.
- Shutdown fees.
- Flashing.
- Supplemental framing.
- Standpipes.
- Furnishing/installing fire alarm equipment.
- Underground work.
- Trenching/backfilling

We thank you for the chance to present this proposal and your interest in our Company. We look forward to serving your fire protection needs. If you have any questions, please contact me at (845) 677-5201.

Sincerely,
Calculated Fire Protection Co., Inc.

Erik Manfredi

Erik Manfredi
Estimator