Estimate

DATE	No.
9/12/2024	5023

Bob Dietz & Sons, Inc.
474 Springtown Road
New Paltz, NY 1256l-3032
Phone # 845-255-0086 tony@dietzhomes.com
Fax # 845-255-3431 Bobdietzandsons.com

Customer:

Montana Contracting
Ines MacAdams
173 N Rte 9W
Congers, Ny 10920

Description	Qty	Rate	Total
45 HAVILAND KEMMERER PROJECT ADDITION / EXPANSION			
PLANS by GRAYDON YEARICK 19 pages.			
Civil and site plans are limited			
1. GENERAL CONDITIONS			
Mobilization of equipment And site layout	**1**	**5,830.00**	**5,830.00**
Subtotal			**5,830.00**
2. EROSION CONTROL and CLEARING			
Silt fencing (per foot) ALLOWANCE nothing is shown on the plans	**300**	**6.60**	**1,980.00**
Tree clearing and chipping Estimating 6 Trees to remove	**1**	**3,850.00**	**3,850.00**
Strip Topsoil and stockpile for later use. LIMIT of DISTURBANCE FOR CONSTRUCTION AREA	**10,000**	**0.33**	**3,300.00**
Subtotal			**9,130.00**
3. DEMOLITION			
Remove parts of existing stone wall and Concrete walk the conflict new construction area	**1**	**2,871.00**	**2,871.00**
Subtotal			**2,871.00**
4. EXCAVATION			
Excavation for 4' frost walls Per LF .	**401**	**18.95**	**7,598.95**
Backfill for 4' frost walls Per LF . Compaction in lifts Interior and exterior	**401**	**18.95**	**7,598.95**
Item # 4 per ton If needed to structural fill on the interior of the foundations for grade changes	**200**	**30.00**	**6,000.00**
Allowance of 200 tons			
Install 4" perforated PVC with 3/4 stone and fabric to daylight LF	**600**	**13.13**	**7,878.00**
6" of 3/4" stone under slab leveled and compacted. For Garage and addition slabs SF cost	**3,000**	**2.20**	**6,600.00**
Estimate Total			

Estimate

DATE	No.
9/12/2024	5023

Bob Dietz & Sons, Inc.
474 Springtown Road
New Paltz, NY 1256l-3032
Phone # 845-255-0086 tony@dietzhomes.com
Fax # 845-255-3431 Bobdietzandsons.com

Customer:

Montana Contracting
Ines MacAdams
173 N Rte 9W
Congers, Ny 10920

Description	Qty	Rate	Total
Parking and drive for new garage area. IF NEEDED ALLOWANCE FOR 1500 SF area **1' of road base graded and compacted. Topped with 4" of item 4 graded and compacted** **Geo fabric installed**	**1,500**	**5.00**	**7,500.00**
Finish Grade site, topsoil from site stockpile. Seed / Mulch . No import of Topsoil **Allowance of 8000 SF projected**	**8,000**	**0.44**	**3,520.00**
Many of the items are by the unit and allowance. These can be adjusted as needed.			
EXCLUSIONS: **ROCK REMOVAL** **TESTING AND ENGINEERING** **PLANS DO NOT SHOW ANY UTILITIES - SEWER -ELECTRIC- WATER**			
Sales Tax		**8.00%**	**0.00**
Estimate Total			**$64,526.90**