Estimate

DATE	No.
1/23/2025	5579-1

Bob Dietz & Sons, Inc.
474 Springtown Road
New Paltz, NY 1256l-3032
Phone # 845-255-0086 tony@dietzhomes.com
Fax # 845-255-3431 Bobdietzandsons.com

Customer:

Montana Contracting
Ines MacAdams
173 N Rte 9W
Congers, Ny 10920

Description	Qty	Rate	Total
CREST ROAD HOUSE SITE			
REVISED 1/23/25 (remove drive way work and add 1 retaining wall excavation)			
1. General Conditions			
Mobilization of equipment	7	700.00	4,900.00
Site layout and record as built data GC to provide 6 current survey control points	1	7,522.00	7,522.00
Subtotal			12,422.00
2. Erosion Control			
Silt fencing 500 LF at house site and septic field area.	500	5.80	2,900.00
Silt Fence along the Driveway has been installed and drive way is already rough graded			
Concrete wash out	1	1,450.00	1,450.00
Construction Entrance tracking pad	1	3,350.00	3,350.00
Tree clearing and chipping . (THE SITE HAS BEEN CLEARED)	0	0.00	0.00
Strip Topsoil and stockpile on site for later use	1	2,350.00	2,350.00
Subtotal			10,050.00
3. Excavation and grading			
Excavation General grading to finish what was started . Minor grading to dress driveway and upper parking area at house location (3 day allowance)	0	11,000.00	0.00
Excavation for 4' frost walls and fill depth foundation wall excavation 225 LF	1	9,225.00	9,225.00
Backfill for 4' frost walls and full depth walls 225 LF	1	13,700.00	13,700.00
8-10 ' lifts compacted 270 tons of select fill imported to use as backfill			
Pier excavation and backfill 10 piers	10	280.00	2,800.00
6" of 3/4" stone under Basement slab leveled and compacted 1000 SF	1	4,400.00	4,400.00
Excavation 50 LF retaining wall as bridge abutment. 4" perf drain and stone bedding with fabric to daylight backfill included	1	4,075.00	4,075.00
Estimate Total			

Estimate

DATE	No.
1/23/2025	5579-1

Bob Dietz & Sons, Inc.
474 Springtown Road
New Paltz, NY 1256l-3032
Phone # 845-255-0086 tony@dietzhomes.com
Fax # 845-255-3431 Bobdietzandsons.com

Customer:

Montana Contracting
Ines MacAdams
173 N Rte 9W
Congers, Ny 10920

Description	Qty	Rate	Total
DRIVEWAY WORK. IF NEEDED PER PLAN (Road looks to be cut in and rough graded)			
Top driveway with 3/4" item #4 4" thick 16800 SF	**0**	**1.12**	**0.00**
12' wide driveway- constructed with 8" ROB or equal road base material 16,800 SF	**0**	**1.90**	**0.00**
Construct a 5' wide swale approximately 8-12" deep per plan locations 1400 LF Grass lined	**0**	**6.61**	**0.00**
General house Parking area per plan 8000 SF 8" of road base and 4" item 4 top	**8,000**	**2.93**	**23,440.00**
Subtotal			**57,640.00**
4. Septic system per plan Base proposal (1) 1250 Gallon gravity system to primary field			
IT APPEARS THE FIELD AREA IS ALREADY GRADED AND NO IMPORT OF FILL IS NEEDED ?			
1250 gal. Precast septic tank gravity to D box and (10) 50 ' laterals	**1**	**32,995.00**	**32,995.00**
Provide all material and labor to install (!0) laterals -tank and D box			
Backfill and seed and stabilize			
No import of septic fill			
Subtotal			**32,995.00**
5. Domestic Water			
Water line trench (trench and sand only) From the well to the house 50 LF	**50**	**18.00**	**900.00**
Subtotal			**900.00**
6. Underground Electrical service. (Per plan from town road pole to the house foundation			
Dig 24 - 30 " deep electric line trench backfill using 1' sand bedding .	**1,535**	**25.50**	**39,142.50**
From the pole to the house 1535 LF			
Supply (1) 3" conduit and (2) 2" conduits sch 40 pipe installed			
Subtotal			**39,142.50**
7. Regrade topsoil and Stabile disturbed areas			
Estimate Total			

Estimate

DATE	No.
1/23/2025	5579-1

Bob Dietz & Sons, Inc.
474 Springtown Road
New Paltz, NY 1256l-3032
Phone # 845-255-0086 tony@dietzhomes.com
Fax # 845-255-3431 Bobdietzandsons.com

Customer:

Montana Contracting
Ines MacAdams
173 N Rte 9W
Congers, Ny 10920

Description	Qty	Rate	Total
Finish Grade site, with stockpiled topsoil and seed / straw stabilization . -no import of topsoil.	**1**	**10,100.00**	**10,100.00**
Up to 60000 SF disturbed area			
Subtotal			**10,100.00**
Subtotal			**163,249.50**
Exclusions ;			
1.Driveway culvert pipes and retaining walls. Driveway looks to be Rough cut in and pipes in			
2.Future studio excavation / studio septic / studio water / Studio electric			
3.Future pool work			
4. Rock Excavation Per day $3500 per day for Jackhammer / $3000 per day large Ripper			
Sales Tax		**8.00%**	**0.00**
Estimate Total			**$163,249.50**