G. MELOMO EXCAVATING, INC.
25 Carlough Road, Unit 2, Bohemia, NY 11716

Owner Information

Customer Name	Island Wide Construction Mangement	Project Name	Wing Stop Huntington Station
Contact	Woody Kerzner	Date of Proposal	6/6/2025
Address	-	Proposal Number:	1
City, State ZIP	-	Address	725 North Broadway (Route 110)
Phone	(516) 523-0729	City, State ZIP	Amityville, NY 11701
Fax:	-	Start Date	T.B.D.
Email	islandwideconstructionmgnt@gmail.com	Completion Date	T.B.D.

We Hereby Propose the Following Scope of Work, to be Completed:

Mobilization/General Conditions:

* Provide (1) Mobilization/Demobilization For Equipment **(Pricing Subject To Change If Additional Mobilizations Required)**

** **All Surveying, Stake-Out And As-Built Drawings To Be Performed By Others**

General Conditions Total: $ 3,000.00

Site Demolition:

* Remove And Dispose Asphalt (Max. 4" Thick), Curbs, Sidewalk (Max. 4" Thick), Trash Enclosure Pad (Max. 6" Thick), Fencing, Misc. Site Features

** **Existing Building To Remain (All Select Demolition Work And Asbestos Abatement/Removal On Existing Building Excluded)**

** **All Utility Disconnections, De-Energizing And Overhead Wire Removals To Be Performed By Others By Others**

** **All Off-Site Demolition Work Excluded**

Site Demolition Total: $ 28,700.00

Tree Clearing:

* Clear Trees and Vegetation (On-Site Only) as per Plan. Truck and Dispose Off-Site

Tree Clearing Total: $ 8,800.00

Site Excavation:

* Mass Site Grading For Asphalt Areas, Concrete Sidewalks, Trash Enclosure, Landscape Areas, Etc. As Per Plan

* Export Excess Fill

** **Existing Building To Remain (All Building Excavation Work Excluded)**

** **RCA/Base Material Under All Concrete Flatwork And All Off-Site Excavation Excluded**

** **Excludes Any Remediation Or Undercutting Of Unsuitable Fill. All Fill Removal Must Be Clean Of Debris And Contaminants (Concrete, Asphalt, Brick, Bog, Etc.)**

Site Excavation Total: $ 17,200.00

Drainage:

* Remove And Dispose One Existing Drainage Structure **(Assuming Max. 10'Ø x Max 12' Deep)**
* Furnish And Install (1) New Drainage Structure **(Assuming Max. 10'Ø x Max 12' Deep)** Including (1) 24"Ø x 4" Thick Round Casting
* Backfill/Compact All Void With Excavated Material
* All Storm Rings To Include Filter Fabric **(Footing Rings Excluded)**
* All Castings To Be Imported Cast-Iron
* Backfill Collar With **On-Site** Material
* Export Excess Fill (All Excavated Material Must Be Clean/Free of Debris/Contaminants)

** **Roof Leader Piping/Interconnecting Piping Excluded**

** **Pricing Subject To Change Based On A Verification In-Field Of The Existing Drainage Pool Size And Depth**

Drainage Total: $ 11,400.00

Sanitary:

* Abandon Existing Septic System As Per Plan In Accordance With SCDHS Requirements **(Demolition Excluded)**
* Furnish And Install (1) FUJI CEN-7 Septic System Complete (Including Control Panel) In A Precast H-20 Rated Ring, (1) 1,500 Gal. Septic Tank, (1) 1,500 Gal. Grease Trap, (1) 750 Gal. Pre-Treatment Tank (Inc. (1) 4"Ø Effluent Filter), (2) 4'Ø Sanitary Manholes, (2) 10'Ø x 12' Deep Leaching Pools (Inc. High Domes), 4"/6" Piping, (2) Cleanouts, (2) Building Connections
* Control Panel To Be Mounted On Building **(H-Frame Excluded)**
* All Castings To Be Imported Cast-Iron
* Backfill With **Excavated** Material.
* Export Fill

** **All Required Electric Service To FUJI Septic System/Control Panel To Be Provided By Others**

** **All Interior Plumbing By Others. Mininum 2' Feet of 4" Piping Must Be Protruding Foundation.**

** **No SCDHS Approved Sanitary Plan Provided. Pricing Contingent Upon Review of A SCDHS Approved Sanitary Plan**

** **Excludes A 3-Year Operations & Maintenance Agreeement. Maintenance Contracts Must Be Purchased Directly Throught A Certified FUJI Distributor**

** **Excludes Any Remediation Or Undercutting Of Unsuitable Fill. All Fill Removal Must Be Clean Of Debris And Contaminants (Concrete, Asphalt, Brick, Bog, Etc.)**

Sanitary Total: $ 71,800.00

Additional Sanitary Piping (Future Tenants):

* Provide Additional Sanitary Piping And Fittings Including (1) Future 6" Grease Line Connections And (1) 4" Future Sanitary Line Connections For (2) Future Development Spaces **(Not Dictated On Sanitary Plans)** For A Total of (2) Future Grease Line Connections And (2) Future Sanitary Line Connections
* All Piping To Be Installed +/-5 Feet of Proposed Building Footprint
* Work To Be Performed Simulanteously With Sanitary Structure Installation

** **No SCDHS Approved Sanitary Plan Provided. Pricing Contingent Upon Review of A SCDHS Approved Sanitary Plan**

Additional Sanitary Piping (Future Tenants) Total: $ 7,000.00

Water:

* Furnish and Install (45') of 1.5"Ø "K" Copper From The Property Line To +/- 5 Feet of Existing Building Footprint
* Backfill With **Excavated** Material (All Excavated Material Must Be Clean/Free of Debris/Contaminants)

** **No Approved Water Drawings Provided. Pricing Contingent Upon Review of Approved Drawings**

** **Excludes: Permits, Tap, Water District Fees, Meter, Meter Pit, RPZ, Service Gate Valve/Box and Curb Stop/Box**

Water Total: $ 3,600.00

Electrical/Site Lighting Excavation:

* Trench For Underground Electric Service From Pole To Building Footprint As Per Plan. Backfill With Excavated Material
* Trench For Underground Site Lighting Electric Service As Per Plan. Backfill With **Excavated** Material
* Excavate For (3) Site Lighting Pole Foundations **(Supplied By Others)**. Backfill With **Excavated** Material
* All Excavated Material Must Be Free of Debris/Contaminants

** **All Underslab Electrical Trenching Inside Building Excluded**

** **All Electrical Work To Be Performed By Others. Electrican Must Be On-Site To Coordinate Excavation Work**

Electrical/Site Lighting Excavation Total: $ 4,900.00

Total Bid Price: $ 156,400.00

Alternates:

RCA Under Asphalt:

* Furnish, Place, Compact And Grade (4") of R2 RCA Under On-Site Asphalt Areas. Approximately 9,200 Square Feet

** **RCA Under Off-Site Asphalt Areas Excluded**

** **Fine Grading of RCA And All Asphalt Work To Be Performed By Others**

RCA Under Asphalt Total: $ 10,900.00

G. MELOMO EXCAVATING, INC.
25 Carlough Road, Unit 2, Bohemia, NY 11716

Payment Terms

To Be Mutually Agreed Upon Based On Schedule of Value And Subcontractor Agreement

Notes

* The above pricing is valid for 30 days from the stated bid date.
* Any changes requested following acceptance of this proposal is subject to a formally agreed upon change order prior to any changes made.
* Proposal based on drawings by Bar Architecture, P.C. Dated 1-29-2025 And H2M Architects + Engineers Dated April 2025
* No Geotechnical Report Provided
* Adequate access for equipment must be established prior to start of work.

Exclusions

* Gravel, Imported Fill/Topsoil, Building Demolition, Underslab Plumbing/Electrical Excavation, Curb Excavation
* Excavation or Removal of contaminated soil or debris mixed with soil and/or asphalt/concrete
* Private markouts, restoration of walkways, curbs, asphalt, buried electric, sprinkler or other unmarked utilities, all fencing, barricading.
* Restoration of walkways, curbs, asphalt, all fencing, barricading, buried electric, sprinkler or other unmarked utilities,
* Cutting, capping or relocation of utilities
* Interior Demolition or Penetrations (lie. make openings) to existing building
* Excavation and backfill for proposed concrete, asphalt, masonary or wood curbing, etc. except as noted above
* Excavation and backfill for other trades except as noted above
* Sheeting, shoring, bracing, underpinning or excavation for underpinning except as noted.
* Soil testing or inspection fee of any kind
* Excavation or removal of surface or buried debris, unknown structures or obstructions
* Extra depth excavation below bottom of footing or subgrades on plan
* Pumping or dewatering of groundwater or surface water except as noted
* Layout, Survey, Stakeout or As-Builts
* Street Cleaning
* Dust Control
* Site protection, vibration/air monitoring
* Frost excavation, snow removal or circumstances related to weather conditions
* Night or weekend working hours
* Anything else not specifically included in the above stated scope of work is not included

Company Proposal

G, Melomo Excavating, Inc. propose the above scope of work, to be completed by the agreed upon Completion Date for the total amount stated above.

6/6/2025

Submitted by (Company Representative) **Date**

Owner Acceptance

I hereby accept the above scope of work, proposed to be completed by the agreed upond Completion Date with Melomo Excavating for the above stated total amount.

Submitted by (Authorized Representative) **Date**