Virtuoso
1911 Broadway
Brooklyn, NY, 11207
(347) 235-5246

03/06/2025

Estimate: 25002201

Stephen Powers
J.T. Magen & Company Inc.

Re: Major League Soccer Rev. 1

Virtuosohereby proposes all materials, labor and supervision in accordance with drawings dated 10/18/2024 for the sum of **$3,582,193**

Estimate Table

Description	Total Estimate
06.2300 Closet Interiors	16,935
09.2300 Drywall & Carpentry	2,127,701
09.2500 Acoustical Ceilings	966,771
09.9100 Painting	470,785
Totals	**$3,582,193**

Virtuoso
1911 Broadway
Brooklyn, NY, 11207
(347) 235-5246

Estimate Description: Major League Soccer Rev. 1

Scope of Work

Estimate Table

Description
06.2300 Closet Interiors
F/I Closet Interiors (Hat Shelf & Rod)
09.2300 Drywall & Carpentry
F/I 3-5/8" Metal Stud Framing @ PT-6B
F/I Blanket Insulation @ PT-6B
F/I Two (2) Layers of 5/8" GWB Walls on Each Side @ PT-6B
F/I 3-5/8" Metal Stud Framing @ PT-3B
F/I 5/8" GWB Walls @ PT-3B
F/I 3-5/8" Metal Stud Framing @ PT-8F
F/I 5/8" GWB Walls @ PT-8F
F/I 3-5/8" Metal Framed Soffit(s) Above Storefront(s)
F/I 5/8" GWB Soffit(s) Above Storefront(s)
F/I 2-1/2" Metal Stud Framing @ PT-8G
F/I 5/8" GWB Walls @ PT-8G
I/O Fire Extinguisher Cabinet
F/I 3-5/8" Metal Stud Framing @ PT-8K
F/I Blanket Insulation @ PT-8K
F/I Two (2) Layers of 5/8" GWB Walls @ PT-8K
F/I 3-5/8" Metal Stud Framing @ PT-9G
F/I Blanket Insulation @ PT-9G
F/I Two (2) Layers of 5/8" Gold Bond XP on West Side + Two (2) Layers of 5/8" GWB Walls on Dry Side @ PT-9G
F/I C-H Metal Stud Framing @ PT-13A
F/I One (1) Layer of 1" Fire Shield Shaft Liner on One Side + Two (2) Layers of 5/8" Type X GWB on Other Side
F/I 3-5/8" Metal Stud Framing @ PT-10D
F/I Blanket Insulation @ PT-10D
F/I 5/8" Gypsum Firecode "C" Type GWB Walls @ PT-10D
F/I 3-5/8" Metal Stud Framing @ PT-9B
F/I Blanket Insulation @ PT-9B
F/I 5/8" Gold Bond XP on West Side + 5/8" GWB Walls on Dry Side @ PT-9B
F/I 3-5/8" Metal Stud Framing @ PT-9J
F/I Blanket Insulation @ PT-9J
F/I Two (2) Layers of 5/8" Gold Bond XP
F/I 3-5/8" Metal Stud Framing @ PT-4A
F/I Blanket Insulation @ PT-4A

Virtuoso
1911 Broadway
Brooklyn, NY, 11207
(347) 235-5246

Description
F/I 5/8" GWB Walls @ PT-4A
F/I Wood Blocking
F/I 3-5/8" Metal Stud Framing @ PT-10K
F/I Blanket Insulation @ PT-10K
F/I TWo (2) Layers of 5/8" Gypsum Firecode "C" Type GWB Walls on Each Side @ PT-10K
F/I 3-5/8" Metal Stud Framing @ PT-8L
F/I 5/8" GWB Walls @ PT-8L
F/I 3-5/8" Metal Stud Framing w/Bracing @ 48" O.C. @ PT-1C
F/I 5/8" GWB Walls @ PT-1C
F/I 7/8" Hat Channel Furring @ PT-8C
F/I 5/8" GWB Walls @ PT-8C
F/I 2-1/2" Metal Stud Framing @ PT-3A
F/I 5/8" GWB Walls @ PT-3A
F/I Hung GWB Ceilings
F/I 2-1/2" Metal Stud Framing
F/I Blanket Insulation
F/I 5/8" GWB Soffit Fascia
I/O Interior HM Door, Frame & HW (Single)
I/O Interior HM Doors, Frame & HW (Pair)
I/O Interior Wood Door & HW
I/O Interior HM Door, EZY-Jamb & HW
I/O Interior Wood Door, Wood Frame & HW
I/O Interior Wood Door & HW (Single)
I/O Bath Accessories
F/I Wood Blocking
F/I CN02 Light Cove Above Interior Storefront
F/I 5/8" GWB Walls
F/I 3-5/8" Metal Stud Framing
F/I Blanket Insulation
F/I 5/8" Plywood Walls @ Back To Back TV Wall
09.2500 Acoustical Ceilings
ACT-1 Ceilings - Armstrong Optima Square Tegular 3259 On Interlude 9/16" Tee System 30"x30" White
ACT-3 Ceilings - Armstrong Ultima Health Zone Beveled Tegular On Interlude XL 9/16" Tee System, Shadow Molding At Wall, 24"x24" White
ACT-2 Ceilings - Armstrong Optima Tegular On Interlude 9/16" Tee System, Shadow Molding At Walls, 30"x60" White
F/I MM-1 Metal Mesh Ceiling - Banker Wire Mid-Fill Woven Wire Mesh Pattern, Product #M22-80, Powdercoat Finish, With Powdercoated Metal Trim
F/I TC-1 Surface Mounted Armstrong Ceiling Tiles - Tectum Direct Attach 1" Thick Custom Size, Beveled Edge, White

Virtuoso
1911 Broadway
Brooklyn, NY, 11207
(347) 235-5246

Description
F/I SPC-3 Suspended Stretched Ceiling , Newmat Acoustic Perf04, Finish Cambera S626, Concealed Knife Edge Frame, Suspension
F/I SPC-4 Suspended Acoustic Ceiling Tiles Woven Image, Fuji Juni, Fuji Roku, Colourways 420, Suspended Array Mount, White Finish
F/I SP-1 Suspended Mirror Ceiling - Flexmirror, The Mirror, Concealed Frame, Magnetic T-Grid Suspension
F/I SPC-2 Suspended Stretch Ceiling - Newmat Acoustic Perf04, Blanc Satin SX03, Concealed Knife Edge Frame, Suspension
09.9100 Painting
Paint GWB Walls
Paint GWB Soffit(s) Above Storefront(s)
CS-1 Acoustic Spray On Ceiling - International Cellulose Corporation K-13 Thermal Insulation 1" Thick, White
Paint GWB Ceilings
Wipe & Paint Exposed Ductwork
Paint Exposed Sprinkler Piping
Paint GWB Soffit Fascia
Paint HM Door & Frame (Single)
Paint HM Door & Frame (Pair)
Paint/Stain Wood Door
Paint/Stain Wood Door + Wood Frame
Paint/Stain Wood Door (Single)
Paint GWB Walls

Virtuoso
1911 Broadway
Brooklyn, NY, 11207
(347) 235-5246

Exclusions

1. Permits & Fees – No costs associated with permits, bonds, or fees.
2. Design & Engineering – No responsibility for design, engineering, or stamped drawings.
3. Structural Work – No structural modifications, reinforcement, or temporary shoring.
4. Unforeseen Conditions – No costs related to hidden or unforeseen conditions such as asbestos, lead, mold, or existing damage.
5. Existing Conditions – No repairs or patching outside the specified scope.
6. Furring for MEPs – No furring, soffits, or bulkheads required solely for mechanical, electrical, or plumbing.
7. Blocking & Backing – No wood or metal blocking unless explicitly noted in the drawings.
8. Firestopping & Insulation – Excludes fire caulking, insulation, or spray fireproofing.
9. Doors, Frames, & Hardware – Excludes furnishing and installing doors, frames, and hardware.
10. Glass & Glazing – No storefront, glazing, or glass partition work.
11. Millwork & Cabinetry – No installation of millwork, cabinets, or casework.
12. Acoustical Treatments – No acoustic panels or fabric-wrapped panels.
13. Surface Prep Beyond Spec – No patching, skim-coating, or extensive surface preparation beyond standard finish requirements.
14. Specialty Finishes – No epoxy, faux finishes, Venetian plaster, or high-performance coatings.
15. Painting of Exposed MEP – No painting of ductwork, conduit, or piping unless specifically required.
16. Exterior Painting – No painting of exterior surfaces, including façade work.
17. Touch-Ups After Trades – No rework or touch-ups due to damage by other trades

All materials guaranteed to be as specified, and above work to be performed in accordance with the drawings and specifications submitted for the above work, and completed in a substantial workmanlike manner.

Any alteration or deviation from above specifications involving extra costs will be executed only upon written order, and will become an extra charge over and above the proposal. All agreements contingent upon strikes, or delays beyond our control.

Total **$3,582,193**

By signing this document, the customer agrees to the services and conditions outlined by this document.

_____

Virtuoso