AMAXX Inc.
845.878.0001
TRUCKING • EXCAVATION • SITE DEVELOPMENT

Big Geyser, 22 Sutton Place, Brewster, NY

Prepared By

Amaxx Inc

124 State Route 22
Pawling, New York 12564

8458780001
amaxxincoffice@gmail.com

Prepared For

Montana Contracting

Joe Montana
173 US-9W
Congers, New York 10920

845-398-1778
ines@montanacontracting.com

9/5/2025

Scope of Work

PHASE 2

Site Prep.....$2,541.68

Demolition.....$58,578.81

Erosion Control.....$30,505.86

Storm Drainage.....$93,183.42

Excavation/Grading.....$366,667.96

Electric/Site lighting.....$45,763.95

Sanitary Sewer.....$8,374.94

Retaining Walls.....$253,022.90

Concrete Flatwork.....$165,112.89

Site Improvements.....$7,041.14

Parking Lot/Roadways.....$411,005.94

Site Restoration.....$6,045.07

TOTAL:$1,447,844.56

Proposal Total	**$1,447,844.55**

Terms of Service

EXCLUSIONS:

Permit/Bond fees

Engineering fees

Surveying/Layout

Rock hammering and/or removal

Topsoil import

Structural fill import

Existing utility alterations

Irrigation

Shoring/Piling

Unsuitable fill removal/replacement

Guiderails/handrails

Fencing, permanent

Dewatering

Material testing

Building openings

Hardscaping/Landscaping

PLEASE NOTE:

We utilize GPS for all layout, localization points from surveyor required

Proposal good for 60 days

Proposal based off Insite plans, last revised 6/23/25

Line Item Detail

Name	Qty	Unit
02 EX-1		
DEMO-curb removal/disposal, concrete	1,604.00	Ln Ft
DEMO-fence removal/disposal, chain-link	1,012.00	Ln Ft
DEMO-MEP service removal	180.00	Ln Ft
DEMO-sanitary force main removal	230.00	Ln Ft
DEMO-tree/stump removal	3.00	EA
SP-topsoil strip/ stockpile	185.00	Cu Yd
03 SP-1.1		
AS-asphalt,2"	68,661.00	Sq Ft
AS-Item 4, 8" compacted	1,695.00	Cu Yd
CF-loading dock pads/ramp, 6"	89.00	Cu Yd
CF-sidewalks, concrete	18.00	Cu Yd
SI-bollards	2.00	EA
SI-signage	10.00	EA
SR-topsoil spread, 4"	161.00	Cu Yd
03_Big Geyser_Architectural Drawings_2025-06-20.pdf Page 008		
DEMO-asphalt removal/disposal	209.00	Cu Yd
DEMO-concrete slab removal/disposal	113.00	Cu Yd
DEMO-overburden removal/disposal	2,624.00	Cu Yd
DEMO-tennis court clay removal/disposal	294.00	Cu Yd
EX-underslab prep, 8"	1,418.00	Cu Yd
05 SP-2		
CF-curbing, concrete	1,518.00	Ln Ft
EL-elec. service relocation	220.00	Ln Ft
EX-mass cut	6,574.00	Cu Yd
EX-mass fill	1,080.00	Cu Yd
EX-overburden removal/disposal	6,588.00	Cu Yd
RW-retaining walls, CIP	221.00	Cu Yd
SD-15" FES	2.00	EA
SD-15"HDPE	334.00	Ln Ft
SD-15"HDPE	132.00	Ln Ft
SD-24" FES	1.00	EA
SD-catch basin, precast	4.00	EA
SD-existing basin regrade, BA2	1.00	EA
SD-existing structure tap	3.00	EA
SD-trench drain, precast	59.00	Ln Ft
SS-force main relocation	209.00	Ln Ft
UT-gas line relocation	220.00	Ln Ft
06 SP-3		
EC-concrete wash-out	2.00	EA
EC-inlet protection	5.00	EA
EC-silt fence, installation and maintenance	669.00	Ln Ft
EC-stabilized construction entrance	116.00	Cu Yd
07 LP-1		
EL-electrical trenching, site lighting	694.00	Ln Ft
EL-light pole bases, precast concrete	6.00	EA
11 D-1		
AS-asphalt striping	1.00	EA