Big Geyser, 22 Sutton Place, Brewster, NY

Prepared By	Prepared For	10/23/2025
Amaxx Inc	Montana Contracting	
	Joe Montana	
124 State Route 22 Pawling, New York 12564	173 US-9W Congers, New York 10920	
8458780001	845-398-1778	
amaxxincoffice@gmail.com	ines@montanacontracting.com	

Scope of Work

PHASE 2

Site Prep.....$2,541.68

Demolition.....$58,578.81

Erosion Control.....$30,505.86

Storm Drainage.....$114,288.42

Excavation/Grading.....$3404,865.40

Electric/Site lighting.....$45,763.95

Sanitary Sewer.....$8,374.94

Retaining Walls.....$253,022.90

Concrete Flatwork.....$165,112.89

Site Improvements.....$7,041.14

Parking Lot/Roadways.....$489,235.94

Site Restoration.....$6,045.07

TOTAL:$1,585,377.00

Proposal Total	$1,585,376.97

Terms of Service

EXCLUSIONS:

Permit/Bond fees

Engineering fees

Surveying/Layout

Topsoil import

Existing utility alterations

Irrigation

Shoring/Piling

Unsuitable fill removal/replacement

Guiderails/handrails

Rock hammering and/or removal

Structural fill import

Fencing, permanent

Dewatering

Material testing

Building openings

Hardscaping/Landscaping

PLEASE NOTE:

We utilize GPS for all layout, localization points from surveyor required

Proposal good for 60 days

Proposal based off Insite plans, last revised 10/14/25

Line Item Detail

Name	Qty	Unit
AS-asphalt,2.5/1.5		
AS-asphalt,2.5/1.5	35,096.00	Sq Ft
AS-asphalt, 4" binder, 2" top		
AS-asphalt, 4" binder, 2" top	33,303.00	Sq Ft
AS-asphalt striping		
AS-asphalt striping	1.00	EA
AS-Item 4, 8" compacted		
AS-Item 4, 8" compacted	1,695.00	Cu Yd
CF-curbing, concrete		
CF-curbing, concrete	1,518.00	Ln Ft
CF-loading dock pads/ramp, 6"		
CF-loading dock pads/ramp, 6"	89.00	Cu Yd
CF-sidewalks, concrete		
CF-sidewalks, concrete	18.00	Cu Yd
DEMO-asphalt removal/disposal		
DEMO-asphalt removal/disposal	209.00	Cu Yd
DEMO-concrete slab removal/disposal		
DEMO-concrete slab removal/disposal	113.00	Cu Yd
DEMO-curb removal/disposal, concrete		
DEMO-curb removal/disposal, concrete	1,604.00	Ln Ft
DEMO-fence removal/disposal, chain-link		
DEMO-fence removal/disposal, chain-link	1,012.00	Ln Ft
DEMO-MEP service removal		
DEMO-MEP service removal	180.00	Ln Ft
DEMO-sanitary force main removal		
DEMO-sanitary force main removal	230.00	Ln Ft
DEMO-tree/stump removal		
DEMO-tree/stump removal	3.00	EA
EC-concrete wash-out		
EC-concrete wash-out	2.00	EA
EC-inlet protection		
EC-inlet protection	5.00	EA
EC-silt fence, installation and maintenance		
EC-silt fence, installation and maintenance	669.00	Ln Ft
EC-stabilized construction entrance		
EC-stabilized construction entrance	116.00	Cu Yd
EL-elec. service relocation		
EL-elec. service relocation	220.00	Ln Ft
EL-electrical trenching, site lighting		
EL-electrical trenching, site lighting	694.00	Ln Ft
EL-light pole bases, precast concrete		
EL-light pole bases, precast concrete	6.00	EA
EX-mass cut		

EX-mass cut	6,574.00	Cu Yd
EX-mass fill		
EX-mass fill	1,080.00	Cu Yd
EX-overburden removal/disposal		
EX-overburden removal/disposal	7,999.00	Cu Yd
EX-underslab prep, 8"		
EX-underslab prep, 8"	1,418.00	Cu Yd
RW-retaining walls, CIP		
RW-retaining walls, CIP	221.00	Cu Yd
SD-15" FES		
SD-15" FES	3.00	EA
SD-15"HDPE		
SD-15"HDPE	334.00	Ln Ft
SD-15"HDPE		
SD-15"HDPE	244.00	Ln Ft
SD-24" FES		
SD-24" FES	1.00	EA
SD-catch basin, precast		
SD-catch basin, precast	5.00	EA
SD-existing basin regrade, BA1		
SD-existing basin regrade, BA1	11,626.00	Sq Ft
SD-existing basin regrade, BA2		
SD-existing basin regrade, BA2	1.00	EA
SD-existing structure tap		
SD-existing structure tap	3.00	EA
SD-trench drain, precast		
SD-trench drain, precast	59.00	Ln Ft
SI-bollards		
SI-bollards	2.00	EA
SI-signage		
SI-signage	10.00	EA
SP-topsoil strip/ stockpile		
SP-topsoil strip/ stockpile	185.00	Cu Yd
SR-topsoil spread, 4"		
SR-topsoil spread, 4"	161.00	Cu Yd
SS-force main relocation		
SS-force main relocation	209.00	Ln Ft
UT-gas line relocation		
UT-gas line relocation	220.00	Ln Ft