Quality Fence
1223 Lincoln Terrace Peekskill, NY 10566 | Tel: 914-737-8700
11 Deer Court Brewster, NY 10509 | Tel: 203-443-1300

We are grateful for your interest in our services and are pleased to offer the below estimate for Montana Contracting at the property located at 22 Sutton Pl Brewster

Job Description:

- ❏ Furnish & Install approx. 390LF of 4' High Black Chain Link Fence
- ❏ 2" End/Terminal Posts
- ❏ 1⅝" Line Posts
- ❏ 1 ⅜" Top Rail
- ❏ Tension Wire on Bottom
- ❏ (1) 4' Wide Gate

Total Job Cost …….……...…….…… .**$10,500**
Deposit …….…….…… ……... $3,500
Balance Due at Completion …….….. $7,000

Job Description:

- ❏ Furnish & Install approx. 390LF 4' High Aluminum Fence
- ❏ 2"x2" Black Posts Set in Concrete
- ❏ Heavy Duty Gate Posts set in Concrete
- ❏ (1) 4' Wide Gate
- ❏ No takeaway factored
- ❏ Limited Lifetime Manufacturer Warranty

Total Job Cost …….……...…….…… .**$19,750**
Deposit …….…….…… ……... $9,750
Balance Due at Completion …….….. $10,000

Continued on Next Page

Quality Fence

Job Description: **WOOD GUARD RAIL**

- ❑ Furnish & Install approx. 160LF 30” High Wood Guard Rail
- ❑ 6”x6” Pressure Treated Posts set in Concrete for added Strength
- ❑ (1) Horizontal 2”x12” Pressure Treated Board Bolted to Posts
- ❑ 8’ Spacing on Posts

Total Job Cost …….……...…….…… .**$6,350**
Deposit …….…….…… ……... $2,350
Balance Due at Completion …….….. $4,000