ALL PHASE ELECTRIC ENTERPRISES, INC.

Licensed & Insured Electrical Contractor
License # E-393
NJ License #34EI01391800

75A Lake Road, Suite 179
Congers, New York 10920
845-267-2339 Phone
845-267-2338 Fax

Sparks Car Wash Newburgh

Approx Start Date **Approx Finish Date / /**

Job Location: 1229 NY-300, Newburgh

November 21st, 2025

Montana Contracting
173 RT. 9W
Congers, NY, 10920

Attn: Ines MacAdam
Phone:
Email: ines@montanacontracting.com

We Hereby submit specifications and price for work being performed along with labor and material to complete the job as follows:Plans/Specs Dated: GKA Architects 10/24/25 E-0.1, E-1.1, E-1.2, E-1.3, E-2.1,

Scope of Work:

1. Furnish and Install Temp Power and Lighting. Connection from either Temp Generator or Utility Feed included. Utility Fees for Temp Power and/or Temp Generator not included. Temp Generator available for rent if needed.
2. Install only all Interior Lighting as per plans.
3. Furnish and Install Time Controller and Contactor Panel for Lighting
4. Install only all Site Lighting. No Trenching or Concrete Bases included for Pole Fixtures.
5. Furnish and Install all Receptacles including Duplex, Quad, GFI, WP, and Dedicated.
6. Furnish and Install Power and Connections for Mechanical Equipment including EF, CU, HP, UH, and CWH. No LV or Control Wiring Included.
7. Furnish and Install (2) Data Ports in IT Room. Rack and Network by Others
8. Furnish and Install Cat 6 Wire for Wifi Access Point. 20’ Slack to be left in the IT Room.
9. Furnish and Install Power and Connections for Signage. Final Connection by Sign Contractor.
10. Furnish and Install Conduit and Pull String for all Cameras and Speakers for E 1.3 Plan.
11. Furnish and Install New Incoming 480/277V Service from Utility Provided Transformer per One Line. Price based on Aluminum Feeders. Trenching by Others
12. Furnish and Install Panel H, Panel LA, 45 KVA XFMR, and 75 KA Transformer and all Branch Circuits.
13. Install only Motor Control Center. MCC Panel to be provided by Others.

14. Furnish and Install Power and Connections for all Branch Circuits for MCC.
15. Install Only Vacuum Controller Panels.
16. Furnish and Install Wire Way and Vacuum Motor Disconnects.
17. Furnish and Install Power and Connections for (19) Vacuums. This includes Conduit and Wire. Trenching by Others. Control Wiring not included.

Total: $232,250.00

Add Alternates:

Primary Service:

1. Furnish and Install approx 250' #2 Okenite 15KV Primary Wire and 4" Conduit from proposed utility pole to proposed transformer location.

Total: $24,000.00

Interior Lighting Budget $13,500.00
Exterior Lighting Budget: $17,700.00

Fire Alarm:

1. Furnish and Install Fully Programmable Fire Alarm System that complies to plans/specs. Installation is subject to Local Code and Fire Marshall/Inspector Approval. Includes Panels, Devices, Horn Strobes, Smokes, Pull Stations, Annunciators, etc. Programming Included in Price.
2. Fire Alarm Monitoring available at a monthly cost to be discussed with Ownership at a later date.

Total: $14,000.00

Qualifications:

- ***All Work Performed During Normal Business Hours 7:30am to 3:30pm***
- ***All Circuits are all AFCI/GFCI Protected per new NEC***
- ***Electrical Inspection Included; Fee by Others ($2,500.00 Budget)***
- ***No Utility Fees***
- ***All Panels Assumed Adequate and Available***

- ***No General Contracting Work***
- ***No Painting or Patching***
- ***Speaker Wiring Furnished by Others***
- ***No Rubbish Removal***
- ***No Rigging***
- ***Trenching by Others***
- ***Area to be Free of Asbestos***
- ***Gas by Others; By Licensed Local Plumber***
- ***No Core Drilling or Poke Through; Work Done on Straight Time***
- ***Bathroom Fans Furnished by Others***
- ***Venting by Others***
- ***No Roof Penetrations***
- ***Intercom/Security System/Building Access Not Included***
- ***No Building Permit or Filing Fees***
- ***No Data/Telephone Wiring***
- ***No Security Wiring***
- ***All Exterior Fixtures on Timers or Photo Cells***
- ***Wire Price Subject to Market Value***
- ***Not Responsible for Electric in Space During Construction and Demo; Owner to Secure Panels and Access***
- ***Exclude Start up and Testing of Switch Gear/Generators. Asco or Equal ATS Switches. Including Infra-Red Test and Load Bank Testing, Programming and Indoctrination or Systems with Building Management and Personnel***
- ***No Concrete Cutting or Patching***
- ***Core Drilling Furnished by Others***

- ***No VFD Drives (Mechanic Contractor to match the motor) Labor to wire and Install Included***
- ***Additional Cost for Startup of Gear is Not Included***
- ***No Low Voltage or Control Wiring***
- ***Assumed Adequate Space Available in Service Room for Service Equipment Specified on Drawings***
- ***Not Responsible for Existing Violations Unforeseen or Unexposed***
- ***Not Responsible for Delays with Utility Company. We will provide Transparency and all Contact Information within Utility Company but are not held liable for Delays***
- ***Not Responsible for Delays in any Custom orders includes; Panels, Switchgear, Generators, Lighting, etc…***
- ***Price is based on Non Prevailing Wages.***
- ***Not Responsible or Held Liable for any Failure or Delay in Performing any Obligation Under Contract That is Due to Any of the Following Causes; Acts of God, Terrorism, Epidemic, Pandemic (including the COVID-19 Pandemic), Quarantine, Natural Catastrophes or General Lack of Availability of Materials or Changes in Market Prices***
- ***All Phase Electric Reserves the Right to Adjust Quotations based on Unforeseen Changes in Leadtimes/Pricing until the Markets Stabilize. All Labor Quotations will Remain Valid for (30) Days***
- ***Price Good for (30) Days***

There will be a 1 year warranty on the workmanship to start when job is complete

Respectfully Submitted,

Paul White

Any alterations or deviation from above specifications involving extra costs will be executed only upon written order and will become an extra charge over and above estimate. All agreement convergent upon strikes, accidents, or delays beyond our control. All extra work Will be required 50% down prior to start. When extra is complete, balance paid upon completion of extra.

- Payment for all special non refundable material or equipment is required to place order.

Acceptance of Contract

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payments will be made as outlined above.

SIGNATURE_____ **Date of Acceptance**_____

SIGNATURE_____ **Date of Acceptance**_____