GEO GEOTHERMAL ENERGY OPTIONS

OIL-FREE ENERGY SOLUTIONS

Building Insulation Contract

Customer: North River Builders
Phone: 845-656-8515
Email: chris@northriverbuild.com

June 6, 2025

Job Address:	Billing Address:
To: New House 25 Stonewall Lane Mamaroneck, Ny 10543	To: 221 Smithtown Rd Wappingers Falls, Ny 12590

Item	Work Scope	R-Value		Total
Closed Cell	Approximately 6.5" of Closed Cell Foam in Attic Roof Rafters	R-	49	
Open Cell	Approximately 6.75" of Open Cell Foam in Garage Ceiling	R-	30	
Open Cell	Approximately 5" of Open Cell Foam in Exterior 2x6 Walls of the 1st & 2nd Levels	R-	22	
Open Cell	Approximately 5" of Open Cell Foam in 2x6 House Garage Dividing Wall	R-	22	
Open Cell	Approximately 5" of Open Cell Foam in Attic Gable End Walls	R-	22	
Open Cell	Approximately 5" of Open Cell Foam in Exterior 2x6 Garage Walls	R-	22	
Open Cell	Approximately 5" of Open Cell Foam in Perimeter Rim Joist of the 1st Floor, Basement, & Garage	R-	22	
Rockwool	R30 Rockwool in Basement Ceiling Held in Place With Insulation Supports	R-	30	
	Intumescent Fire Coating Applied to Closed Cell Foam in Attic			**Base Price**
	Foam Around Windows & Doors			**$ 40,160.00**
	Options			**Option Additional Cost**
Closed Cell	Approximately 4" of Closed Cell Foam in Garage Ceiling	R-	30	**$ 1,133.00**
Closed Cell	Approximately 3" of Closed Cell Foam in Exterior 2x6 Walls of the 1st & 2nd Levels	R-	22	**$ 3,450.00**
Closed Cell	Approximately 3" of Closed Cell Foam in 2x6 House Garage Dividing Wall	R-	22	**$ 525.00**
Closed Cell	Approximately 3" of Closed Cell Foam in Attic Gable End Walls	R-	22	**$ 420.00**
Closed Cell	Approximately 3" of Closed Cell Foam in Exterior 2x6 Garage Walls	R-	22	**$ 652.00**
Closed Cell	Approximately 3" of Closed Cell Foam in Perimeter Rim Joist of the 1st Floor, Basement, & Garage	R-	22	**$ 675.00**

REQUIREMENT TO SCHEDULE JOB:

1) SIGNED CONTRACT
2) 50% DEPOSIT:
BALANCE DUE UPON COMPLETION

All prices good for 15 days

Terms of Service:

1) Charges include all materials and labor for the installation and completion of insulation project listed above. Geothermal Energy Options is not responsible for building materials, tools, or personal items left in or near where work is to be performed.
2) Any changes or additions must be in writing, not oral, and be signed by all parties in contract.
3) Proper respiratory equipment is required in the work spray zone(s). As such, only Geothermal Energy Options employees are allowed in the work are during spray operations due to dust and off-gassing. It is recommended the work area and areas sharing the same air space remain unoccupied for a minimum of 24 hours.
4) Any additional services and/or work not specifically mentioned in this contract will be subject to a different agreement. All costs associated with the collection of this proposal including attorney fees but not limited to, after work has been completed are the responsibility of the customer signing this agreement. If not paid, a 2% charge per month will be added for non-payment and all legal and collection fees to collect this debt will be reimbursed t to Geothermal Energy Options by the customer signing this agreement.
5) While the material is guaranteed to perform to published specifications, Geothermal Energy Options does not promise that the performance, in a particular situation, will meet customer's expectations.
6) All refunds are subject to a $250 administration fee.

ACCEPTANCE: I have read, understand and agree to the work scope and attached TERMS OF SERVICE.

Homeowner/Builder _____ Date _____ Steve Nassani (845) 705-8952 _____ Date _____

Geothermal Energy Options, LLC Foam Division