IRON FELLAS
STEEL FABRICATORS

Ms. Ines MacAdam
Montana Contracting
173 US-9W,
Congers, NY 10920, USA

Re: 25 Stonewall Lane, Mamaroneck, New York 10543
I-F Est No #25-048

Ms. MacAdam:

We propose to provide the necessary labor to **FABRICATE AND INSTALL** the **MISC. METALS** in accordance with the dated **04/15/2025 DOB SUBMISSION** prepared by **DAY STOKOSA Engineering**

ITEM No.	SCOPE OF WORK / DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL
1	Furnish and Install, Steel beams and columns, - W12x35 beam, 2ea - HSS4x4x1/2 column, 7ea Referred from A-7, Shop Primed	LBS	3,100		
2	Fabricate and Install, Window well misc. steel items, - 3 sided railing, 36" H - ladder Referred from A-2, Painted Black	Location	3		
3	Fabricate and install, steel railing @North elevation entrance, 2side Referred from A-5, Painted Black	EA	1		
4	Fabricate and install, steel railing @East elevation entrance, 2side Referred from A-6, Painted Black	EA	1		
5	Cable railing @South elevation on 2 location Referred from A-6, Painted Black	LF	85		

TOTAL: $ 58,650

The following items are not included in our price:

- PE Calcs and Engineering
- Chopping and patching of concrete or masonry
- Shoring and false work,
- Testing and inspection or filing fees
- Demolition and removal, except for beams being reconnected
- Overtime, other than for deliveries, if required
- Cribbing or false work for crane

- Shoring, jacking dry packing
- Exposing and cleaning existing steel
- Architectural metals such as aluminum, stainless steel (except railings), bronze, etc.
- Any cladding for structural steel, stair stringers or miscellaneous steel trim
- Grounds for wall handrails
- Light gage framing
- Performance bond
- Electric power and hook-up and disconnect fees
- Special paint
- Surveys
- Setting of bearing plates, anchor bolts and leveling plates
- Sales tax, tax exempt
- Overtime, other than for deliveries, if required.
- Allowances

QUALIFICATIONS

All obstructions to the erection of miscellaneous iron must be removed or relocated prior to the installation of the work. Access to the work for men and materials must be guaranteed. Adequate and unobstructed access into, through and around the site must be provided and maintained at all times.

If the work is located in an open shaft or outside the building GC has to provide scaffolding or work platform to stage and erect steel.

All work to be done during regular working hours, unless specifically stated otherwise in this proposal.

All steel required to be painted will receive one shop coat of standard paint. No special finishes are included. The AISC has long discouraged the use of primers where the structural steel is to be in contact with concrete or fireproofing, therefore no paint is required for the structural steel on this project, nor is the cost of it included in our proposal.

All beam splices, if required, will be field bolted.

Shop drawings will be prepared for your approval before any work commences.

We shall be given use of the material hoist during regular time at no charge to Iron Fellas, Inc.

General contractor to provide necessary benchmarks and lines as required.

Any material supplied by us which are built into concrete or masonry will be delivered F.O.B. trucks at the jobsite, for the unloading, distribution and erection by others.

This price remains in effect for thirty (30) days, after which the price becomes subject to all applicable material and labor increases.

Terms of Payment:
Twenty-five percent [25%] deposit, progress payments, and full balance due upon completion.

Very truly yours,
Iron Fellas, Inc.

Oguzhan (Ozzy) Orhan
Co-Founder

Accepted by:

for ……..
By: _____

Title:_____
Date:_____