ESTIMATE

Service Address	Prepared For
5 Heidi Ln Gardiner, NY 12525	Montana Contracting 173 N Route 9W Congers, NY 10920 +(845) 398-1778 x18

SUQUI L HOME IMPROVEMENT INC

CIRCLEVILLE, NY 10919
Phone: (845) 270-9131
Email: suquihomeimprovements@gmail.com

Estimate #	166
Date	04/29/2025
Expiration Date	05/30/2025
PO #	5 Heidi Ln Framing
Business / Tax #	84-2898034

Description	Total
Scope of Work – Framing (Labor Only)	$105,000.00

We propose to provide labor-only rough framing services for the construction of a new residential home in accordance with the approved architectural and structural plans. The work to be performed includes, but is not limited to, the following:

Framing Preparation:
Installation of pressure-treated (PT) sill plates wherever wood is in contact with concrete or masonry, as specified in the construction drawings.

Floor Framing:
Complete framing of the first and second floor systems including joists, girders, beams, and all necessary blocking as indicated in the plans.
Installation of subfloor sheathing on all floors per specifications.

Wall Framing:
Framing of all exterior and interior walls including all partitions.
Installation of all headers, blocking, and bracing as required by code and drawings.
Proper framing for all door and window openings.

Roof Framing:
Construction of the entire roof framing system including installation of rafters, ridges, hips, valleys, LVLs, PSLs, and any engineered lumber or structural elements specified in the plans.
Installation of roof sheathing as per drawings.

Stair Openings:
Framing of stairwell openings on all applicable floors as shown in the plans.

Deck/Porch Framing (3 Total):

Rough framing of 3 exterior decks/porches per the construction documents.
Note: Installation of composite decking boards, railings, or any finish decking material is not included in this scope.

Sheathing:
Installation of all exterior wall sheathing in accordance with project plans.

Window and Exterior Door Installation:
Installation of all windows and exterior. (doors & windows provided by others)
We will properly flash and seal all window and door openings using tape, wrap, and sealants as shown in the drawings and per manufacturer instructions.

*Added 5/19/2025 : Framing of Basement Walls – Full framing of interior basement walls was not included in our initial proposal.
Special Foundation Tie-Downs – Additional structural tie-downs required throughout the foundation.
Installation of 1x4" Furring Strips(monopoly framing) – Horizontal and vertical furring strips to be framed by our crew across specified areas.

Exclusions:
Material supply (labor only).
Installation of decking boards or railings.
Interior finish carpentry or trim.
Insulation, mechanical, electrical, or plumbing work.
Any work not explicitly mentioned above.
We are not responsible for material take-off or procurement; all framing materials must be provided by others

---

Contractor Responsabilities $0.00

**Contractor shall provide qualified workers to fulfill the scope of the work with high level of craftsmanship.
**Work to be coordinated to maintain 1 point of egress into existing home at all times.
**Contractor shall do their best to protect landscaping, plants, flowers and trees.
**Keep site tidy and clean up trash, sawdust and debris daily. Use magnets and clean up stainless steel nails, screws and flashing scraps around home.
**Maintain access for other trades people to the addition that is currently under interior construction.
**Any un-used material to be organized neatly at location selected by client at the end of the project.
**Final clean-up at completion of job.

*******Professional Services Provided by Contractor(Suqui L Home Improvement Inc):
§ 4.9.1 The Contractor shall not be required to provide professional services that constitute the practice of
architecture or engineering unless such services are specifically required by the Architect Documents or unless the
Contractor is required to provide such services in order to carry out the Contractor responsibilities for its own
construction means, methods, techniques, sequences, and procedures. The Contractor shall not be required to

provide professional services in violation of applicable law.
**The Client shall not give instructions or orders directly to the Contractor's employees unless such persons are designated as authorized representatives of Suqui L Home Improvement Inc.

Extras and Change Orders $0.00

*Any changes, modifications, or additions to the original scope of work must be documented through a written/Email no verbal Change Order.
Suqui L Home Improvement Inc shall not be required to perform any additional work outside of the agreed-upon scope without a signed Change Order that clearly outlines the additional work to be performed, the time required, and the cost associated with the changes.
Before any additional work begins, the Contractor and the Owner/General Contractor must agree in writing on the price and any adjustments to the project timeline resulting from the change.
Suqui L Home Improvement Inc shall not be responsible for any delays, costs, or damages arising from changes to the project scope that are not agreed to in writing.
Failure to reach an agreement on the terms of a Change Order shall relieve Suqui L Home Improvement Inc of any obligation to perform the additional work, and the Contractor shall not be held liable for any consequences arising from the refusal to perform such work.

Payments $0.00

All payments must be made in full within 10 calendar days of each milestone completion to avoid delays in scheduling the next phase of work.
This payment schedule is based on agreed target dates and assumes no unforeseen delays outside of the contractor’s control (weather events, material delays, etc.).
Any requested changes to the scope of work (change orders) may result in adjusted pricing and scheduling.

Remedies for Nonpayment:
If the Client does not pay the Contractor (Suqui L Home Improvement Inc) through no fault of the Contractor, within seven days from the time payment should be made as provided in this Agreement, the Contractor may, without prejudice to any other
available remedies, upon seven additional days’ notice to the Client, stop the Work of this Contractor until
payment of the amount owing has been received. The Contract Sum shall, by appropriate Modification, be
increased by the amount of the Contractor’s reasonable costs of demobilization, delay, and remobilization.

Subtotal	$105,000.00
Total	**$105,000.00**

For valuable consideration, the parties agree as follows
No modifications of this contract will be effective unless it is in writing and is signed by both parties.
this contract binds and benefits both parties.
Time is the essence of this contract.
this contract is governed by the laws of the State of NEW YORK.
By signing this document, the customer agrees to the services and conditions outlined in this document.

Luis Suqui	Montana Contracting