TRI-STATE COMMERCIAL ROOFING CORP

143 Route 59 / Bldg 6C

Hillburn, NY 10931

PH: 845-362-1730 www.tristateroofing.com **Fax:845-356-2284**

Certified **Excellence in Roofing & Waterproofing** **Insured**

Montana Contracting **July 29, 2025**
173 Rte. 9W
Congers, NY 10920
Re: Angel Nyack - 18 S Broadway, Nyack, NY 10960

Tri-State Commercial Roofing Corp. hereby proposes to furnish all labor, materials, tools, equipment and services necessary for and incidental to the proper installation and completion of this project. This work will include all roofing scope associated with the new HVAC units being installed on the roof by others. As this is a tax-exempt project, no taxes have been included in our proposal.

SCOPE OF WORK

1. **Scrape away all embedded roof gravel around the entire perimeter of the area where the two new 12' equipment rails will be installed on the roof to hold the 5 new air conditioning condensers. After scraping, we will heat up the existing asphalt roofing with a torch to further clean and smooth the surface in order to proceed with the remainder of the scope and so that we can tie the new roofing into a smooth clean surface.**
2. **Cut open and remove all existing roofing materials and insulation down to the bare metal roof deck where the two new 12' equipment rails will be installed on the roof.**
3. **Install all required leveled, treated wood blocking where the new rails will sit.**
4. **Mount the new rails to the wood blocking. The rails will be supplied and located on the roof by others.**
5. **Flash the new rail curbs as per all manufacturer's specifications and tie all flashing work into the existing roof.**
6. **Install up to 3 pourable sealer pockets (pitch pockets) for the 5 new line sets and fill them with 1-part pourable sealer.**
7. **Remove all job-related debris from the premises.**
8. **All work not specified above is excluded from this proposal.**

Total Investment for this project is $11,380.00 (Eleven Thousand Three-Hundred Eighty Dollars)

All payments will be made per standard AIA contract terms and as per our submitted schedule of values.

Respectfully Submitted,

Stuart Roberts

Stuart Roberts, President